

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

- | | | |
|----|---|---------------------------|
| 1. | Date of receipt of applications for the tender
Form a/w requisite documents: - | 8.07.2022 upto 5.00 PM. |
| 2. | Date of issue /sale of tender forms against
Cash payment (Non-refundable):- | 11.07.2022 upto 4.00 PM. |
| 3. | Date of receipt of tenders: - | 12.07.2022 upto 10.30 AM. |
| 4. | Date of opening of tenders: - | 12.07.2022 at 11.00 AM. |

Sr.No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	A/R & M/O PWD Rest House & EE Office at Bangana Tehsil Bangana Distt. Una (HP). (SH:- P/F curtain etc).	99295	2000	Two months	350/-	Class-A to D
2	A/R & M/O on Jogipanga Balh Chaproh road km 0/0 to 8/00.(SH:- P/L hot applied Thermoplastic compound 2.5 mm & P/F dual directional reflective cat eyes (3M) on curves.).	99716	2000	Two months	350/-	Class-D
3	C/o link road to village Khairian from Baruhi Dumkhar road km 0/0 to 1/00. (SH:- C/O edge wall & V-shape drain from RD 0/0 to 0/062).	96550	2000	Two months	350/-	Class-D
4	C/o link road from Nari Devi Singh to Jhikla Kharol km.0/0 to 3/0(SH:- P/L WMM & MT in km. 0/636 to 0/954).	498182	10000	Two month	350	Class-D

The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

- The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).

2. The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

Executive Engineer
Bangana Division
HPPWD Bangana.

No.PW/BGN/CB/T-1/2022-23- 3571-99
Cop forwarded to the following for information and necessary action:-


dated 27/06/22

1. The Engineer-in-Chief HPPWD. Nirman Bhawan Shimla.
2. All the Chief Engineer in HPPWD.
3. The Superintending Engineer, 15th Circle, HPPWD., Una.
4. All the Assistant Engineer, working under this Division.
5. The B.D.O. Bangana
6. Accounts Branch.
7. Drawing Branch.
8. Various Contractors working under this Division
9. Notice Board.

Executive Engineer,
Bangana Division,
HPPWD Bangana.

Certificate

Certified that the tenders called vide this office letter No. PW/BGN/CB/T-1/2022-23-3571-99 dated 27.06.2022 is emergent nature and in public interest.


Executive Engineer,
HPPWD Division
Bangana.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O P.W.D. Rest House & E.E. office at Bangana Tehsil Bangana Distt. Una (H.P)							Estimated Cost: ` 99295.00
							Earnest Money: ` 2000.00
							Time Limit: Two month
Sr. No.	Description of work	No.or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.	
				Figures	Words		
1	Providing and Fixing Roller blind and zebra blinds curtains with all type of accessory with unit controler and roller blinds black out fabric & Zebra blinds curtains for door windows and ventilator including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.37	Per Square metre				
Total in Figures							


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on Jogipanga Balh Chaproh road Km 0/000 to 8/000 (SH: Providing and Laying hot Applied thermoplastic compound 2.5mm & P/F Dual Direction reflective Cat eyes (3M) on curves)					Estimated Cost Rs	
					Earnest Money Rs	2000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	Figures	RATE Words	AMOUN Rs. P
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.including carriage of material within all leads and lifts The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	116.40	Per Square metre			
2	Providing and fixing Dual Direction Reflective Cat Eye with Double Barrel Sanks of Impact resistant ABS PLASTIC STUD 100X90X16MM Ultea Voilet , resistant Yellow/ Red Colour havinf micro persmatic / Cube corner reflectors suitable for fixing with epoxy / Bitumen adseive make M-3 , including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	360.00	Each			
Total Rs.						


 Executive Engineer
 Bangana Division
 P.P.W.D. Bangana

SCHEDULE OF QUANTITY

Name of Work:- C/o link road to Village Khairian from Baruhi Dumkhar road Km 0/000 to 1/000 (SH: C/o Edge wall from Rd 0/000 to 0/062 & V-shape drain from Rd 0/000 to 0/062)

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and Words		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government	16.78	Per cubic metre			
2	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.34	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and technical specification clause 800, & 1200 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimetres) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths and the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.60	Per cubic metre			

Estimated Cost: `96550.00

Earnest Money: ` 2000.00

Time Limit: Two month

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and Words		AMOUNT Rs.
				Figures	Words	
4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	61.00	Each			
Total in Figures						


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangan

SCHEDULE OF QUANTITY

Name of Work:- C/O link road from Nari Devi Singh to Jhikla Kharol Km 0/000 to 3/000 (SH: P/L WMM & M/T in Km 0/636 to 0/954)

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406. including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	80.14	Per Cubic metre			
2	Providing and applying primer coat with BITUMEN emulsion SS-1 on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer @ 0.70kg-1.00 kg (zero decimal seven zero kilogram to one decimal zero kilogram) per square metre using mechanical means as per M.O.R.D. technical specifications clause 502 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1018.40	Per Square metre			
3	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg.per sqm (Zero point two hundred seventy five kilogram) per square metre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification .clause 503 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1018.40	Per Square metre			
4	Providing laying and rolling of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre size aggregate at the rate of 0.27 cum(zero point two seven cubic metre)mixed with penetration grade bitumen binder VG-10 at the rate of 14.6 kg. per ten square metre and laying with paver finisher to required line grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant laying and rolling with a three wheel 80-100 (eighty to one hundred)KN static road roller capacity finished to required level and grade to be followed by seal coat of either type A or type B or type C mechanically as per . technical specifications clause No. 508 (Bitumen VG-10) as per the entire satisfaction and direction of Engineer – in- Charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1018.40	Per Square metre			

Estimated Cost: 499182.00
Earnest Money: 10000.00

Time Limit: Two month

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
5	Providing and laying seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN V G - 10 at the rate of 0.68 kg (zero point six eight kilogramme) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying mechanically of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1018.40	Per Square metre			
Total in Figures						


 Executive Engineer
 Bangana Division
 P.P.W.D. Bangana