

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Scaled items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated 13.7.2022 up to 10.30AM and the same will be opened on the same day at 11.30 AM in the presence of contractors /firms or their authorized representative . The application for purchase of tender forms will be received up to 2.00 PM on dated 12. 07.2022 and tender forms can be obtained from this office against cash payment (nonrefundable) on 12.7 2022 ( 5.00PM ) and no tender form shall be issued by the post . The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	C/ O Link Road from Main Road to Raina Basti via Lotus International Convent School Rakkar at Kaloha( SH:- C/o Cement Concrete pavement at Rd 0/0 to 0/080)	474240	10000	Three Month	350	6&8
2	C/o Ayurvedic Dispensary at landiyara Tehsil Dada Siba Distt Kangra (SH:- C/O R/wall for site Development )	432899	9000	Three Month	350	6&8
3	Construction of protection wall near the house of Sh Naveen Parbhakar S/O Sh Amar Chand & Other Village Nihari Ward No 4 in GP Pirsaluhi ( SH:- C/O Protection wall at Rd 0/018 to 0/052.40 (Deposit work)	299886	6000	Two Month	350	6&8

- 1) Certified that tender of above works are being called in Exigency of public interest ,

*[Signature]*  
Executive Engineer,  
Kotla Behar Division HPPWD.,  
Kotla Behar

NO.PWD/KB/CB/TENDER/ 2022-23

1463-70


DATED 25.6.2022

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2

*[Signature]*  
Kotla Behar Division HPPWD.,  
Kotla Behar

CERTIFICATE

Certified that tenders called vide this office Notice No  
FWD/KB/CB/Tender /2021-22 - 1463-1470 dated 25.6.2022 for 3 No. Job are hereby  
invited without press notice due to exigencies / emergency of work in the public interest

  
Executive Engineer,  
Kotla Behar Division HPPWD.,  
Kotla Behar



**SCHEDULE OF QUANTITY**

Name of work:- Construction of Protection wall near the house of Sh. Naveen Parbhakar S/o Sh. Amar Chand & other Vill. Nihari Ward No. 4 in GP Pirs (SH:- Const. of Protection wall at RD. 0/018 to 0/052.40) (Deposit work).

Sr. No.	Description of Item	Quantity	Rate in		Unit	An
			Figures	Words		
1	Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	22.62 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in all heights/depts, in or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depts and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete, as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	90.13 Cubic metre			Per Cubic metre	
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain reinforcement concrete abutments, wing wall return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specification clause 614, 709, 1204, 3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.00 Number			Each	
<b>TOTAL</b>						

Executive Engineer,  
Kodla Behar Division,  
BPPWD Kodla Behar.

# SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 474240  
Earnest Money :- Rs. 75000  
Time Limit :- Four Month.

Name of work:- Construction of link road from main road to Rana Basti via Lotus International Convent School Rakkar at Kaloha (SH: C/o Cement Concrete Pavement at RD. 0 to 0/080).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiselling, wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of slumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling, ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	64.00 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.00 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical Specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	64.00 Cubic metre			Per Cubic metre	
TOTAL						

Executive Engineer,  
Kotla Behar Division,  
DPPWD Kotla Behar.




# SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 4328  
 Earnest Money :-Rs. 9,00  
 Time Limit :- Three Month.

Name of work:- Construction of Ayurvedic Dispensary at Landiara Teh. Dadasiba Distt. Kangra (HP) (SH:- Const. of Retaining wall for site development).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	30.50 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in all heights/depths, in or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete, as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	89.50 Cubic metre			Per Cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and M.O.R.D. technical specification clause 1203 and 1604 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	31.50 Cubic metre			Per Cubic metre	

Sr. No.	Description of Item	Quantity	Rate in		Unit	Am
			Figures	Words		
4	Providing and laying 100mm (One Hundred millimeter) dia PVC pipe Weep Holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of 1V:20H ( One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification clause 709, 1206.6 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.00 Number			Each	
5	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302,304 , 1603 Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	583.20 Cubic metre			Per Cubic metre	
TOTAL						

  
 Executive Engineer,  
 Kotla Behar Division,  
 MPPWD Kotla Behar.