

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

***** Notice Inviting Tender *****

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **04.07.2022** up to **11:00 A.M.** And the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **02.07.2022** up to **4:00 P.M.** and the application for issue of tender form shall be received on **01.07.2022** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of link road from Sakrehar to Dharamgiri road Km 0/000 to 1/800 in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement).	499968/-	10000/-	Three months
2	Construction of link road Danoa Kharat Khas via Dard in Distt Kangra (HP) (SH:-Construction of 900mm dia RCC pipe culvert along with wing wall at RD 1/600 to 1/650).	499195/-	10000/-	Three months
3	Construction of link road Thana Bargran to Busal in Distt Kangra (HP) (SH:-Construction of edge wall at RD 3/800 to 3/896).	499947/-	10000/-	Three months
4	Construction of link road to Thamba Basti in G.P. Sadoon Bargran in Distt Kangra (HP) (SH:- Providing and laying cement concrete pavement road in KM 0/050 to 0/221).	498920/-	10000/-	Three months
5	Link road from Hanuman Mandir to Sh Satosh Saini House in G.P. Rin Km 0/000 to 0/200 in Distt Kangra (HP) (SH:-Providing and laying G-II and Cement concrete pavement road between Km 0/000 to 0/115) Deposit work	338160/-	6800/-	Three months
6	Construction of Kahanphatt Toru road in Distt Kangra (HP) (SH:-Construction of retaining wall at RD 0/120 to 0/144)	499956/-	10000/-	Three months
7	Construction of link road Thana Bargran to Busal in Distt Kangra (HP) (SH:-Construction of road side drain at RD 3/600 to 3/877).	499010/-	10000/-	Three months

1. The contractor/firm should be registered as or dealer GST No. or EPF No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserve s the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/Tender/2022/ **3785- 3815**

Dated/ **18-06-2022**

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla
5. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
6. The Principal, Dr. RPGMC, Tanda.
7. The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the departmental website.
8. The Deputy Commissioner, Kangra at Dharamshala.
9. All the S.E.s/E.E.s under North Zone.
10. The Sub-Divisional Officer (C) Nagrota Bagwan.
11. The Block Development Office Nagrota Bagwan
12. All the Assistant Engineer under this Division.
13. The Drawing /Accounts Branch in this office.
14. The Contractors concerned.
15. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 499968.00
 EARNEST MONEY :- Rs. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of link road from Sakrehar to Dharamgiri road Km 0/000 to 1/800 in Distt. Kangra (H.P.)

SUB-HEAD :- Providing and laying cement concrete pavement.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering .Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	14.88 Cubic metres			Per cubic metre	
2	Providing and laying concrete for plain reinforcement concrete in open foundation including the cost of centering and shuttering complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 with 1:1½:3 (One Cement: One and half coarse sand : Three graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and as directed by the Engineer-Incharge including carriage of materials within all leads and lifts and other incidentals.	70.41 Cubic meters			Per cubic metre	
TOTAL: -						

Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 499195.00
EARNEST MONEY :- ₹ 10000.00
TIME LIMIT :- THREE MONTHS

NAME OF WORK :- Construction of link road Danoa to Kharat Khas via Dard in Distt. Kangra (H.P.).

SUB-HEAD :- Construction of 900mm dia RCC Hume Pipe culvert alongwith wing walls at RD's 1/600 to 1/650

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including entire carriage of materials within all leads, lifts and other incidentals.	96.95 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (One Cement : Three coarse sand): Six graded stone aggregate 40 mm (Forty millimetre) nominal size) complete etc as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	27.33 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	59.85 Cubic metres			Per cubic metre	
4	Providing and laying non-pressure NP2 class Reinforced Cement Concrete hume pipes 900mm (Nine hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	10.00 Running metre			Per running metre	
5	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as per drawing and HP.PWD technical specifications, and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	16 Numbers			Each	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	21.28 Cubic metres			Per cubic metre	
7	Filling with available fly ash and earth (Excluding rock) trenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer -in-charge, including compacting each layer by rolling/ ramming and watering, all complete as per drawing including entire carriage of materials within all leads and lifts and other incidentals.	8.30 Cubic metres			Per cubic metre	
TOTAL :-						


Executive Engineer,
H.P.P.W.D., Division,
Tarda at Nagfota Bagwan.

Schedule of Quantity

ESTIMATED COST: - Rs. 499947.00
 EARNEST MONEY : - Rs. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK : - Construction of link road Thana Bargran to Busal in Distt. Kangra (H.P.).
 SUB HEAD : - Construction of Edge wall at RD 3/800 to 3/896

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	51.84 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	97.20 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	52.00 Running metres			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	41.25 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- Rs. 498920.00
 EARNEST MONEY :- Rs. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of link road to Thamba Basti in G.P. Sadoon Bargran in Distt. Kangra (H.P.).
 SUB HEAD :- Providing and laying cement concrete pavement road in Km 0/050 to 0/221

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidentals.	35.67 Cubic metres			Per Cubic metres	7
2	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 40mm (Forty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	71.35 Cubic meters			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - Rs. 338160.00
 EARNEST MONEY :- Rs. 6800.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Link road from Hanuman Mandir to Sh. Satosh Sainin House in G.P, Rin Km 0/00 to 0/200 in Distt. Kangra (H.P.).
 SUB HEAD :- Providing and laying G-II and cement concrete pavement road between Km 0/0000 to 0/115 (Deposited)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidental.	12.28 Cubic metres			Per Cubic metres	7
2	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 40mm (Forty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-Incharge including carriage of materials within all leads and lifts and other incidentals.	52.61 Cubic meters			Per cubic metre	
TOTAL :-						

Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- Rs. 499956.00
 EARNEST MONEY :- Rs. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Kahanphatt Toru road in Distt. Kangra (H.P.).
 SUB HEAD :- Construction of Retaining wall at RD 0/120 to 0/144
 Description of items

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
		3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	18.15 Cubic meters			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	101.82 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	19 Numbers			Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	14.08 Cubic metres			Per cubic metre	
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	22.40 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- Rs. 499010.00
 EARNEST MONEY :- Rs. 10000.00
 TIME LIMIT : THREE MONTHS

ME OF WORK :- Construction of link road Thana Bargran to Busal in Distt. Kangra (H.P.).

DESCRIPTION OF ROAD SIDE DRAIN AT RD 3/600 TO 3/877

DESCRIPTION OF ITEMS

Sl. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within a any lead as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	149.58 Cubic meters	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering .Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	87.26 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.