

Himachal Pradesh
Public works Department

No:-PW/EE/MDK//TA/Tenders/2022:- 2561-64

Dated: - 14.07.2022

To

✓ The Director,
Information and Public Relation,
H.P.Shimla-171002.

Subject: -

Publishing of Advertisement.

Dear Sir,

Kindly get the enclosed press notice inviting tender to be published in One Hindi and One English leading News paper and Giri Raj as per date shown Tender Notice (NIT) under intimation to this office please.

Encl:-Press Notice.

✓
Executive Engineer,
Mechanical Division,
HP.PWD. Kullu.

Copy forwarded to the Superintending Engineer, Mechanical Circle. HP. PWD. Dharamshala for information please.
Copy to the Drawing Branch in this office along with Press Notice for information.

Copy to the Notice board.

Encl:-Press Notice

✓
Executive Engineer,
Mechanical Division,
HP.PWD. Kullu.



Office of
EXECUTIVE ENGINEER (MECHANICAL DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101
PHONE/FAX: 01902-222052, E.mail.eems-kul-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rates tenders on form No. 6 & 8 are hereby invited by the **Executive Engineer Mechanical Division HPPWD Kullu** on behalf of Governor of H.P. for the following works from PWD registered contractors. The tenders should reach this office on or before **21-7-2022** up to 11:00 AM and shall be opened on the same day at 11:30 AM in the presence of tenderers or their authorized representative who wish to be present. The telegraphic and conditional tenders shall not be accepted. The tender forms can be had from this office against cash payment (Nonrefundable) up to **20-7-2022** till 4.00 P.M.

The earnest money in the shape of National Saving certificates/time deposit/saving account in any of the post office saving bank account in H.P. duly pledged in favour of Executive Engineer Mechanical Division HP PWD Kullu must accompany each tender. The tender received without proper earnest money will summarily be rejected. The undersigned reserve the right to reject the tender without assigning any reasons. If holiday falls on date of opening of tender it will be opened on next working day.

Sr. No.	Name of work	Amount put to tender	Cost of tender form	Earnest Money	Time allowed
1	Construction of 62.00 mtr span temporary wire rope Jhulla over river Parvati Katagla, including construction of wire crates etc.	2,28,646.00	350.00	4,600.00	One Month

TERMS AND CONDITION:-

1. Copy of Registration / Enlistment with HP PWD Department.
2. Copy of GST/PAN number must also accompany with application for purchase of tender form.
3. The rate shall be valid up to 90/120 days.
4. Income tax as per rule and royalty as per HP Govt. rules GST @ 2% will also be deducted from the bill.
5. Conditional/telegraphic tenders are not acceptable.
6. Tender received after due date and time shall not be entertained.
7. The payment of the job shall be released only after completion of work and 10% security will be released after 6 months duly certified by the Engineer-in-Charge.

(Er. G. L. Thakur)
Executive Engineer,
Mechanical Division,
H.P PWD Kullu-175101


Schedule of Quantity

Name of Work: Construction of 62 mtr span temporary wire rope Jhulla over river Parvati at Katagala, including construction of wire crates etc.).

Estimated Cost - 228646/-
Earnest Money - 4600/-
Time one month

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount
1	Earth work in surface excavation not exceeding 30 cm in (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge. (Ordinary rock.)with in all lead & lifts of material as per the direction and entire satisfaction of Engineer -in- Charge.	10	Cum			
2	Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) with in all lead & lifts of material as per the direction and entire satisfaction of Engineer -in- Charge.	1.35	cum			
3	Square rubble masonry with hard stone of approved quality in foundation and plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) with in all lead & lifts of material as per the direction and entire satisfaction of Engineer -in- Charge.	17.36	Cum			
4	Providing and laying boulder apron laid in wire crates with 4mm dia. G.I. wire for crates wall. with in all lead & lifts of material as per the direction and entire satisfaction of Engineer -in- Charge.	11.71	Cum			
5	Providing and laying cement concrete in retaining walls, return walls, (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) with in all lead & lifts of material as per the direction and entire satisfaction of Engineer -in- Charge.	5.31	Cum			

6	Providing and fixing ISMB-200mm 86 kg including steel reinforcement 8mm dia 20kg for rings etc. with in all lead & lifts of material as per the direction and entire satisfaction of Engineer –in- Charge.	106	Kg				
7	Providing/Fixing of wire rope 16mm diameter. 6x36 steel core with in all lead & lifts of material as per the direction and entire satisfaction of Engineer –in- Charge.	270	Rmt				
8	Providing and fixing of Nylon rope 12 mm dia. with in all lead & lifts of material as per the direction and entire satisfaction of Engineer –in- Charge.	130	Rmt				
9	Providing/fixing of trolly with 2 Nos. of pulleys. with in all lead & lifts of material as per the direction and entire satisfaction of Engineer –in- Charge.	2 Nos	No.				
10	Providing/fixing wire rope U-clamps 16mm superior quality. with in all lead & lifts of material as per the direction and entire satisfaction of Engineer –in- Charge.	60	Nos.				


 Executive Engineer
 Mechanical Division
 H.P. PWD Kullu.