


**HPPWD
Tender Notice**

Sealed Item rates Tenders on PWD form 6&8 are invited by the Executive Engineer HP.PWD Nurpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R), so as to reach in his office on or before **25/07/2022** up to 11.00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative, if any. The tender forms can be obtained from this office against cash payment non-refundable during the working hours on **23/07/2022 up to 4.00 PM** and no tender form shall be issued by post. Application for issue of tenders should reach in the office along with all the required documents on or before **22/07/2022**. The earnest money in the shape of FDR of any nationalized Bank in H.P, duly pledged in the name of Executive Engineer, Nurpur Divn. HP.PWD Nurpur must accompany with the application. The conditional tender and tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserves the right to reject any tender without assigning any reason.

Sl. No.	Name of work	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit	Cost of tender form (Rs)
1	2	3	4	5	6
1	C/O link road Odder to Gatla Kms 0/0 to 1/200 (SH:- Providing and laying 80mm thick interlocking paver block at RD 0/624 to 0/711 (Length=87.00 mtr.)	495552/-	10000/-	Three months	350/-
2	Construction of Ladori to Ghalaon road kms 0/0 to 1/750 (SH:- Providing and laying 80mm thick interlocking concrete paver block from RD 0/720 to 0/810).	470745/-	10000/-	One month	350/-
3	Construction of link road to Suliali Dev Bharari Harijan Basti road kms 0/0 to 2/0 (SH:- Const.of U-shape drain with edge wall at RD 1/035 to 1/070 and construction of 900mm dia Hume pipe culvert at RD 1/070 and parapets).	235072/-	4700/-	Two months.	350/-
4	A/R & M/O Nurpur Lahru Tunnu Hatti road kms 0/0 to 15/390 (SH: Providing and laying 80mm thick interlocking concrete paver block from RD 15/049 to 15/100 and 15/135 to 15/155).	450048/-	10000/-	One month	350/-
5	Construction of Community Hall at Village Ban in ward No.4 in GP Nagni Tehsil Nurpur Distt. Kangra H.P. (SH: - Construction of main building) (Deposit work)	496707/-	10000/-	Two year	350/-
6	Construction of road from Bhatki to Gurchal via Bhagola Kuttan road kms 0/0 to 4/020 (SH:- Const.of edge wall at RD 0/875 to 0/905 and Providing and laying interlocking paver block 80mm thick in kms 0/895 to 1/925).	467023/-	10000/-	Three months	350/-
7	A/R & M/O Govt. Degree College Nurpur Distt. Kangra HP (SH:- Construction of retaining wall, Cabinet work in Principal office and Superintendent office).	323339/-	6600/-	Two years	350/-
8	Construction of link road to Harijan Basti Gharnoo road (SH:- Const.of U-shape drain with edge wall at RD0/050 to 0/080, C/O retaining wall, parapets and Providing/laying interlocking concrete paver block at various reaches in between kms 0/300 to 0/400).	481392/-	10000/-	One month	350/-

Certified that tender of above works are being called of emergent nature in Exigency of public interest.


 Executive Engineer
 Nurpur Division, HPPWD,
 Nurpur.
 For on behalf of Governor of HP

Himachal Pradesh
Public Works Department

Registered

No. PWN/CB/GA/E-27/Tender/2021-22-
To

2372

Dated:-

18/7/22

The Executive Engineer (IT Cell),
Nigam Vihar Shimla.

Subject: - Publication of Tender Notice.

Enclosed please find herewith the corrigendum in the Notice Inviting tender published on department website vide this office letter No., 191 dated 6/4/2022, in compliance to the Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th, July 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA/As above.


Executive Engineer,
Nurpur Division, HP PWD,
Nurpur.

SCHEDULE OF QUANTITY

Name of work :- Construction of Ladori to Chaloan road Km. 0/0 to 1/750 Estimated cost Rs. 470745.00
 (SH: Providing and laying 80mm thick interlocking con concrete paver block from RD.0/720 to 0/810) Earnest money Rs.10000 .00
 Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	29.70 cubic meter			Per cubic meter	
2	Providing and laying of I S I marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	297.00 square meter			Per square meter	
				Total		


 Executive Engineer
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY

Name of work :- Construction of Ladori to Chaloan road Km. 0/0 to 1/750 Estimated cost Rs. 470745.00

(SH: Providing and laying 80mm thick interlocking con concrete paver block from RD.0/720 to 0/810) Earnest money Rs.10000 .00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	29.70 cubic meter			Per cubic meter	
2	Providing and laying of I S I marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	297.00 square meter			Per square meter	
				Total		


 Executive Engineer
 Nurpur Division HPWD
 Nurpur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to Suliali Dev Bharari Harijan Basti road km. 0/0 to 2/0
(SH: Const. of U-shape drain with edge wall at RD. 1/035 to 1/070 and construction of 900mm Dia Hume pipe culvert at RD. 1/070 and parapets)

Estimated cost Rs. 235072.00
Earnest money Rs.4700.00
Time limit :- Two month

Sr. No.	Description of items	Rate in		Unit	Amount
		Qty.	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth. and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	45.73 cubic meter		Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 3: 6 (one cement: three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802.803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	13.05 cubic meter		Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of structure i.e. in cradle beading complete of plain cement concrete grade M-15 (M-fifteen) nominal mix 1:2½:5 (one cement; two and half sand : five graded crushed stone aggregate 20mm (twenty millimeters) including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806 , 807 1202 and 1204 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	1.51 cubic meter		Per cubic meter	
4	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203	0.09 cubic meter		Per cubic meter	

	and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.				
5	Providing and laying mechanically mixed and vibrated cement concrete grade M-15 (M-fifteen) in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form in parapets/toe walls bedding complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals.	26.68			Per cubic meter
5	Providing and laying to level o slope 900mm (nine hundred millimeters) dia meter reinforced cement concrete pipes NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding the cost of excavation, protection work, back filling concrete and masonry work in head walls and parapets a per drawing and M O R D technical specification clause 1108 and as per direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, malkana, toll tax, sale tax and other taxes imposed by the Government.	7.50			Per running meter
6	Earth filling in foundation , trenches and banking including breaking clods, ramming and dressing ground for the purpose of making embankments or filling up ground depression as per drawing and technical specification clause 305.3.9 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental .	4.94			Per cubic meter
	Total			Total	



Executive Engineer
Nurpur Division HPPWD
Nurpur

Executive Engineer
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Nurpur Lahru Tunnu Hatti road Km 0/00 to 15/390
(SH: Providing and laying 80mm thick interlocking con concrete paver block from RD.
15/049 to 15/100 and 15/135 to 15/155)

Estimated cost Rs. 450048.00
Earnest money Rs.10000 .00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including approved and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	106.09 cubic meter			Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	53.04 cubic meter			Per cubic meter	
3	Providing and laying of ISI marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	530.45 square meter			Per square meter	
				Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY
Name of work :- Construction of Community Hall at Village Ban in Ward No.4 G P Nagni Tehsil
Nurpur Distt. Kangra HP (Deposit work)
(SH:- Construction of main building)

Estimated cost Rs. 496707.00
 Earnest money Rs. 10000.00
 Time limit :- Two year

Sr No	Description of items	Quantity	Rates	Unit	Amount
			Figures Words		
1.	Excavation in foundation, trenches etcetera in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work . jumper blasting work . soft and hard blasting and doing work in saturated soil including chiseling or wedging out rock where blasting work is prohibited or any other mixed variety of soil including shoring, strutting dewatering and pumping or bailing out water (surface and sub soil water) upto any depth or any quantum of water including slush which may arise during dewatering removal of slush and stacking the serviceable and unserviceable material clear from the edges of excavation as directed by the Engineer-in-charge and then returning the stacked soil in 15 cm (fifteen centimeters) layers when required into plinths and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth as directed by Engineer in charge within all leads and lifts disposed earth to be levelled and neatly dressed including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive of octroi, royalty, malkana, toll tax, G S T, and other taxes imposed by the government.	31.98 cubic meter		Per cubic meter	
2.	Providing/ fixing form work with steel plates 3.15mm (Three point one five millimeters) thick, welded with angle iron in frame 30x30x5mm (Thirty into Thirty into Five millimeters) so as to give a fair finish including centering, shuttering strutting and propping etc, with wooden battens and ballies, height of propping and centering in all heights / depth below supporting floor to ceiling and removal of the same for in situ reinforced concrete and plain concrete work in foundation footings, basis of columns etcetera and mass concrete as per approved	37.93 square meter		Per square meter	

	drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals				
3.	Providing and fixing form work with steel plates 3.15mm(three point one five millimeters)thick welded with angle iron in frame 30x30x5mm(thirty into thirty into five millimeters),so as to give a fair finish including centering ,shuttering, strutting and propping etcetera with wooden battens and ballies, height of propping and centering in all heights/ depth below supporting floor to ceiling upto any height and removal of the same for in situ reinforced concrete and plain concrete work in Columns, pillars abutments, post and struts (square rectangular or polygonal in plan in any heights / thickness/depths etcetera upto all floor level including carriage of materials within all leads , lifts and other incidental and as per approved drawings, design and as per directions by the Engineer in charge. The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	22.94	square meter	Per square meter	
4.	Providing form work with steel plates 3.15mm(three point one five millimeters)thick welded with angle iron in frame 30x30x5mm(thirty into thirty into five millimeters),so as to give a fair finish including centering ,shuttering, strutting and propping etcetera with wooden battens and ballies, height of propping and centering in all heights / depths below supporting floor to ceiling upto any height and removal of the same for in situ reinforced concrete and plain concrete work in lintels, beams, plinth beams, girders, bressumers and cantilevers etcetera upto all floor level including carriage of materials within all leads , lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government .	7.48	square meter	Per square meter	
5.	Providing and fixing form work with steel plates 3.15mm(three point one five millimeters)thick welded with angle iron in frame 30x30x5mm(thirty into thirty into five millimeters),so as to give a fair finish including centering ,shuttering, strutting and propping etcetera with wooden battens and ballies, height of propping and centering in all heights / depths below supporting floor to ceiling	28.34	Runnin g meter	Per running meter	

	upto any height/ depths and removal of the same for in situ reinforced concrete and plain concrete work in edges of slabs and breaks in floors and walls of any width etcetera upto all floor level including carriage of materials within all leads and lifts and other incidental as per approved drawings, design and as per directions by the Engineer in charge. The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.					
6.	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded broken /crushed stone aggregate 40mm(forty millimeters) nominal size vibrated and mechanically mixed and curing complete excluding the cost of centering and shuttering in all work upto plinth level and as per approved drawing ,design and as per directions of Engineer in charge including carriage of materials within all leads , lifts and other incidentals The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	3.88	Cubic meter		Per cubic meter	
7.	Providing and laying cement concrete 1:5: 10(one cement; five sand : ten graded broken /crushed stone aggregate 40mm(forty millimeters) nominal size vibrated and mechanically mixed and curing complete excluding the cost of centering and shuttering in all work upto plinth level and as per approved drawing ,design and as per directions of Engineer in charge including carriage of materials within all leads , lifts and other incidentals The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	3.60	Cubic meter		Per cubic meter	
8.	Providing and laying in position machine batched and machine mixed design mix M-20 (M-twenty) grade to obtain the minimum compressive strength of 20 N/mm ² (twenty newton per square millimeters)with cement contents not less than 320 kg (three hundred twenty kilogram) per cubic meter and curing complete excluding cost of reinforcement for reinforced concrete work as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability for all work above plinth level to all floor level as per direction of Engineer-in-charge	17.21	Cubic meter		Per cubic meter	

	including carriage of materials within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government					
9.	Providing and fixing Steel reinforcement of Tata/ Tison / Sail Thermo-Mechanically Treated bars of grade Fe-500 (D) for reinforcement cement concrete work including straightening, cutting, bending, placing in position and binding all complete for all floors level including carriage of materials within all leads, lifts and other incidentals.. The rate is including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	2403.40	kilogram		Per kilogram	
10.	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement: six sand) and curing complete including carriage of materials within all leads and lifts and other incidental.	9.16	Cubic meter		Per cubic meter	
11	Brick work using Second class common burnt clay buildings bricks in super-structure above plinth level to all floor level in cement mortar 1:6 (one cement : six sand) and curing complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	14.13	Cubic meter		Per cubic meter	
					Total	

Executive Engineer
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :- Const of link road from Bhatki to Gurchal via Bhagola Kuttan road km 0/0 to 4/020
(SH: Const of edge wall at RD 0/875 to 0/905 and Providing and laying interlocking paver block
80mm thick in km 0/895 to 1/925)

471073-4
Estimated cost Rs. 469025.00
Earnest money Rs. 10000.00
Time limit : Three month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Words	Figures		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 as per direction and entire satisfaction of Engineer-in-charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or any other taxes imposed by the Government.	54.40 cubic meter			Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement: four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	22.40 cubic meter			Per cubic meter	
3	Providing and laying of ISI marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	224.00 square meter			Per square meter	

4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802.803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	22.50 cubic meter		Per cubic meter
5	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614, 709, 1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.00 Number		Each
		Total		


Executive Engineer,
Nurpur Division HPPWD
Nurpur

Executive Engineer,
Nurpur Division HPPWD
Nurpur

Name of work :- A/RV & M/O of Govt. Arya Degree College, Nurpur Distt. Kangra HP
(SH:- Construction of Retaining wall, Cabinet work in Principal office and Superintendent office)

SCHEDULE OF QUANTITY

Estimated cost Rs. 323339.00
Earnest money Rs. 6600.00
Time limit :- Two year

Sr No.	Description of items	Quantity	Rate in	Words	Unit	Amount
1	Excavation in foundation, trenches etcetera in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work . jumper blasting work , soft and hard blasting and doing work in saturated soil including chiseling or wedging out rock where blasting work is prohibited or any other mixed variety of soil including shoring, strutting dewatering and pumping or bailing out water (surface and sub soil water) upto any depth or any quantum of water including slush which may arise during dewatering removal of slush and stacking the serviceable and unserviceable material clear from the edges of excavation as directed by the Engineer-in-charge and then returning the stacked soil in 15 cm (fifteen centimeters) layers when required into plinths and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth as directed by Engineer in charge within all leads and lifts disposed earth to be levelled and neatly dressed including carriage of materials within all leads, lifts and other incidental charges	19.05 cubic meter	171.40		Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded broken /crushed stone aggregate 40mm(forty millimeters) nominal size vibrated and mechanically mixed and curing complete excluding the cost of centering and shuttering in all work upto plinth level and as per approved drawing ,design and as per directions of Engineer in charge including carriage of materials within all leads , lifts and other incidentals The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	39.15 cubic meter	3450.00		Per cubic meter	
3	Providing and fixing cabinet work made of 19mm(Nineteen millimeters) thick water proof termite resistant commercial board including vertical partitions, shelve and shutters frame of first class hard wood and hard wood edging 6mm (six millimeters) thick complete including top finished with 1mm (one millimeter) thick mica lamination sheet of approved shade and 6mm (six millimeters) thick commercial ply back side	34.50 square meter	4158.95		Per square meter	

	complete including nickle plated bright finished piano hinges and carriage of materials in all leads and lifts.					
4	Providing and fixing 75x65x4mm (heavy duty) bright finished brass butt hinges necessary screws complete including carriage of materials with in all leads and lifts	45.00 Nos.	137.30		Each	
5	Providing and fixing 65x35 mm (sixty five into thirty five millimeters) special quality bright finished brass cup boards locks or ward robe locks with six levers including necessary screws complete of approved quality including carriage of materials with in all leads and lifts	20.00 Nos.	238.40		Each	
6	Supplying and fixing 5 mm (five millimeter) thick glass panes of modi guard / Sanit gobain with putty and nails complete and as directed by Engineer in charge including carriage of materials within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	10.00 square meter	1565.70		Per square meter	
7	Providing and fixing 100mm (one hundred millimeters) bright finished brass floor door stopper with rubber cushion screws to suit shutters thickness complete including carriage of materials with in all leads and lifts	25.00 Nos.	147.20		Each	
8	Providing and fixing chromium plated brass 50mm (fifty millimeters) for cup boards locks or ward robe locks with six levers including necessary screws complete of approved quality including carriage of materials with in all leads and lifts	45.00 Nos.	116.70		Each	
9	Providing and laying granite stone in flooring 20mm (average) thickness base of cement mortar 1:4 (one cement: four sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone including rubbing and polishing complete upto all floor level as per HP.PWD. Specifications, approved drawings, designs and entire satisfaction and directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.00 square meter	3329.35		Per square meter	
				Total		


 Executive Engineer
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to Harijan Basti Gharnoo road
(SH: Const. of U-shape drain with edge wall at RD. 0/050 to 0/080, C/O Retaining wall, parapets and Providing/laying interlocking concrete paver block at various roaches in between km. 0/300 to 0/400)

Estimated cost Rs. 481392.00
Earnest money Rs. 10000 .00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	42.94 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802, 803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	57.86 cubic meter			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	26.10 cubic meter			Per cubic meter	

4	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T. or other taxes imposed by the Government.	6.40 cubic meter		Per cubic meter	
5	Providing and laying of ISI marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	64.00 square meter		Per square meter	
6	Back filling with granular materials behind abutment, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	12.76 cubic meter		Per cubic meter	
7	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	35.00 No.		Each	
8	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of structure i.e. in parapets complete of plain cement concrete grade M-15 (M-fifteen) nominal mix 1:2½:5 (one cement; two and half sand : five graded crushed stone aggregate 20mm (twenty millimeters) including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806 , 807 1202 and 1204 as per directions of Engineer-in- charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	5.75 cubic meter		Per cubic meter	
			Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur