

Himachal Pradesh
Public Works Department

No. PW.KD.GA/ Tender/2022-23 5087-5186

Dated : 18-07-2022

To

The Executive Engineer (IT cell),
Nigam Vihar, Shimla-2.

Subject:-

Publication of tender Notice.


Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per notification pr. Secy (PW) to the govt. of HP letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice urgent in nature and in public interest.

DA/NIT & Schedule of quantity certificate.


Executive Engineer
Killar Division HP, PWD
Killar (Pangi)

Copy forwarded for information and necessary action to:-

1. Copy forwarded to Resident Commissioner Pangi at Killar
2. Copy forwarded to Chief Engineer (KZ) HP PWD Dharmshala
3. Copy forwarded to Superintending Engineer 7th Circle HP PWD Dalhousie


Executive Engineer
Killar Division HP, PWD
Killar (Pangi)

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
“NOTICE INVITING TENDER”**

Sealed item rate tender on form No. 6&8 are hereby by the Executive Engineer, Killar Division, HPPWD, Pangi for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractor enlisted in HPPWD so as reach in this office as per time schedule given below:-

1. Date of receipt of Applications for tender forms:- **26.07.2022** upto 3:00 PM
2. Date issue/sale of Tender forms:- **27.07.2022** upto 5:00 PM
3. Date of receipt of Tender :- **28.07.2022** upto 11:00 AM
4. Date of opening of Tender:- **28.07.2022** upto 11:30 AM

Sr. No.	Name of Work	Estimated cost	Earnest Money	Cost of form (Rs.)	Time period for completion	Form No.	Eligibility of contractors
1	C/O link road to village jalwas (SH:- C/O R/Wall in wire crate at RD 0/720 to 0/740 and E/Wall between RD 0/740 to 0/800)	435584.00	10,000/-	350/-	Three Months		Class “D” enlisted in HPPWD
2	A/R & M/O to various roads under Killar Sub Division No-I Killar pangi (Sub-Head: - Repair of earthen Shoulder and unlined drain for various roads etc)	497175.00	10,000/-	350/-	Three Months	6&8	-do-
3	A/R & M/O to various roads under Killar Sub Division No-I Killar pangi Sub-Head: - Repair of earthen Shoulder and unlined drain for various roads etc)	497175.00	10,000/-	350/-	Three Months	6&8	-do-
4	C/O link road to village changli Punto Km 0/0 to 2/130(SH:- Construction of wire crate B/wall at RD 1/680 to 1/700, 1/835 to 1/855 and C/O wire crate R/wall at RD 1/835 to 1/855.)	493037.00	10,000/-	350/-	Three Months	6&8	-do-
5	C/O link road to village changli Punto Km 0/0 to 2/130 (SH:- Construction of R/Wall between at RD 1/270 to 1/285.)	386084.00	10,000/-	350/-	Three Months	6&8	-do-
6	C/O link road to village changli Punto Km 0/0 to 2/130 (SH:- Construction of R/Wall between at RD 1/330 to 1/342)	390841.00	10,000/-	350/-	Three Months	6&8	-do-
7	A/R & M/O to various roads under Killar Sub Division No-I Killar pangi (Sub-Head: - Repair of earthen Shoulder and unlined drain for various roads etc.)	497175.00	10,000/-	350/-	Three Months	6&8	-do-
8	C/O link road to village changli Punto Km 0/0 to 2/130 (SH:- Construction of R/Wall between at RD 1/380 to 1/395)	386896.00	10,000/-	350/-	Three Months	6&8	-do-

TERMS & CONDITION:- The tender documents shall be issued to those contractor/firms who fulfill the following documents with the application:-

1. The valid enlistment/ registration of contractor in appropriate class.
2. Permanent Account Number (PAN).
3. GST Number.


4. Earnest money in the shape of National saving certificate/time deposit account in any of the post office in HP. FDR from any Nationalized Bank (i/c SBI , Cooperative Bank & HP Garmin Bank) duly pledged in favour of the executive Engineer.
5. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money and cost of tender form shall summarily be rejected.
6. Tax clearance certificate (T.C.C.) issued from the concern
7. Ed Exercise and taxation department.
8. Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained/considered and will summarily be rejected.
9. Executive Engineer reserves the right reject or cancel any or all the tenders without assigning any reasons.
10. The offer of the tender shall be remain valid upto 120 days after the opening of tender.
11. If the date given above happens to be a holiday, the same shall be processed on next working days.
12. The contractors/firm must quote their rate in words as well as figures failing with Xen reserves the right to accept/reject any or all tenders.
13. The tender form will not be issued to those contractor/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
14. One contractor should not have more than two major works in hand at a time.
15. Work should be completion by the contractor within the stipulated period.
16. Works completion and work in hand certificate issued by the concerned Executive Engineer must be attached with the application for issued of tender form.


Executive Engineer,
Killar Division HP,PWD,
Killar (Pangi)

For and on behalf of the governor of HP.

CERTIFICATE

It is certified that the tender as called and opened on dated 28.07.2022 vide NIT No.PW-KD-DB/Tender/2022-23/ 5087-5186 dated. 18.07.2022 in respect of Killar Division, HP.PWD. Killar (Pangi) is very urgent and exigencies/emergency due to Snow bound area and less working season in the valley. Local Administrative Resident Commissioner Pangi at Killar has desired to open all the road for vehicular traffic the month of July, 2022 by improving the road surface etc. in public interest, hence above are tender are invited vide principal Secretary (PW) to the Govt. of Himachal Pradesh Endst. No PBW(B)/A(3)/1/2022 dated 16 July, 2021 due to urgency and emergent nature.



Executive Engineer
Killar Division HP,PWD
Killar (Pangi)

Schedule of Quantity					
Name of Work:- C/O link road to village jalwas (SH:- C/O wire crate R/Wall at RD 0/720 to 0/740 an C/O E/Wall at RD 0/740 to 0/800					
				Estimated Cost	435584.00
				Earnest Money	2000.00
				Time	Three Month
				Estimated Rate	Amount
S No	Description of work	Quantit y	Unit	Figure	Words
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of	145.05	Per cubic metre		
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 (two hundred eighty) and IS: 4826 (Four thousand eight hundred twenty six) in 100mm x 100mm (hundred millimetre into hundreded millimetre) mesh woven diagonally including 10 per cent (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) as per drawing and technical specifications clause 1301, to the entire satification and direction of engineer-in-charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental. The rates are inclusive of GST and other taxes to be imposed by the Government.	90.85	Per Cubic Metre		
3	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetra in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	205.48	Per Cubic Metre		
17	Back filling with granular material behind abutment wing wall and return wall and retaining/ breast walls, complete as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300, as per direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	38.00	Per Cubic Metre		
Total					

Executive Engineer
Killar Division
HPPWD Killar

SCHEDULE OF QUANTITY						
Name of Work:- A/R & M/O to various roads under Killar Sub Division No-I Killar pangi						
Sub-Head: - - Repair of earthan Shoulder and unlineed drain for various roads etc.						
S r.	Description of Items	No.or Qty.	Unit	Estimated Rate		Amount
				Figure	Words	
1	Making up loos material / irregularities on shoulder to the design level by adding fresh approved slected soil and compacting it with appropriate equipment at OMC upto lead of 100 metre as per technical specification clause 1903. as per direction of Engineer-in-charge including carriage of materials upto all leads andlifts and other incidental. The rate including ectroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government	13250.00	Per Square Metre			
2	Construction unlineed surface drain of avrage cross- sectional area 0.40 Squaremetre in soil specified lines, grades, level and dimesion. Excavated material to be used in embankment with a lift upto 3.00 metre and lead of all lead as per technical specification clause 307 as per entire satisfaction as per direction of Engineer-in-charge including carriage of materials upto all leads andlifts and other incidental. The rate including ectroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government	6500.00	Per Running Metre			

Executive Engineer
Killar Division
HPPWD Killar

Job No-3.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O to various roads under Killar Sub Division No-I Killar pangi				Estimated Cost:Rs.	497175.00		
Sub-Head: - - Repair of earthan Shoulder and unlined drain for various roads etc.				Earnest Money:Rs.	10000.00		
				Time Limit :	One Month		
S	r.	Description of Items	No.or Qty.	Unit	Estimated Rate		Amount
					Figure	Words	
1		Making up loos material / irregularities on shoulder to the design level by adding fresh approved slected soil and compacting it with appropriate equipment at OMC upto lead of 100 metre as per technical specification clause 1903. as per direction of Engineer-in-charge including carriage of materials upto all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana toll tax sale tax or other taxes imposed by the Government	13250.00	Per Square Metre			
2		Construction unlined surface drain of avrage cross- sectional area 0.40 Squaremetre in soil specified lines, grades, level and dimesion. Excavated material to be used in embankment with a lift upto 3.00 metre and lead of all lead as per technical specification clause 307 as per entire satisfaction as per direction of Engineer-in-charge including carriage of materials upto all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana toll tax sale tax or other taxes imposed by the Government	6500.00	Per Running Metre			


 Executive Engineer
 Killar Division
 HPPWD Kilar

Job No-4

Schedule of Quantity					Estimated Cost	493037.00
Name of Work:- C/O link road to village changli Punto Km 0/0 to 2/130					Earnest Money	10000.00
(SH:- Construction of wire crate B/wall at RD 1/680 to 1/700, 1/835 to 1/855 and C/O wire crate R/wall at RD 1/835 to 1/855.					Time	Three Month
S N	Description of work	Quantity	Unit	Estimated Rate		Amount
				Figure	Words	
2	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of	98.00	Per cubic metre			
	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 and IS: 4826 in 100mm X100mm mesh including 10 percent extra for laps and joints laid with stone boulders weight not less than 25kg. each as per drawing and technical specification clause 1301. as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana toll tax , sale tax or other taxes imposed by the Government.	325.00	12.50			
	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.	13.50	Per cubic metre			
Total						


 Executive Engineer
 Killar Division
 HPPWD Khar

Job No-5

Schedule of Quantity						Estimated Cost	386084.00
Name of Work:- C/O link road to village changli Puntto Km 0/0 to 2/130						Earnest Money	10000.00
(SH:- Construction of R/Wall between at RD 1/270 to 1/285.						Time	Three Month
S	N	Description of work	Quantity	Unit	Figure	Estimated Rate	
						Words	Amount
1		Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling (wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	35.76	Per cubic metre			
2		Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	103.12	Per cubic metre			
3		Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	0.09	tonne			
4		Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	23.34	Each			

5	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	17.08	Per cubic metre			
Total						


 Executive Engineer
 Kallar Division
 HPPWD Kallar

Job No. 6

Schedule of Quantity					Estimated Cost	390841.00
Name of Work:- C/O link road to village changli Punto Km 0/0 to 2/130					Earnest Money	10000.00
(SH:- Construction of R/Wall between at RD 1/330 to 1/342					Time	Three Month
S N	Description of work	Quantity	Unit	Estimated Rate	Amount	
				Figure Words		
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering. and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	72.88	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana toll tax ,sale tax or other taxes imposed by the Government. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	103.12	Per cubic metre			
3	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	0.09	tonne			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia P/V/C pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	23.34	Each			

5	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	17.08	Per cubic metre			
Total						


 Executive Engineer
 Killar Division
 HPPWD Killar

Job. No. 7.

SCHEDULE OF QUANTITY						
Name of Work:- A/R & M/O to various roads under Killar Sub Division No-I Killar pangi						
Sub-Head: - - Repair of earthan Shoulder and unlined drain for various roads etc.						
S r.	Description of Items	No.or Qty.	Unit	Estimated Rate		Amount
				Figure	Words	
1	Making up loos material / irregularities on shoulder to the design level by adding fresh approved slected soil and compacting it with appropriate equipment at OMC upto lead of 100 metre as per technical specification clause 1903. as per direction of Engineer-in-charge including carriage of materials upto all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	13250.00	Per Square Metre			
2	Construction unlined surface drain of avrage cross- sectional area 0.40 Squaremetre in soil specified lines, grades, level and dimesion. Excavated material to be used in embankment with a lift upto 3.00 metre and lead of all lead as per technical specification clause 307 as per entire satisfaction as per direction of Engineer-in-charge including carriage of materials upto all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	6500.00	Per Running Metre			

Executive Engineer
Killar Division
HPPWD Killar

Job No. 8

Schedule of Quantity					Estimated Cost	386896.00
Name of Work:- C/O link road to village changli Punto Km 0/0 to 2/130					Earnest Money	10000.00
(SH:- Construction of R/Wall between at RD 1/380 to 1/395					Time	Three Month
Description of work					Estimated Rate	Amount
S	N	Quantity	Unit	Figure	Words	
1	Earth work in excavation for structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering, and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	42.10	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana toll tax ,sale tax or other taxes imposed by the Government. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	103.12	Per cubic metre			
3	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	0.09	tonne			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	23.34	Each			

5	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1204.3.8 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government. complete as per M.O.R.D. technical specifications section No. 503 including hauling/ carriage of materials to various location through all modes of transportation all leads, lifts and other incidental and as per direction of Engineer-In-Charge. The rate including of GST, or other taxes imposed by the government.	17.08	Per cubic metre			
Total						


 Executive Engineer
 Killar Division
 HPPWD Killar