

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 23.07.2022 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours:

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Schedule	
1	Last date for tender receipt of application for tender form	21.07.2022 upto 4:00 PM
2.	Last date of sale of tender forms.	22.07.2022 upto 4:00 PM
3.	Date of receipt of tender forms	23.07.2022 upto 10:30AM
4.	Date of opening of tenders	23.07.2022 at 11:00AM


Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1.	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road km 48/0 to 87/0 (SH:- C/O Brest Wall between Km 82/315 to 82/330)	287305/-	5800/-	One Month	350/-
2.	A/R & M/O of HPPWD Rest House at Rajgarh, District Sirmour (HP) (Sh:- Providing and Laying Paint and Distemper in Building)	2,27,934/-	4,600/-	One Month	350/-
3.	Construction of link road from Kot Dhangar to Chamroga Km 0/0 to 3/0 (SH:- C/o 900mm dia RCC Hume pipe culvert alongwith both side wing wall at RD 0/620) Under SCSP	2,79,430/-	5,600/-	Two Months	350/-
4.	Construction of Kulath Kori Jolla road Km. 0/0 to 9/500 (Providing and laying G-II in km 1/0 to 1/500) Under SCSP.	2,95,799/-	6,000/-	One Month	350/-
5.	C/O Tikkri Tali to Jolla Bohal road Km 0/0 to 1/080 (SH:- Providing and laying Kharanja soling in Km 0/0 to 0/160).	90,840/-	2,000/-	One Month	350/-
6.	Restoration of rain damages on Churwadhar Gadol Pirag road Km 0/0 to 10/750 (SH:- C/O Wire crate Brest wall between Km 5/670 to 5/695).	3,93,289/-	8,000/-	Two Months	350/-
7.	A/R & M/O to Solan Meenus road Km 24/345 to 61/0 (SH:- Improvement of curves between Km 37/345 to 37/495 & C/O U-shape drain in Km. 37/251 to 37/400).	4,96,882/-	10,000/-	Two Months	350/-

Certificate :-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who dose not have more than two works in hand in HPPWD Circle/ Division.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.

10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW(B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.
12. The tender document shall be issued to only those contractors who submit registration of GST No.
13. The tender document shall be issued to only those contractors who submit GST Clearance Certificate signed by the Asstt. Commissioner (Taxes).
14. The tender document shall be issued to only those contractors who submit GSTR 3B upto the last date of the proceeding month.


Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP

9
on behalf of Governor of Himachal Pradesh
Tel. No. 01799-221023
Mail. ee-raj-hp@nic.in


Dated:-

16-07-22

No.PW/RGH/Estt-Tender/2022-23-

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-1.
2. The Chief Engineer (South) HP.PWD, Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.



Executive Engineer,
Rajgarh Division,
HP. PWD. Rajgarh.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- C/O Breast wall between Km 82/315 to 82/330).

Estimated cost:-Rs.2,87,305/-
Earnest money:- Rs. 5,800/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	42.08	Per Cubic Metre.			
2	Providing and laying concrete for plain Cement concrete in 1:4:8 (one cement: four sand: eight graded crushed hard stone aggregate 40 (forty) millimeter nominal size) mechanical mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	60.72	Per Cubic Meter.			
3	Providing weep holes in brick masonry/Plain/Reinforced concrete abutment, wing wall/ return wall with 100 mm (one hundred millimeter) dia AC pipe, extending through the full width of the structure with slope of 1: 20 1(V): 20 (H) towards drawing face. Complete as per drawing and technical specifications clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three seven) including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	14.00	Each			
4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	2.70	Per cubic meter.			


Executive Engineer
Rajgarh Division
JHP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O of HPPWPD Rest House at Rajgarh, District Sirmour (HP) (Sh:- Providing and Laying Paint and Distemper in Building)


Job No.

Estimated cost:-Rs. 2,27,934/-

Earnest money:- Rs. 4,600/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Distemping with oil bond washable distemper of approved brand and manufacture (two coats) and of required shade on undecorated wall surface to give an even shade over and including a priming coat of with distemper primer approved brand and manufacture thoroughly brushing the surface free from mortar droppings and other foreign matter including preparing the surface even and sand papered smooth complete as per HP.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of	1128.78	Per Square metre.			
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade. New work two or more coats applied 21.43ltr/10sqm over and including priming coat of exterior primer applied 0.90 ltr/10sqm as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	567.09	Per Square metre.			
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	315.59	Per Square metre.			
4	French spirit polishing Two or more coats on new works including a coat of wood filler as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	126.80	Per Square metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work : Construction of link road from Kot Dhanger to Chamroga Km 0/0 to 3/0 (SH:- C/o 900mm dia RCC Hume pipe Estimated cost:- Rs. 2,79,430/-
 culvert alongwith both side wing wall at RD 0/620) Under SSCP
 Earnest money:- Rs. 5,600/-
 Time Limit:- Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	51.02	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	30.43	Per Cubic Metre			

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:6:12 (One Cement : Six Sand : Twelve graded stone) aggregate 40 mm (Forty) millimetre nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3.62	Per Cubic Metre			
4	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	12.25	Per Cubic Metre			
5	Providing and laying reinforced cement concrete 900 mm (Nine Hundred millimeter)dia pipe class NP-2(Non Presseure- Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	7.50	Per running Metre.			
6	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	5.00	Each			
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.24	Per Cubic Metre.			


 Executive Engineer,
 Raigarh Division
 JHP:PED, Raigarh.

SCHEDULE OF QUANTITY

Name of work : Construction of Kulath Kori Jolla road Km 0/0 to 9/0 (SH:- Providing and laying G-II in Km. 1/00 to Estimated cost: - Rs. 2,95,799/-
1/500) Under SCSP. Earnest money: - Rs. 6,000/-
Time Limit: -One Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing and laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (Eighty- One hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill up the interstices of coarse aggregate, watering and compacting to the required density WBM Grading -II as per Technical Specification Clause 405. (Clause Four Hundred Five) By Manual Means , including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	132.00	Per Cubic Metre.			


Executive Engineer
Rajgarh Division
HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work : Construction of Tikkri Tali to Jolla Bohal road km 0/0 to 1/080 (SH:- providing and laying Kharanja Estimated cost: - Rs. 90,840/- soling in Km. 0/00 to 0/160).
 Earnest money: - Rs. 2,000/-
 Time Limit: -One Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing and laying stone soling properly hand-packed filling interssices with kharanja stone and consolidating with power and roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP. PWD specification 100mm(One hundred) millimetre spread thickness (finished work including materials and labour By Manual Means , including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	58.96	Per Cubic Metre.			


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damages on Churwadhar Gadol Pirag road Km 0/0 to 10/750 (SH:- C/O Wire crate Brest wall between Km 5/670 to 5/695).

Estimated cost: - Rs. 3,93,289/-
Earnest money: - Rs. 8,000/-
Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate	
				in figures.	in words
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	93.00	Per Cubic Metre.		
2	Providing and laying of boulder apron laid in wire crates with 4 mm(four milimeter) dia GI wire conforming to IS:280 (two hudred eighty) and IS:4826(four thousand eight hundred twenty six) in 100 mm x 100 mm(one hundred into one hundred milimeter) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301,(one thousand three hundred one) including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	144.06	Per Cubic Metre		


Executive Engineer,
 Raigarh Division
 HPPWD Raigarh.

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to Solan Meenus road Km 24/345 to 61/0 (SH:- Improvement of curves between Km 37/345 to 37/495 & C/O U-shape drain in Km. 37/251 to 37/400).

Estimated cost: - Rs.4,96,882/-
Earnest money: - Rs.10,000/-
Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate	
				in figures.	in words
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in - Charge for smooth riding. The recovery for stones, whether useful or not, for 110.09 cum (One hundred ten point zero nine cubic metre) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1501.25	Per Cubic Metre.		

2	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	62.58	Per Cubic Metre.			
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:2:4. (One Cement : Two Sand : Four graded stone) aggregate 20 mm (Twenty) millimetre nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3.910	Per Cubic Metre			
4	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	35.770	Per Cubic Metre			
5	Providing toor steel reinforcement for reinforced cement concrete work including beding binding and placing in position complete up to floor level all hieghts as per HP.PWD specification, including carriege of all labour equipments and materials to various location through all modes of transportation in all lead and lifts, including all incidental charges.	293.25	Per Kilogra mme			


 Executive Engineer,
 K. Rajgarh Division
 Upper Rajgarh