

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender-NIT/2022:-

7293-99

Dated: 29-06-2022

To

✓ The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: -

Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pr. Secy. (PW), to the Govt. of H.P. letter No.PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - Notice Inviting Tender.
(13 Nos. Works)

019
Executive Engineer,
HP.PWD., Division,
Nerchowk.

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD., Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Account Branch and Drawing Branch in this office.
Notice Board.

Executive Engineer,
HP.PWD., Division,
Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed Prcantage rate tender on form "6&8" are invited by the Executive Engineer, Nerchowk, H.P.P.W.D. Nerchowk for the following work from the approved and eligible contractors enlisted in H.P.P.W.D. so as to reach in his office on or before **13-07-2022 upto 11.30 A.M.** and will be opened on the same day at **3.00 P.M.** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:00 A.M. on 11-07-2022** and EMD should be attached during the submission of application for obtaining the tender form, without Earnest Money & Cost of tender form, application will not be accepted.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest should be attached with application. The offer of the tender shall be kept open for **90 days**. The Executive Engineer reserves the right to reject the tender without assigning any reason:-

Sr. No.	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender Form (Rs.)	Time limit	Eligible Class of Contractor
1.	Annual Repair and Maintenance in Shri Lal Bahadur Shastri Govt. Medical College & Hospital at Nerchowk, Mandi (SH:- Providing and Fixing CPVC fitting in WC of boys and girls hostel in all floors).	430160	8600	350	Two Months	"C&D"
2	RRD on Ratti Randhara road Km. 0/0 to 9/00 (SH:-C/o PCC R/wall at RD.0/910 to 0/920 with Toe Wall)	301449	6100	350	Two Months	"C&D"
3.	Construction of link road from Rajgarh to Koyla Mata Mandir Piplu Segli road Km. 0/0 to 5/00 (SH:-C/o PCC R/wall at RD. 1/345 to 1/360 with toe wall).	425019	8500	350	Two Months	"C&D"
4.	RRD on Manjhyali Ghoru Sardhwar road Village Batahan Km. 0/0 to 13/0. (SH:-Construction of PCC Breast wall at RD.9/120 to 9/130).	154026	3100	350	Two Months	"C&D"
5.	Addition and Alteration work in MBBS Boys and Girls Student Hostels (SH:-Providing and Fixing Collapsible gate in Third and Fourth floor of Block-B)	105080	2100	350	One Month	"C&D"
6.	Addition and Alteration in operation theater at 6 th floor under SLBS Govt. Medical College & Hospital at Nerchowk. (SH:-Construction of wash rooms, instrument washing area and pantry along with creation of window in HOD room, main glass door to dialysis room) Job No.1	369160	7400	350	Two Months	"C&D"
7	Improve of Black spot on Chhapru Nallah to Khakhriyana road Km.0/0 to 4/500. (SH:-C/o PCC R/wall at RD.4/160 to 4/175 with toe wall).	429244	8600	350	Two Months	"C&D"
8	Black spot Galma Majhyali road Km. 0/00 to 9/00 (SH:-Construction of PCC Breast wall at RD. 1/300 to 1/312).	121013	2500	350	Two Months	"C&D"
9	RRD Ratti Kalkhar road Km. 0/0 to 10/0 (SH:-Providing and Laying steel grating for road crossing at RD.0/630 to 0/646.80).	205457	4200	350	Two Months	"C&D"
10	A/R & M/O various roads under Rewalsar Sub-Division HP.PWD., Rewalsar, (SH:-Supplying and Stacking graded crushed stone aggregate 13.2 mm to 5.6 mm and coarse sand) Rewalsar Section.	199100	4000	350	One Month	"C&D"
11	Annual repair and maintenance of building of SLBS Govt. Medical College & Hospital at Nerchowk. (SH:-Providing and Fixing iron chequered plates/panel in the room of transformer and DG area).	147337	3000	350	One Month	"C&D"
12	Addition and Alteration in the campus of SLBS Govt. Medical College & Hospital at Nerchowk. (SH:-Providing and Fixing CHEMICAL RE-BARING of tor steel, Civil work and Chemical Water proofing of lift pits in Hospital, RDH and Nursing Student Hostels).	356871	7200	350	One Month	"C&D"
13	Annual Repair and Maintenance of various non residential building of Shri Lal Bahadur Shastri Govt. Medical College & Hospital at Nerchowk, Mandi (SH:-Supplying and stacking of 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm).	41160	850	350	One Month	"C&D"

It is certified that the above tenders i.e. Sr. No. 1 to 13 are very Urgent Nature, so may be uploaded on department website in public interest.

Contd. ---2---

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and tendered amount below 30% of the estimated cost will be summarily rejected.


Executive Engineer,
HP.PWD. Division,
Nerchowk. 

SCHEDULE OF QUANTITY						
NAME OF WORK :- Annual Repair and Maintenance in Shri Lal Bahadur Shastri Govt, Medical College & Hospital at Nerchowk, Mandi (Sub Head:- Providing and fixing CPVC fitting in WC of boys and girls hostel in all floors.)			Estimated Cost:- 430160.00			
			Earnest Money :- 8600.00			
			Time :- Two Months			
S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m (one point zero zero millimetre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete including carriage of materials with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-charge.	916.00			Per Running Metre	
2	Providing and fixing stainless steel long body bib cock long nose with wall flange VAALVE make CAT No. 919904 complete including carriage of material with in all leads and lift and other incidentals and as per the direction of the Engineer in charge.	88.00			Each	
3	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622, of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement : three coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including carriage of materials with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-charge.	34.35			Per Square Metre	
					Total	430160.00
Quoted Percentage in Figures Quoted Percentage in Words						
			Executive Engineer, HPPWD Division Nerchowk			

Job No. 2

Name of work:- RRD on Ratti Randhara road km. 0/0 to 9/00. (SH:- C/O PCC R/wall at RD. 0/910 to 0/920 with Toe Wall)									
S.N o		Description of item	Quantity	Rate		Unit	Amount	Estimated Cost:- 301449.00 Earnest Money :- 6100.00 Time :- Two Months	
				In figure	In word				
1		Earth work in excavation of foundation of structure in all kinds of classification of soil such as pick work, jumper work, blasting work saturated soil including chiseling wedging out of rock where blasting is prohibited or any other mixed variety of soil, dewatering and/or removal of slush and other incidentals, lifts upto any height, stacking the excavated soil upto all leads and lifts clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) thick layer when required into plinths, sides of foundation etc. consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respects.	31.60						
2		Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	79.70						
3		Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specifications complete including carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	10.60						
4		Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications including carriage of material and other incidentals as per the direction of the Engineer-in-Charge .	14.00						

SCHEDULE OF QUANTITY	
1	100
2	200
3	300
4	400
5	500
6	600
7	700
8	800
9	900
10	1000
11	1100
12	1200
13	1300
14	1400
15	1500
16	1600
17	1700
18	1800
19	1900
20	2000
21	2100
22	2200
23	2300
24	2400
25	2500
26	2600
27	2700
28	2800
29	2900
30	3000
31	3100
32	3200
33	3300
34	3400
35	3500
36	3600
37	3700
38	3800
39	3900
40	4000
41	4100
42	4200
43	4300
44	4400
45	4500
46	4600
47	4700
48	4800
49	4900
50	5000
51	5100
52	5200
53	5300
54	5400
55	5500
56	5600
57	5700
58	5800
59	5900
60	6000
61	6100
62	6200
63	6300
64	6400
65	6500
66	6600
67	6700
68	6800
69	6900
70	7000
71	7100
72	7200
73	7300
74	7400
75	7500
76	7600
77	7700
78	7800
79	7900
80	8000
81	8100
82	8200
83	8300
84	8400
85	8500
86	8600
87	8700
88	8800
89	8900
90	9000
91	9100
92	9200
93	9300
94	9400
95	9500
96	9600
97	9700
98	9800
99	9900
100	10000

OK

Executive Engineer,
HPPWD Division
Nerchowk

SCHEDULE OF QUANTITY						
Name of work:- RRD on Manjhyali Ghour Sardhwar road village Batahan Km. 0/0 to 12/0. (SH:- Construction of PCC Breast wall at RD. 9/420 to 9/130)						
Estimated Cost:- 154026.00						
Earnest Money :- 3100.00						
Time :- Two Months						
S No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area in all kinds of classification of soil such as pick work, jumper work, blasting work saturated soil including chiseling wedging out of rock where blasting is prohibited or any other mixed variety of soil, dewatering and/or removal of slush and other incidentals by mechanical means including cutting and trimming of side slopes and disposing of excavated earth including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	26 60	172 00	Rs One hundred seventy two and paise nil only	Per cubic Metre	4575 00
2	Earth work in excavation of foundation of structure in all kinds of classification of soil such as pick work, jumper work, blasting work saturated soil including chiseling wedging out of rock where blasting is prohibited or any other mixed variety of soil, dewatering and/or removal of slush and other incidentals, lifts upto any height, stacking the excavated soil upto all leads and lifts clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) thick layer when required into plinths, sides of foundation etc. consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respects	9 96	287 00	Rs Two hundred eighty seven and paise zero only	Per cubic Metre	2859 00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification in cement concrete 1 5 10 (one cement five sand. Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	40 58	3485 10	Rs. Three thousand four hundred eighty five and paise ten only	Per cubic Metre	141425 00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V 20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	18 00	287 05	Rs. Two hundred eighty seven and paise zero five only	Each	5167 00
					Total	154026.00

Quoted Percentage in figure

Quoted Percentage in Words



Executive Engineer,
HPPWD Division
Nerchowk

SCHEDULE OF QUANTITY

NAME OF WORK :- Addition and Alteration work in MBBS Boys and Girls Student Hostels. (SH:- Providing and fixing Collapsible gate in Third and Fourth floor of Block-B.)

Estimated Cost:- 105080.00

Earnest Money :- 2100.00

Time :- OneMonths

[illegible]

Job No.6

14.

SCHEDULE OF QUANTITY						
NAME OF WORK :- Addition and alteration in operation theater at 6th floor under SLBS Govt. Medical College & Hospital at Nerchowk . (SH : - Construction of wash rooms, instrument washing area and pantry along with creation of window in HOD room , main glass door to dialysis room) Job No. - 1				Estimated Cost:- 369160.00 Earnest Money :- 7400.00 Time :- Two Months		
S.N o	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres (fifty) lead including carriage of materials with in all leads and lifts and other incidentals and as per the direction of the Engineer in charge.	0.91			Per Cubic Metre	
2	Providing and laying autoclaved aerated cement blocks masonry with 150mm/230mm/300 mm (one hundred fifty /two hundred thirty / three hundred millimetre) thick AAC blocks in super structure above plinth level up to floor V level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete (The payment of RCC band and reinforcement shall be made for seperately) including carriage of materials with in all leads and lifts and other incidentals and as per the direction of the Engineer in charge.	11.05			Per Cubic Metre	
3	12 mm (twelve millimetre) cement plaster on rough side of single or half brick wall of mix: 1:4 (one cement: four coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	113.16			Per Square Metre	
4	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	113.16			Per Square Metre	
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	113.16			Per Square Metre	
6	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	113.16			Per Square Metre	
7	Wall painting One or more coats on old work with plastic emulsion paint of approved brand and manufacture to give an even shade complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	528.30			Per Square Metre	
8	complete. Providing and laying Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred) (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (one Cement : four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sq.m (three point three kg/sqm) including pointing the joints with white cement and matching pigments etc., complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	19.98			Per Square Metre	

9	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm (twelve millimetre) thick bed of cement Mortar 1:3 (one cement: three coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	69.66			Per Square Metre	
10	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform etc complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.86			Per Square Metre	
11	Providing and laying in position reinforced cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm (twenty millimetre) nominal size) , excluding the cost of centering, shuttering, finishing and reinforcement all work up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.19			Per Cubic Metre	
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of materials with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	15.20			Per Kilogram	
13	Providing and fixing 18 mm (eighteen millimetre) thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for Kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (onecement : four coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels including carriage of materials with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	2.01			Per Square Metre	
14	Providing and fixing 600x400x250 mm (Six hundred into four hundred into two hundred fifty millimetre) size white vitreous china laboratory sink including rim, CERA make with making all connections excluding cost of fittings complete at all levels including carriage of materials with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00			Each	
15	Providing and fixing 560x470x190 mm (five hundred sixty into four hundred seventy into one hundred ninety millimetre) size counter wash basin of CERA and PAREWARE Make CAT NO S2030104 with C.I. or M.S. bracker painted white including cutting holes in walls and making good the same out excluding fitting complete including carnage of material with in all lads and lifts complete in all respect as per direction of Engineer-in-Charge	8.00			Each	
16	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required including carriage of materials with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	8.00			Each	

[illegible]

Executive Engineer,
HPPWD Division
Nershpaw
Nershpaw

[illegible]

SCHEDULE OF QUANTITY						
Name of work:- Black Spot Galma Majhyali road Km. 0/00 to 9/00. (SH):- Construction of PCC Breast wall at RD. 1/300 to 1/312)		Estimated Cost:- 121013.00 Earnest Money :- 2500.00 Time :- Two Months				
S.N o	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area in all kinds of classification of soil such as pick work, jumper work, blasting work saturated soil including chiseling wedging out of rock where blasting is prohibited or any other mixed variety of soil, dewatering and/or removal of slush and other incidentals by mechanical means including cutting and trimming of side slopes and disposing of excavated earth including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	12.48			Per cubic Metre	
2	Earth work in excavation of foundation of structure in all kinds of classification of soil such as pick work, jumper work, blasting work saturated soil including chiseling wedging out of rock where blasting is prohibited or any other mixed variety of soil, dewatering and/or removal of slush and other incidentals, lifts upto any height, stacking the excavated soil upto all leads and lifts clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) thick layer when required into plinths, sides of foundation etc. consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respects.	11.64			Per cubic Metre	
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	32.16			Per cubic Metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	12.00			Each	
					Total	
Quoted Percentage in figure						
Quoted Percentage in Words						
 Executive Engineer, HPPWD Division Nerchowk						

Job No. 9

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:- A/R & M/O Ratti Kalkhar road Km. 0/0 to 10/0. (Sub Head :- Providing and laying steel grating for road crossing at RD 0/630 to 0/646.80)			Estimated Cost:- 205457.00			
			Earnest Money :- 4200.00			
			Time :-Two Months			
S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Steel work welded in built up sections trusses and framed work including cutting, hoisting, fixing and launching in position and applying a priming coat of red lead paint In gratings framed guard bars ladders, railings, brackets and similar works including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	17.15	11980.00	Rupees Eleven thousand nine hundred eighty and paise zero only.	Per Quintal	205457.00
					Total	205457.00
			Quoted Percentage in Figure			
			Quoted Percentage in Figure			
						 Executive Engineer, HPPWD Division, HPPWD Nerchowk

Executive Engineer
HPPWD Division
Nerchowk

SCHEDULE OF QUANTITY						
NAME OF WORK :- Addition and alteration in the campus of SLBS Govt . Medical College & Hospital at Nerchowk. (SH : - Providing and fixing CHEMICAL RE - BARING of tor steel , Civil work and Chemical Water Proofing of lift pits in Hospital, RDH and Nursing student Hostels.)						Estimated Cost:- 356871.00
						Earnest Money :- 7200.00
						Time :- One Months
S.N	Description of item	Quantity	In figure	Rate	Unit	Amount
0				In word		
1	Providing and fixing 10 mm (Ten millimetre) dia CHEMICAL RE- BARING of tor steel complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.00			Each	
2	Providing and fixing civil work on the base of lift pits complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	61.30			Per Square Metre	
3	Providing and fixing water proofing of lift pit as per procedure complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	146.86			Per Square Metre	
					Total	356871.00
	<u>Quoted Percentage in Figures</u>					
	<u>Quoted Percentage in Words</u>					
	Assistant Engineer, Medical College Sub Division, HPPWD Nerchowk.					
	Executive Engineer, HPPWD Division Nerchowk					

[illegible]


Executive Engineer
HP.PWD Division
Nerchowk-175008