

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2022-23- 5315-16  
To

Dated: 05-07-2022

The Executive Engineer (IT Cell),  
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 20.07.2022.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.

  
Executive Engineer,  
Paonta B&R Division,  
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12<sup>th</sup> Circle HP.PWD Nahan for information please.

  
Executive Engineer,  
Paonta B&R Division,  
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Scaled items rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 20.07.2022 up to 11.30 AM and shall be opened on 20.07.2022 the same day at 11.40 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 19.07.2022 for which the applications should reach in this office up to 4.00 PM on 18.07.2022. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.


| Sr. No. | Name of works                                                                                                                                                            | Estimated Cost    | Earnest Money   | Time Limit   | Cost of Form | Class |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|-----------------|--------------|--------------|-------|
| 1       | A/R & M/O Ajoli Kishankot road Km. 0/0 to 2/0. (SH:- C/o extra road diversion for safety of school students km 0/0 to 0/150)                                             | Rs.<br>4,40,826/- | Rs.<br>10,000/- | Three months | 350/-        | C & D |
| 2       | A/R & M/O Ajoli Kishankot road Km. 0/0 to 2/0. (SH:- P/L top layer 0.50 mm thick repair in PCC (1:2:4) of existing cement road in Km. 0/500 to 1/0)                      | Rs.<br>4,84,535/- | Rs.<br>10,000/- | Three months | 350/-        | C & D |
| 3       | A/R & M/O Ajoli Kishankot road Km. 0/0 to 2/0. (SH:- P/L top layer 0.50 mm thick repair in PCC Km. 0/0 to 0/500)                                                         | Rs.<br>4,84,535/- | Rs.<br>10,000/- | Three months | 350/-        | C & D |
| 4       | Construction of link road from Kundion to Toka Jhabha Basti Km. 0/0 to 1/600. (SH:- C/o 5/7 mtrs. Wide road in km 0/0 to 1/375) (Deposit work)                           | Rs.<br>4,92,045/- | Rs.<br>10,000/- | Three months | 350/-        | C & D |
| 5.      | R/R damage on link road to village Samon Kanyon Km. 0/0 to 1/500. (SH:- C/o R/Wall in Cement concrete from Km. 0/003 to 0/015) As desired by the road passing committee. | Rs.<br>4,28,570/- | Rs.<br>10,000/- | Three months | 350/-        | C & D |

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number and GST clearance certificate from GST deptt.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number.
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis.
10. Only Two tender form will be issued to one contractor.

  
Executive Engineer,  
Paonta B&R Division,  
HP. PWD., Paonta Sahib.

Dated:- 05-07-2022

No.PWP/CB-Tender Notice/2022-23- 5317-66

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
- 10 Notice Board.

  
Executive Engineer,  
Paonta B&R Division,  
HP. PWD., Paonta Sahib.

Job No-1

| Schedule of Quantities                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Estimated Cost:- Rs. 4,40,826/- only |         |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------|---------|
| Name of work:- A/R & M/O Ajoli Kisharikot Road Km.0/0 to 2/0 (SH)-Construction of extra road diversion for safety of School students km 0/0 to 0/150. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Earnest money :- Rs.1000/- only      |         |
| S.No                                                                                                                                                  | Sub head and items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Time allowed:- Three months          |         |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rate in                              | Unit    |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Figures                              | Words   |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Qty                                  | Amount  |
| 1                                                                                                                                                     | Providing laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with 3-wheeled static roller 8-10 tonnes in stages to proper grade and chamber applying and brooming crushable screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-2 as per technical specification clause 405, WBM Grading-II including all leads, lifts and carriage of materials, as per the direction and entire satisfaction of Engineer-in charge. | 55.13                                | Per Cum |
| 2                                                                                                                                                     | Providing laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base /base course on well prepared surface and compacting with vibratory roller to achieve the desired density, in all leads and lifts to entire satisfaction of Engineer-in charge.                                                                                                                                                               | 51.98                                | Per Cum |
| 3                                                                                                                                                     | Providing and applying primer coat with Bitumen emulsion (SS-1) grade on the prepared surface of granular base including cleaning of road surface and spraying primer @0.70-1.00 kg / sqm using mechanical means as per technical specification clause 502 including all leads, lifts and carriage of materials, as per the direction and entire satisfaction of Engineer-in charge.                                                                                                                                                                                                                                      | 488.25                               | per sqm |
| 4                                                                                                                                                     | Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor @ 0.25 to 0.30 kg as per sqm on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per Technical specification clause 503 including all leads, lifts and carriage of materials, as per the direction and entire satisfaction of Engineer-in charge.                                                                                                                                                                                                                                          | 488.25                               | per sqm |
| 5                                                                                                                                                     | Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction, in all leads and lifts to the entire satisfaction of Engineer-in charge.                                                                                                                                  | 14.65                                | per sqm |
| Total                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                      |         |

  
 S. G. R. DIVAKAR H.E. P.D.  
 District Engineer

| Schedule of Quantities                                                                                                                                         |                                                                                                                                                                                                                                |        |                             | Estimated Cost:- Rs. 4,84,535/- only |        |       |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----------------------------|--------------------------------------|--------|-------|
| Name of work:- A/R & M/O Ajoli Kishankor road km 0/0 to 2/0 (SH-P/L top layer 0.50 mm thick repair in PCC [1:2:4] of existing cement road in km.0/500 to 1/0). |                                                                                                                                                                                                                                |        |                             | Earnest money :- Rs.10000 /- only    |        |       |
| S.No                                                                                                                                                           | Sub head and items of work                                                                                                                                                                                                     | Qty    | Time allowed:- Three months |                                      | Amount |       |
|                                                                                                                                                                |                                                                                                                                                                                                                                |        | Figures                     | Words                                |        |       |
|                                                                                                                                                                |                                                                                                                                                                                                                                |        |                             | Rate in                              | Unit   |       |
| 1                                                                                                                                                              | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work up to plinth level : 1:2:4 (1 cement : 2.coarse sand): 4 graded stone aggregate 20mm nominal size) | 81.375 |                             | per sqm                              |        |       |
|                                                                                                                                                                |                                                                                                                                                                                                                                |        |                             |                                      |        | Total |

Executive Engineer,  
Paonta B&R Division,  
HP, PWD, Paonta Sahib.

Job No-3

| Schedule of Quantities                                                                                                |                                                                                                                                                                                                                                                                                                        |       |                             |       | Estimated Cost:- Rs. 4,84,535/- only |        |
|-----------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------------------------|-------|--------------------------------------|--------|
| Name of work:- A/R & M/O Ajoli Kishankot road km 0/0 to 2/0 (SH-P/L) top layer 0.50 mm thick in PCC km 0/0 to 0/500). |                                                                                                                                                                                                                                                                                                        |       |                             |       | Earnest money :- Rs.10000/- only     |        |
| S.No                                                                                                                  | Sub head and items of work                                                                                                                                                                                                                                                                             | Qty   | Time allowed:- Three months |       | Rate in                              |        |
|                                                                                                                       |                                                                                                                                                                                                                                                                                                        |       | Figures                     | Words | Unit                                 | Amount |
| 1                                                                                                                     | Construction of unlined surface drains of average cross sectional are 0.20 sqm in soil & ordinary rock to specified lines grades levels and dimensions excavated materials to be used in embankment with a lift upto 3m and lead of 50m. (Average lead 25m) as per technical specification clause 307. | 81.38 |                             |       | per sqm                              |        |
| Total                                                                                                                 |                                                                                                                                                                                                                                                                                                        |       |                             |       |                                      |        |

Executive Engineer,  
 Paonta B&R Division,  
 HP PWD, Paonta Sahib.

Job No-4

**SCHEDULE OF QUANTITIES.**

| SCHEDULE OF QUANTITIES.                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |          |                  |         |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|----------|------------------|---------|
| Name of work:- Construction of link road from Kundion to Toka Jhabha Basti km. 0/0 to 1/600 (SH:-C/O 5/7 mtrs.wide road in km. 0/0 to 1/375). (Deposit work). |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |          |                  |         |
| Estimated Cost :- Rs.4,92,045/- ONLY.                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |          |                  |         |
| Earnest Money :- Rs.9,800/- ONLY.                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |          |                  |         |
| Time Allowed :- Three Months.                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |          |                  |         |
| S.No.                                                                                                                                                         | Sub head and items of work.                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity. | Rate in  | Unit.            | Amount. |
|                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           | Figures. |                  |         |
| 1                                                                                                                                                             | Excavation in soil in hilly area by mechanical mens including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m(one point five metre) and a lead upto 20m(twenty metre) as per technical specification clause 1603.1, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.                                                                    | 1227.75   |          | Per cubic metre. |         |
| 2                                                                                                                                                             | Construction of embankment with approved material deposited at site from roadway cutting and foundation of other structure graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5, including all leads, lifts an carriage of materials, asper entire satisfaction of Engineer-in-charge.                                                                                               | 1227.75   |          | Per cubic metre. |         |
| 3                                                                                                                                                             | Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m(one point five metre) transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 with a lead upto 1000 m(one thousand metres) as per technical specification clause 301.5, including all lead lifts and carriage of materials, as per entire satisfaction of Engineer-in-charge. | 559.85    |          | Per cubic metre. |         |
|                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |          | Total:-Rs.       |         |

**NOTE:-** The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of HP. Letter No.PBW(E)(C)17/2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.

  
Executive Engineer,  
Pooncha B&R Division,  
HP PWD, Pooncha Sahib.

Job No-5

| Schedule of Quantities                                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Estimated Cost:- Rs. 4,28,570/- only |         |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------|---------|
| Name of work:- R/R damage on link road to village samon kanyon km.0/0 to 1/500(Site: C/O R.wall in c.cont from km.0/003 to 0/015)As disired by the road passing committee. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Earnest money :- Rs.10000/- only     |         |
| S.No                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Time allowed:- Three months          |         |
| Sub head and items of work                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Rate in                              |         |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Figures                              | Words   |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Qty                                  | Unit    |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                      | Amount  |
| 1                                                                                                                                                                          | Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres dressing of sides and bottom and back filling trenches with excavated suitable material including all leads, lifts and carriage of materials, as per the direction and entire satisfaction of Engineer-in-charge. | 20.28                                | Per Cum |
| 2                                                                                                                                                                          | Centering and shuttering including strutting, propping etc. and removal of form work for Retaining wall, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, kerbs and steps etc. front in all leads and lifts to entire satisfaction of Engineer-in-charge.                                                                                                                                          | 93.408                               | Sqm.    |
| 3                                                                                                                                                                          | P/L c.cont. for plain/RC in open foundation's complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (1:4:8) including all leads, lifts and carriage of materials, as per the direction and entire satisfaction of Engineer-in-charge.                                                                                                                                                                                                 | 69.66                                | Per Cum |
| 4                                                                                                                                                                          | Providing weep holes in brick masonry/stone masonry/plain/reinforced concrete abutments, wing walls, return walls with 100 mm dia PVC pipes extending through the full width of the structure with slope of 1:6/120 H towards drawing face complete including all leads lift and carriage of materials, as per the direction and entire satisfaction of Engineer-in-charge.                                                                                         | 37.00                                | Each    |
| 5                                                                                                                                                                          | Providing and laying filter media with granular crushed aggregate as per specification to thickness of not less than 600 mm with smaller size towards the soil and bigger size towards wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted top firm condition complete as per drawing and technical specification in all leads and lifts to the entire satisfaction of Engineer-in-charge.             | 23.04                                | Per Cum |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Total                                |         |

Executive Engineer,  
Poonja B&R Division  
Type BWD, Poonja Sahib.