



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23- **-10923-32**
To

Dated:- **22-08-2022**

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.**

Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.

Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041


Fax No. 01972-288041.

NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **02-09-2022 up to 10.30 A.M.** and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **31-08-2022 upto 4.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **01-09-2022** during office hours till **4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	Alternation/Modification in Type-III Quarter at P.W.D. Colony for Temporary Accommodation of Tehsil and Treasury Office in View of Proposed Construction of Mini Secretariat Barsar Mehre. (SH:- C/O Toilet Block, C.C. Work - Masonry, Plastering etc) (Deposit Work).	Rs. 4,56,260.00 Only	Rs. 9,200.00 Only	Two Months
2	Alternation/Modification in Type-III Quarter at P.W.D. Colony for Temporary Accommodation of Tehsil and Treasury Office in View of Proposed Construction of Mini Secretariat Barsar Mehre. (SH:- Balance Work of Toilet Block W.S. & S.I, P/F Door, Tile Flooring, Plastering, Distempering etc) (Deposit Work).	Rs. 4,86,478.00 Only	Rs. 9,800.00 Only	Two Months
3	Repair and Maintenance of Residential Building at Barsar. (SH:- P/L Paver Block and Gate etc).	Rs. 3,72,687.00 Only	Rs. 7,500.00 Only	One Month
4.	Restoration of Rain Damages on Various Road Under HPPWD Sub Division Barsar. (Section Barsar-I & II). (SH:- Hiring of Excavator-Cum-Loader D-76 for Removal of Slips, Maintenance of Road Berms and Drain etc at Various Road at Various RDs).	Rs. 4,41,000.00 Only	Rs. 8,900.00 Only	Two Months
5	A/R & M/O Various Road Under HPPWD Sub Division Barsar. (SH:- P/F Dual Direction Delineators and Road Stud Dual Directional Retro Reflecting Cat eyes Studs on Various Road at Various RDs).	Rs. 1,70,043.00 Only	Rs. 3,400.00 Only	One Month

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
Barsar Division
HPPWD Barsar.


On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-105/2022-23-

1075522 dated 22/8/2022


Executive Engineer
Barsar Division
HPPWD Barsar.

Schedule of quantity

Job No 1

Name of work:-Alteration/Modification in Type-III quarters at PWD Colony for temporary accomodation of Tehsil &

Estimated cost Rs:-456260.00

Treasury office in view of proposed construction of Mini Secretariate at Barsar (Mehre)

Earnest money Rs:- 9200.00

(SH:- C/O Toilet Block , C.C work , Masonary Plastering etc. (Deposit work)

Time Limit :- Two Month

Sr.No	Discription of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures		words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) (including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(Fifty metre) in ordinary rock including carriage of materials within all leads and lifts . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	18.89	cubic metre			Per cubic Metre	
2	Stone soling properly hand packed filling intersties with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	14.25	Cubic metre			Per Cubic Metre	
3	Providing and laying 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm (twenty millimetre) nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	10.82	Cubic metre			Per Cubic Metre	
4	Providing and laying 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm (Fourty millimetre) nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	2.11	Cubic metre			Per Cubic Metre	
5	Providing and laying 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm (Twenty millimetre) nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	13.04	Cubic metre			Per Cubic Metre	

6	Providing and laying for steel reinforcement made of TISCON ,SAIL, TATA JINDAL steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax, GST or any other taxes imposed by the Government.	304.80	Kilogram			Per Kilogram
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in Cement mortar 1:6 (one cement : six coarse sand) in super structure above plinth level up to all floors level including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	21.40	cubic metre			Per cubic metre
8	Providing and laying 15 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement : Six coarse sand) upto all floors levels including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	112.93	Square metre			Per square metre
9	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with cement mortar 1:6 (1 cement : 6 coarse sand) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	4.05	cubic metre			Per cubic metre
10	Providing and fixing second class teak wood in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	0.29	cubic metre			Per cubic metre
						Total:-



Executive Engineer
Barsar Division
HPPWD Barsar



Schedule of quantity

Job No 2

Name of work:-Alteration/Modification in Type-III quarters at PWD Colony for temporary accommodation of Tehsil & Treasury office in view of proposed construction of Mini Secretariate at Barsar (Mehre)

Estimated cost Rs:-486478.00

Earnest money Rs:- 9800.00

Time Limit :- Two Month

(SH:- Balance work of Toilet Block , W.S & S.I , P/F Door , Tile flooring, Plastering , Distempering etc. (Deposit work)

Sr.No	Discription of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	12.70	Square metre		Per Square metre	
2	Providing and fixing 35 mm (thirty five millimetre) thick glazed shutters for doors, windows and clerestory windows second class teak wood using 4 mm (four millimetre) thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	12.70	Square metre		Per Square metre	
3	Providing and fixing 200x10 mm (Two hundred into ten millimetre) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 (Ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	4.00	Numbers		Each	
4	Providing and fixing 125 mm (one hundred twenty five millimetre) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	6.00	Numbers		Each	
5	Providing and fixing 100 mm (one hundred millimetre) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	10.00	Numbers		Each	

6	Providing and laying 600x600 mm (Six hundred into six hundred millimetre) vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (Twenty millimetre) thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram/ square metre) including grouting the joints with white cement and matching pigments etc. complete including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	158.70	Square metre			Per Square metre
7	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm (Twelve millimetre) thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg (Three point three kilogram)per sqm including pointing in white cement mixed with pigment of matching shade complete including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	36.00	Square metre			Per Square metre
8	Providing and fixing 0.60mm (zero point sixty millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns (twenty microns) over 5 microns (five microns) primer coating to back coat of polyester of 5 microns (five microns) over 5 microns (five microns) primer coating i/c fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	36.00	Square metre			Per square metre
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-charge. including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	480.00	Kilogram			Per Kilogram
10	Providing and fixing 15 mm (fifteen millimetre) dia nominal bore G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	20.00	Metre			Per running metre

11	Providing and fixing 110mm (one hundred ten millimetre) nominal size high pressure made of Paryware , Hindware , Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	45.00	metre				per running metre	
12	Providing and fixing vitreous Chiana wash down water closet (European Type W.C pan) made of Paryware , Hindware , Cera with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (one cement : one sand) seat and cover to be paid for separately Ordinay closet or equivalent including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2.00	Numbers				Each	
13	Providing and fixing 8 mm (eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	2.00	Numbers				Each	
14	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimetre) dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required white Vitreous China Wash basin size 550x400 mm (five hundred fifty into four hundred millimetre) with a 15 mm(fifteen millimetre) CP Brass single hole basin mixer including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	1.00	Numbers				Each	
15	Providing and fixing white vitreous china squatting plate urinal with integral rim longitudinal flush pipe including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	2.00	Numbers				Each	
16	Providing and fixing 10 (ten) litre capacity - White P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	2.00	Numbers				Each	

17	Providing and fixing 15mm (fifteen millimetre) nominal bore C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	6.00	Numbers			Each	
18	Providing and fixing 15mm (fifteen millimetre) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms (six hundred ninety grams) including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	3.00	Numbers			Each	
						Total:-	

(Signature)

Executive Engineer
Barsar Division
HPPWD Barsar

Job No-3

Schedule of Quantity

Estimated Cost Rs:- 3,72,687.00

Earnest Money Rs:-7500.00

Name of Work:- Repair & maintenance of Residential building at Barsar

(SH:- P/L Paver block & Gate etc.)

Time Limit :- one month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words			
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) (including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. (Fifty metre) in ordinary rock including carriage of materials within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.00	cubic metre		Per cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement : three Sand : six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.00	Cubic metre		Per Cubic Metre	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in Cement mortar 1:6 (one cement : six coarse sand) in super structure above plinth level up to all floors level including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	0.69	cubic metre		Per cubic metre	
4	Providing and laying 15 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement : Six coarse sand) upto all floors levels including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	14.40	Square metre		Per square metre	
5	Finishing walls with water proofing cement paint of required shade old work (one or more coats applied @ 2.20 kg/10 sqm (Two point twenty kilogram /ten square metre) over priming coat of primer applied @ 0.80 litres/10 sqm (Zero point eighty litres/ ten square metre) complete including cost of Priming coat including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	90.00	Square metre		Per square metre	

6	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 60 mm(sixty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	120.00	Square metre			Per Square Metre
7	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can presibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	4.54	Cubic metre			Per Cubic Metre
8	Providing and fixing stainless steel (Grade 304) (Grade three hundred four) railing made of Hollow tubes, channels, plates etc. including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc. including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	108.00	Kilogram			Per Kilogram
9	Stone soling properly hand packed filling intersties with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	12.00	Cubic metre			Per Cubic Metre
						Total:-



Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- Restoration of rain damages on variours road under HPPWD Sub Division Barsar
(Section Barsar 1&11) (SH:- Hiring of Excavator Cum Loader D-76 for removal of slips,
maintenance of road berms and Drain etc. at various road at various Rd.s)

Job No- 4

Estimated cost Rs:- 4,41,000.00

Earnest money Rs:- 8900 .00

Time Limit :- Two Month

Sr.No	Discription of item	Quantity	Unit	Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figures	words		
1	Hiring of machinery excavator cum loader to be deployed for removal of slips including cost of fuel oil lubricant and wages of operation staff will be carried out the owner at his risk and cost including shifting of machinery from one place to other required location actual working hours will be accounted for the pavement and six hours per day working will be required average minimum 20cum(twenty cubic metre) excavation in all kind of soil including loading in tipper / truck and disposal of the same in all leads lifts and carriage of materials shifting of material as per site requirement and direction of the Engineer -in Charge. The contractor will be responsible for any mishappening and working of hour Conditions :- 1 Log book shall be maintained by the department and shall be the part of agreement at the time of bills. 2. Working hour shall be 9.00 to 5.00 PM. 3. Output of the Machinery shall be compare with market rate in case of less out put shall be deducted accordingly. 4. No payment will be made for idle days and machinery under repair 5. No fuel and lubricants supplied by the department..	450.00	Hour			Per Hour	
						Total:-	

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Job No 5

Name of work:-A/R & M/O on various road under HPPWD Sub Division Barsar


Estimated cost Rs:-170043.00

(SH:- P/F Dual Delineators and road stud dual directional retro reflecting cat eyes studs on various road at various Rds)

Earnest money Rs:- 3400.00

Time Limit :- One Month

Sr.No	Discription of item	Quantity		Rate inclusive all taxes I/c G.S.T		Unit	Amount
		100.00	Numbers	Figures	words		
1	Providing and fixing dual direction delineator made of dia 18G (eighteen gauge) MS rectangular pipe of size 25 x 63mm (twenty five x sixty three millimetre) and of length 600 mm (six hundred millimetre) pipe stove enameled and baket to 120 (one hundred twenty) power coated head made of ABC plastic rectangular moulded with flat face provided with high intensity prismatic reflectors of colour (white/Yellow/Red) of size 100 x 125 mm (one hundred x one hundred twenty five millimetre) with additional to reflective strips of 20mm (twenty millimetre) wide make green light as per the direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	100.00				Each	
2	Providing and fixing road studs dual directional retro reflective cat eyes studs made for high quality colour less retro reflective mini board embedded to 6mm high (six millimeter) impact plastic eyes of dia 16mm (sixteen millimeter) containing 7(seven) beads to each thus making a total of 42(forty two) beads housed on both side in a strong aluminum castes stud size 10x10cm(ten into ten centimeter) provided with a mild steel zinc plated nail of dia 12mm (twelve millimeter) for fixing of roads by hammering made green/ lite only as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	175.00	Numbers			Each	
						Total	


 Executive Engineer
 Barsar Division
 HPPWD Barsar