

**Himachal Pradesh  
Public Works Department**

No. PW-SKT-CB -Tender/2022-23

8336

Dated:- 16/08/2022

To,

✓ The Executive Engineer I.T. Cell,  
Nigam Bihar Shimla -2

**Subject:-**

**Publishing of Notice inviting tenders.**

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 27.08.2022 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

**DA:-As above**

  
**Executive Engineer,  
Sarkaghat Division  
HP.PWD.Sarkaghat**

**Himachal Pradesh**  
**Public Works Department**  
**"Notice Inviting Tender"**

Sealed item rate tender are hereby invited in form No. 6&7 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968.The important dates of tender are as under:-

The last date and time of receipt of application for tender form 27.08.2022 up to 4.00 P.M.

The last date for sale of tender is up to 29.08.2022 at 4.00PM.

The tender shall be received up to 11:00 AM on 30.08.2022 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 30.08.2022. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.


| Sr. No. | Name of work                                                                                                                                                                                                       | Estimat ed cost. | Earnest Money. | Cost of form. | Time allowed. |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|----------------|---------------|---------------|
| 1.      | Construction of Play Ground at GMS Gounta Sub- Tehsil Bhadrola Distt. Mandi (HP) (SH:- Cutting in front of Primary School i/c C/O Edge wall in front of School and Road R/wall toward Road side L-18.00 to 38.0 M) | 474077           | 9500           | 350           | One Month     |
| 2.      | Construction of Play Ground at GMS Gounta Sub- Tehsil Bhadrola Distt. Mandi (HP) (SH:- Construction of stage in Masonry including roofing work)                                                                    | 480561           | 9600           | 350           | One Month     |

**TERMS AND CONDITONS:-**

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
8. The tender shall be awarded to the lowest bidder without any negotiation if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The earnest money shall be deposited duly pledged in favour of Executive Engineer B& R Division HPPWD Sarkaghat & Cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.

10. All the required documents should be submitted with the application others wise single application may be rejected.  
11. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.

  
Executive Engineer,  
Sarkaghat Division  
HP.PWD, Sarkaghat.

No. PW-SKT-CB-Tender/2022-23

8329-35

Dated: 16/08/2022

1. The Engineer - in- Chief HPPWD Nirman Bhawan Shimla for information please.
2. The Chief Engineer Hamirpur Zone HP.PWD . Hamirpur for information please.
3. The Superintending Engineer Dharampur Circle, HP.PWD. Dharampur for information please.
4. Block Development officer Sarkaghat for information please.
5. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
6. Copy to Drawing Branch of this office for information.
7. Notice Board.

Executive Engineer,  
Sarkaghat Division  
HP.PWD, Sarkaghat.

## SCHEDULE OF QUANTITY

Name of Work:- Construction of Playground at GMS Gounta Sub Tehsil- Bhadrota Distt-Mandi (HP) (SH:- cutting in front of Primary School i/c  
C/O Edge wall in front of School and R/wall towards road side L-18.00 to 38.0 M)

Rs.474077/-

Estimated cost :-

Rs.9500/-

Earnest Money:-

One month

Time Limit

| Sr.N<br>o | Description of item/Sub Head                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Rate      |          | Unit            | Amount |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|----------|-----------------|--------|
|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          | In Figure | In words |                 |        |
| 1         | Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with a lift upto 1.50 metre and lead upto 20 metre as per clause 1603.02.and as per direction of Engineer-in-Charge.                                                                                                                                                                                                                    | 225.00   |           |          | Per cubic metre | 0      |
| 2         | Earth work in excavation in all kind of classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and direction of Engineer-in-charge complete.                              | 34.15    |           |          | Per cubic metre | 0      |
| 3         | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) with in all lead and lift and as per the direction of Engineer -in -charge.                                                                                                                                                                                       | 54.50    |           |          | Per cubic metre | 0      |
| 4         | Random rubble masonry in cement mortar 1:6 (one cement : six sand) for sub structure complete as per drawing and technical specification clause 702, 704, 1202 and 1204 as per drawing and HP ,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                                                                                                                                                                      | 20.55    |           |          | Per cubic metre | 0      |
| 5         | Construction of subgrade and earthen shoulderwith approved material obtain from borrow pits with all lift and lead transporting to site spreading,grading to require slope and compacting to meet requirement of table 300.2 as per technical specification clause 303.1 as per the direction of Engineer-in-charge.                                                                                                                                                                               | 64.60    |           |          | Per cubic metre | 0      |
| 5         | Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm ( One hundred ) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. | 36       |           |          | Each            | 0      |
| 6         | Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.                                                                                                                                                                                                         | 24.00    |           |          | Per cubic metre | 0      |
|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |           |          | Total:-         |        |

  
Executive Engineer  
B & R Division HPPWD  
Sarkaghat

## SCHUDULE OF QUANTITY

NAME OF WORK :- Construction of playground at GMS Gounta Sub Tehsil Bhadrota Distt. Mandi HP (SH:-construction of Stage in Masonry including roofing work )

Rs. 4,80,561/-

Rs. 9600/-

One month

Estimated cost :-

Earnest money:-

Time allowed:-

| Sr.No | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Quantity | Rates     |          | Unit    | Amount |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|----------|---------|--------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          | In figure | In words |         |        |
| 1     | Providing and fixing 0.62mm (Zero point six two millimetre) thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) rganic coating of 20 (Twenty) microns over 5 ( five) microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating including fixing with screws, preapainted iron J or L hooks, bolts and nuts 6mm(six milimetre) dia with preapainted limpet and rubber washer within all lead and lift and as per the direction of Engineer-in-charge. | 85.80    |           |          | per sqm |        |
| 2     | Providing and fixing ridges or hips 60 cm overall with 0.60mm thick preapainted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with preapainted iron J or L hooks, bolts & nuts 6mm dia & repainted G.I. limpet and bitumen washers complete with all accessories within all lead and lift and as per the direction of Engineer-in-charge.                   | 23.40    |           |          | Per Rmt |        |
| 3     | Providing and fixing M.S. BP Sheet 1.66mm to 2.00 mm thick in eaves board/facial/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately)                                                                                                                                                                                                                                              | 99.66    |           |          | per sqm |        |
| 4     | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works                                                                                                                                                                                                                                                                                  | 1193.07  |           |          | per Kg  |        |
| 5     | Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture                                                                                                                                                                                                                          | 76.06    |           |          | per sqm |        |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |           |          | Total:- |        |

Executive Engineer,  
B&R Division,  
HP PWD, Sarkaghat.