

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2022-23

9001

Dated:- 30/08/2022

To,

✓ The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 06.09.2022 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above

✓
Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

Himachal Pradesh
Public Works Department
"Notice Inviting Tender"

Sealed item rate tender are hereby invited in form No. 6&7 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968. The important dates of tender are as under:-

The last date and time of receipt of application for tender form 07.09.2022 up to 4.00 P.M.

The last date for sale of tender is up to 08.09.2022 at 4.00PM.

The tender shall be received up to 11:00 AM on 09.09.2022 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 09.09.2022. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimat ed cost.	Earnest Money.	Cost of form.	Time allowed.
1.	Restoration of Rain Damages on Chandesh Maseran via Batoh Road Km. 0/0 to 10/600 (SH:- Construction of R/wall in wire crate at RD 9/100 to 9/110)	410856	8300	350	15 days
2.	Restoration of Rain Damages on Chandesh Maseran via Batoh Road Km. 0/0 to 10/600 (SH:- Construction of R/wall in wire crate at RD 9/110 to 9/118)	331104	6700	350	15 days
3.	Restoration of Rain Damages on various Roads under the jurisdiction of Sarkaghat Sub Division HPPWD Sarkaghat (SH:- Hiring of Excavator cum loader for removal of slips/debries on various Roads)	208000	4200	350	One Month
4.	Construction of Link Road to Negi Basti Village Langehar (SH:- Providing and laying Tarring in Km. 0/0 to 0/313)	316130	6400	350	One Month
5.	Restoration of Rain Damages on various Roads under the jurisdiction of Sarkaghat at Sub Division HPPWD Sarkaghat (SH:- Hiring of Tipper for carriage of material for removal of slips and other various work)	96000	2000	350	One Month
6.	Restoration of rain Damages on Patrighat Jawali Gehra Panyali Road Km. 0/0 to 11/375 Portion 6/0 to 11/375 (SH:- C/O R/wall in wire crates at RD 8/795 to 8/801)	402516	8100	350	15 days
7.	Restoration of rain Damages on Patrighat Jawali Gehra Panyali Road Km. 0/0 to 11/375 Portion 6/0 to 11/375 (SH:- C/O R/wall in wire crates at RD 8/801 to 8/806)	336780	6800	350	15 days

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for, not having more than two works in hand in the shape of affidavit duly attested by the competent authority.

4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
8. The tender shall be awarded to the lowest bidder without any negotiation if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The earnest money shall be deposited duly pledged in favour of Executive Engineer B& R Division HPPWD Sarkaghat & Cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
10. All the required documents should be submitted with the application others wise single application may be rejected.
11. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat

Dated: 30/08/2022

No. PW-SKT-CB-Tender/2022-23

8994-9000


1. The Engineer - in- Chief HPPWD Nirman Bhawan Shimla for information please.
2. The Chief Engineer Hamirpur Zone HP.PWD . Hamirpur for information please.
3. The Superintending Engineer Dharampur Circle, HP.PWD. Dharampur for information please.
4. Block Development officer Sarkaghat for information please.
5. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
6. Copy to Drawing Branch of this office for information.
7. Notice Board.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat

1

Schedule of Quantity

Name of work:- Resoration of rain damages Chandesh Maseran via Batoh road km 0/0 to 10/600 (SH:-Construction of R/wall in wire crate at RD 9/100 to 9/110)					Estimated Cost:-	
					Earnest money:-	Rs.4,10,856/-
					Time allowed:-	Rs. 8,300/-
						45 days
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m.(One point five metre) .All kinds of soil including all leads and lifts and as per the direction of Engineer-in-Charge.	18.24			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates made with 4 mm(four millimetre) dia GI wire conforming to IS:280 (IS : Two hundred eighty)and IS : 4826 (IS : four thousand eight hundred twenty six) in 100mm x100mm (one hundred millimetre into one hundred millimetre) mesh (weaved diagonally) including 10% (ten per cent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogramme) including carriage of materials with in all leads and lifts complete in all respects as per the direction Engineer-in- charge.	107.50			Per cubic metre	
3	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	21.19			Per cubic metre	
					Total	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

Name of work:- Resoration of rain damages Chandesh Maseran via Batoh road km 0/0 to 10/600 (SH:-Construction of R/wall in wire crate at RD 9/110 to 9/118)

Schedule of Quantity


Name of work:- Resoration of rain damages Chandesh Maseran via Batoh road km 0/0 to 10/600 (SH:-Construction of R/Wall in wire crate at RD 9/110 to 9/118)									
Schedule of Quantity									
Sr. No.	Description of item	Quantity	Estimated Cost:-		Time allowed:-	Unit	Amount		
			Earnest money:-						
			In figure	In words					
1	Earth work in excavation by /manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m.(One point five metre) .All kinds of soil including all leads and lifts and as per the direction of Engineer-in-Chrage.	18.24			15 days	Per cubic metre			
2	Providing and laying of boulder apron laid in wire crates made with 4 mm(four millimetre) dia GI wire conforming to IS:280 (IS : Two hundred eighty)and IS : 4826 (IS : four thousand eight hundred twenty six) in 100mm x100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten per cent) extra for laps and joints laid with stone boulders weighting not less then 25 kg (Twenty five kilogramme) including carriage of materials with in all leads and lifts complete in all respects as per the direction Engineer -in- charge.	86.40				Per cubic metre			
3	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	17.28				Per cubic metre			
						Total			

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY


NAME OF WORK :-Resoration of rain damages various roads under jurisdiction of Sarkaghat Sub Dision
 IPPWD Sarkaghat (SH :- Hiring of Excavator Cum Loader for Removal of slips/ debries on various roads))

Sr.No	Description of item/Sub Head	Estimated cost :-				
		Earnest Money:-		One Month		
		Time Limit	Rates	Unit	Amount	
		In Figure	In words			
1	2	4	5	6	7	
1	Hiring of Excavator cum loader for cutting work disposal not less then 30 cubic metre per hour including pay of operators, P.O.L charges, maintenance or any minor or major accidents, and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charges.	160.00		Per Hour		


 Executive Engineer,
 Sarkaghat Division,
 HP.PWD, Sarkaghat

Schedule of Quantity

Schedule of Quantity							
Name of work:-Construction of link road to Negi Basti Village Langehar(SH:-providing /laying Tarring in km 0/0 to 0/313) Length-313 mtr. (Under Miner Head)					Estimated Cost:-		Rs. 3,16,130/-
					Earnest money:-		Rs. 6,400/-
					Time allowed :-		one months.
Sr. No.	Description of item	Quantity	Rate		Unit	Amount	
			In figure	In words			
1	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications On W.B.M. @ 0.75 Kg / sqm (zero point seven five killogramme square metre)within all leads, and other incidentals.	782.50			Per square metre		
2	2 cm(two centimetre) premix carpet surfacing with 1.8 cum (one point eight cubic metre) and 0.90 cum (zero point nine zero cubic metre)of stone chippings of 13.2 mm (thirteen point two millimetre) size and 11.2 mm (eleven point two millimetre)size respectively per 100 sqm(hundred square metre) and 52 kg (fifty two killogramme)and 11.2 mm (eleven point two millimetre) of hot bitumen per cum of stone chippings of 13.2 mm (thirteen point two millimetre)and 11.2 mm (eleven point two millimetre)size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etcetra. complete (tack coat to) be paid for separately) With paving Asphalt grade VG-10 heated and then mixed with solvent at the Rate of 70grams per kg of asphalt as per drawing and HP PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.	782.50			Per square metre		
3	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm (two point three six millimetre and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete including hauling/carriage of material through all modes of transportation within all leads, lifts and other incidentals.	782.50			Per square metre		
					Total:-		


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of rain damages on various roads under the jurisdiction of Sarkaghat at Sub - Division HPPWD Sarkaghat (SH:- Hiring of tipper for carriage of material for removal of slips and other various work).

Estimated cost :- Rs. 96000/-
Earnest Money:- Rs. 2,000/-
Time Limit One month


Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Hiring of Tipper for disposal of excavated material and other material. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge with in all leads and lifts	24			Per Day	
					Total:-	

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

Schedule of Quantity

Name of work:- Resoration of rain damages Patrighat Jawali Gehra Panyali road km 0/0 to 11/375 (portion 6/0 to 11/375 (SH:- Construction of R/wall in wire crate at RD 8/795 to 8/801)

11/375 (SH:-Construction of R/wall in wire crate at RD 8/795 to 8/801)						Estimated Cost:-		Rs.4,02,516/-
						Earnest money:-		Rs. 8,100/-
						Time allowed:-		15 days
Sr. No.	Description of item	Quantity	Rate		Unit	Amount		
			In figure	In words				
1	Earth work in excavation by manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m.(One point five metre) .All kinds of soil including all leads and lifts and as per the direction of Engineer- in-Charge.	24.30			Per cubic metre			
2	Providing and laying of boulder apron laid in wire crates made with 4 mm(four millimetre) dia GI wire conforming to IS:280 (IS : Two hundred eighty)and IS : 4826 (IS : four thousand eight hundred twenty six) in 100mm x100mm (one hundred millimetre into one hundred millimetre) mesh (weaved diagonally) including 10% (ten per cent) extra for laps and joints laid with stone boulders weighting not less then 25 kg (Twenty five kilogramme) including carriage of materials with in all leads and lifts complete in all respects as per the direction Engineer -in- charge.	105.84			Per cubic metre			
3	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads, and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	16.20			Per cubic metre			
					Total			


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

Bill Schedule of Quantity	
Name of work:-	Restoration of rain damages Pairighat Jawali Gehra Panyali road km 0/0 to 11/375 (portion 6/0 to 11/375 (SH:-Construction of R/wall in wire crate at RD 8/801 to 8/806)

Draft schedule of Quantity

11/375 (SH: -Construction of R/wall in wire crate at BD 8/801 to 8/806)
11/375 (SH: -Construction of R/wall in wire crate at BD 8/801 to 8/806)

Estimated Cost:-	Rs.3,36,780/-
------------------	---------------

Earnest money:-	Rs. 6,800/-
-----------------	-------------

Time allowed:-	15 days
----------------	---------

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation by manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m. (One point five metre) .All kinds of soil including all leads and lifts and as per the direction of Engineer-in-Charge.	20.25			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates made with 4 mm(four millimetre) dia GI wire conforming to IS:280 (IS : Two hundred eighty)and IS : 4826 (IS : four thousand eight hundred twenty six) in 100mm x100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten per cent) extra for laps and joints laid with stone boulders weighting not less then 25 kg (Twenty five kilogramme) including carriage of materials with in all leads and lifts complete in all respects as per the direction Engineer -in- charge.	88.20			Per cubic metre	
3	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	13.50			Per cubic metre	
					Total	

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.