

Himachal Pradesh
Public works Department

NO-PW-JDT-EA-I Tender NIT/2022-23:- 7680-82

Dated:- 18/08/22

To,

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender notice

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Pr. Sec.(PW)to the Govt.of HP letter No-PBW(B)A9(3)1/2020 dated Shimla -2the 16th july 2021 as the work mentioned in the tender notice are urgent in nature and public interest

DA:- Notice Inviting Tender


Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Copy forwarded the Superintending Engineer 10th Circle
Bilaspur HP PWD Bilaspur for information please

Copy forwarded to the Computer Cell O/O Executive Engineer
(IT Cell) Nigam Bihar Shimla -2 for information and further necessary action action


Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Certificate

Certified that the tenders called vide this office letter
No. PW-JDT EA-I-Tender /2022-23- 7669-79 dated
12/08/022 is emergent nature and in Public interest

Executive Engineer
Jhandutta Division
HPPWD Jhandutta

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage / item rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender
Form a/w requisite documents: -
2. Date of issue/sale of Tender forms against
Cash payment (Non-refundable):-

29/08/2022 up to 02:30 PM

30/08/2022 up to 03:00 PM

The tender shall be received up to **11:00A.M. on 31/08/2022** and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **31/08/2022**

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta. must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

S.No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit	D class
1.	C/O link road to Kaseh km 0/0 to 0/900 (SH:- Extension of 900 mm dia HPC at RD 0/020 along with both side wing wall) Under Deposit work	456592/-	9100/-	350/-	Three Month	D
2.	Repair of Govt. S.S. School at kalei Tehsil Jhandutta Distt. Bilaspur (SH:- Repair Ridge, Vellay & Guter etc.) Deposit work	196177/-	3900/-	350	Three Month	D
3.	C/O link road Bharoli Kallan to Jhunjru via Gurnadi km 0/0 to 8/00 (SH:- C/O R.C.C. slab culvert at RD 0/070 wearing course and Ralling etc.)	86294/-	1700/-	350/-	Three Month	D
4.	C/O Kothi Jungle Malhot road from Tehri to Malroun via Johar Kallian km 0/0 to 4/500 (SH:- C/O 900 mm dia HPC at RD 1/575 with both side W/Wall) Deposit Work HSP	245423/-	4900/-	350/-	Three Month	D
5.	C/O & M/T on link road from Baihi to Badgoun km 0/0 to 1/700 (SH:- P/L soling at RD 0/525 to 0/825) Under OTMNP	229861/-	4600/-	350/-	Three month	D
6.	Repair work at Health Sub-Centre Dohak GP Badgoun Gailu (SH:- C/O B/Wall, P/L flooring tiles, Sanitary works etc) Deposit Work	417959/-	8400/-	350/-	Three month	D
7.	Repair of patch work on Koshrian to Jaddu via Brahmani Kallan in km 0/0 to 14/600 (SH:- Repair of patch work in km 4/00 to 6/00)	431711/-	9070/-	350/-	One month	D
8.	M/T on Nakhlehra to Lular via Pasol road km 0/0 to 5/255 (SH:- R.O.F.D./ Cutting at RD 0/0 to 1/120)	316832/-	6300/-	350/-	Two month	D
9.	C/O link road Balh Chaloo to House of Prem Lal S/O Sh. Anant Ram km 0/0 to 1/500 (SH:- C/O cause way /cross Drainage including both side C.C Pavement at RD 0/0 to 0/165)	467803/-	9400/-	350/-	Three month	D
10.	C/O PHC Building at Marotan Tehsil Jhandutta Distt. Bilaspur HP (SH:- C/O Rain Harvesting storage Tank of 25000 ltr capacity.) Deposit Work	303802/-	6100/-	350/-	Three month	D
11.	C/O link road Dahad to Jabloo road km 0/0 to 3/00 (SH:- C/O Both side Wing Wall of Existing HPC at RD 2/850 Dahad side L=8.00 mtr, Jabloo side L=3.00 mtr & B/Wall at RD 2/850 to 2/860 (L=2.50 mtr)	342912/-	6900/-	350/-	Three month	D
12.	Repair of Health Sub- centre Building at Dholag or Rural Health Department (SH:- Repair of Slab, C/O B/Wall at RD 0/0 to 0/030 & Boundary wall)(Deposit work)	473605	9500/-	350/-	Two month	D
13.	Repair of patch work on Koshrian to Jaddu via Brahmani Kallan in KM 0/0 to 14/600 (SH:- repair of patch work in Km 2/00 to 4/00	431711/-	9070/-	350/-	Three month	D
14.	C/O link road from Main road to House of Bhaq Singh Jol Gharan	298656/-	5900/-	350/-	Three Month	D

15	Repair of Patch work on Koshrian to Jaddu via Brahmani Kallan in Km 0/0 to 14/600 (SH:- Repair of patch work in Km 12/00 to 14/600)	497541/-	10000/-	350/-	Three Month	D
16	M/T on link road Salwad to Baih Chalag Km 0/0 to 5/0 (SH:- M/T in Km 0/0 to 0/345)(Under OTMNP)	491245/-	9800/-	350/-	Three Month	D
17	C/O link road from Berthin Sargal road to house of Kargil Shaheed Sh. Mast Ram Km 0/0 to 1/000 (SH:- P/L soling at RD 0/775 to 1/000)(Under SCDP)	180938/-	3600/-	350	Three Month	D
18	C/O link road from Dahad to village Dehlwin road Km 0/0 to 3/0 (SH:- Formation cutting in KM 1/915 to 2/165)	152155/-	3000/-	350/-	Three Month	D
19	M/T on Nekhlara to Lullhar via pasol road Km 0/0 to 5/255 (SH:- R.O.F.D /cutting at RD 1/150 to 2/075)(Under NABARD)	366141/-	7300/-	350/-	Three Month	D
20	Repair of Patch on Koshrian to Jaddu via Brahmani Kallan in KM 0/0 to 14/600(SH: Repair of patch work in Km 6/000 to 8/00)	431711/-	9070/-	350/-	One Month	D
21	C/O link road from Dokru to Neri via Rohal Km 0/0 to 2/600 (SH:- Edging at various RDs 1/350 to 1/850 & C/O RCC Hume pipe culvert at RD 1/700 (Under SCDP)	328647/-	6600/-	350/-	Three Month	D

1The tender forms will not be issued to those contractors whose performance is not found Satisfactory.

2. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.

3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.

4. Application without all documents will not be entertained.

5. Proxy Application will not be entertained.

Executive Engineer
Jhandutta Division
HPPWD Jhandutta.

No-PW-JDT-CB-Tender NIT/2022-23:-

7669-79

Dated:-

18/08/022

Copy forwarded to the following for information and necessary action Please:-

1. The Engineer -in-Chief HP PWD Nirman Bhawan Shimla
2. All the Chief Engineer in HP PWD
3. The Superintending Engineer 10th Circle HP PWD Bilaspur
4. All the Assistant Engineer Working under this Division
5. The B.D.O Jhandutta
6. A/B & D/B in this office
7. Various Contractors working under this office
8. Notice Board

Executive Engineer
Jhandutta Division
HPPWD Jhandutta

1

Estimated cost: ₹ 456592.00	Only
Earnest Money: ₹ 9100.00	Only

Only

Amoco			
-------	--	--	--

1	Providing sweep beds in brick masonry /stone masonry, plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through full of width of the structure with slope of (V): 20 (twenty) (H) towards drawing face complete as per HPP&D specification including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour, cross, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	34.000	316.65	INR, three hundred sixteen and Paise six five Only	✓	10766.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1.204.3.4 including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour, cross, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	16.200	1265.65	INR, one thousand two hundred sixty five and Paise six five Only		20504.00
6	Providing and laying non-pressure NP 2 (two) class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement into two fine sand) including testing of joints etc. complete in 900 mm (nine hundred millimeter) dia R.C.C. pipe including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour, cross, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.000	3770.10	INR, four thousand three hundred seventy and Paise three zero Only		18851.00
Total:-		% age +/-				456592.00
Quoted Rate in Figures:-						✓
Quoted Rate in Words:-						

Executive Engineer
Bundara Division
HPP&D Bureau


SCHEDULE OF QUANTITY

Name of Work :- Repair of Govt. S. S. School at Kholi Tehsil Jhandutta District
Bhagpur (SH)- Repair Ridge, Vellay & Gutter etc.) Deposit work.

Estimated cost:- ₹ 196177.00 Only
Earnest Money:- ₹ 3900.00 Only
Time allowed:- Three Months

Name of Bidder :-

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Structural steel work erected, welded or welded in both top sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by the contractor shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	101.70	105 990	INR one hundred five and paise nine zero only	Per Kilo gram	100770.00
2	Providing and fixing M.S. BP Sheet 1.60mm to 2mm thick in eaves, bura/facia/raft/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-Charge. (Base members of steel work shall be measured & paid separately) including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by the contractor shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.70	1498.10	INR one thousand six hundred ninety eight and paise one zero only	Per square meter	4035.00
3	Providing and fixing plain multipurpose cement board/light pressure, steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid separately) 6 mm thick Cement fiber board as per IS: 14062 including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by the contractor shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	642.60	INR six hundred twelve and paise six zero only	Per square meter	9639.00
4	Providing and fixing 15 cm wide, 45 cm overall semi circular plain G.S. sheet gutter with iron brackets 40x40mm size, bolts, nuts and washers etc., including making necessary connections with rain water pipes complete 0.63 mm thick with zinc coating not less than 275 g/m ² including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by the contractor shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	71.40	595.90	INR five hundred ninety five and paise nine zero only	Per running meter	42547.00

5	Providing, uncoated G.S. sheet roofing including vertical / curved surface fixed with polyurethane coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. lampet washers or with G.I. lampet washers. Eased with white lead, including a coat of approved sand primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal) vertical or curved surfaces), excluding the cost of purfins, rafters and trusses and including cutting to size and shape wherever required 0.63 mm thick with zinc coating not less than 275 gsm / m ² including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	82.45	384.50 (NR eight hundred sixty one and paise five zero only)	Per square metre	78031.000
6	Providing ridges or hips of width 60 cm overall with plain G.S. sheet fixed with polyurethane coated J or L hooks, bolts and nuts 8 mm dia G.I. lampet and bitumen washers complete 0.63 mm thick with zinc coating not less than 275 gsm/m ² including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.40	704.99 (NR seven hundred forty eight and paise nine only)	Per running metre	10771.000
7	Providing valleys of 90 cm wide overall in plain G.S. sheet fixed with polyurethane coated J or L hooks, bolts and nuts 8 mm dia G.I. lampet and bitumen washers complete : 1.60 mm thick with zinc coating not less than 350 gsm/m ² including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	1092.40 (NR one thousand ninety two and paise four zero only)	Per running metre	1092.000
8	Providing and fixing on wall face unpainted rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes, 110 mm diameter including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	426.30 (NR four hundred twenty six and paise three zero only)	Per running metre	7675.000
9	Applying priming coat With nearly mixed pink or Grey primer (disapproved brand and manufacture on wood work (hard and soft wood) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	260.13	44.80 (NR forty four and paise eight zero only)	Per square metre	11654.000

10)	Painting with acid proof paint of approved brand and manufacture of required colour to give an even shade. One or more coats on oil work including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malakana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	260.13	67.50(INR sixty seven and paise five zero only)	Per square metre	17559.00
11)	Demarcating roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres head of including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malakana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	102.95	87.00(INR eighty seven and paise four zero only)	Per square metre	8098.00
i)	G.S. Sheet				
ii)	Asbestos cement sheet	7.50	41.00(INR forty one and paise one zero only)	Per square metre	208.00
Total:-					196377.00
Quoted Rate in Figures :-		% age +/-			
Quoted Rate in Words :-					

Executive Engineer
Bundara Division
HPPWD, Bundara

SCHEDULE OF QUANTITY

Name of Work :- C/o link road Baharoli Kalban to Jhunjnu via Gernadi Km 0.0 to 3.00
(SH:- C/o R.C.C. slab Culvert at RD 0070 wearing course and Railing etc.) *CTM/18*

Estimated cost:- ₹ 36,294.00 Only
Earnest Money:- ₹ 1700.00 Only
Time allowed:- Three Month

Name of Bidder :-

Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Providing and laying cement concrete wearing course M-20 (twenty) grade including reinforcement complete as per drawing and technical specifications clauses 800 & 1206.3 including cartage of materials with in all trade lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Makhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.42	11232.05	eleven thousand two hundred thirty two and paise zero five only	Per cubic metre	49656.00
2	Construction of R.C.C. railing of M-25 (twenty five) grade in cast-in-situ with 20 mm (twenty millimeter) nominal size aggregate, true to line and grade, tolerance of vertical railing post not to exceed 1 in 500, centre-to-centre spacing between vertical posts not to exceed 2000 mm as per drawing and technical specifications clauses 800, 900 and 1208.3 including cartage of materials with in all trade lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Makhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.60	2694.70	NR two thousand six hundred sixty four and paise seven zero only	Per running metre	36648.00
Total:-						36294.00
Quoted Rate in Figures		% age +/-				
Quoted Rate in Words						


Executive Engineer
Bharatpur Division
Bharatpur
[Signature]

SCHEDULE OF QUANTITY

Name of Work :- Construction of Kadhi Jangal Mahant road from Teleri to Madhwa via Juhar Kallian Kun (B to G-500) (SH). Construction of 900 mm dia BPC at RD 1575 with both side W-wal		Estimated cost:- ₹ 245423.00	Only
(Deposited with) 1350		Earnest Money:- ₹ 4908.00	Only
Name of Bidder :-		Time allowed:- Three Month	

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	47.36	200.10	INR Two Hundred and Paise one mm Only	Per Cubic Meter	9477.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement into four coarse sand into eight graded stone aggregate 40 mm (four millimeter) nominal size) including carriage of material with in all leads and lifts shoring and shattering and carrying complete including pumping or hauling and water (surface and sub soil water) up to all depths and any quantum of water including clearing of slabs which may arise out during dewatering and carriage of machinery, material, tools equipment safety measures and other including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	2.82	5015.90	INR Five thousand Eighteen and Paise nine mm Only	Per Cubic Meter	10432.80
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, seats, buttresses, string or facing courses, parapets, coping, bal blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing 1:3:6 (one cement into three coarse sand) into 50 graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge, including earnings of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	10.28	5254.10	INR Five thousand Two Hundred thirty four and Paise one mm Only	Per Cubic Meter	53807.00

4	Providing and laying non-pressure NP-2 class (light duty) R.C.C. pipes with casters joined with soft mixture of cement mortar in the proportion of 1:2 (one cement into two fine sand) including bedding of joints etc. complete 900 mm (nine hundred millimeter) dia. R.C.C. pipe including carriage of material with in all loads and lifts shoring and shuttering and curing complete including pumping of water (surface and sub soil water) up to all depth and any quantity of water including cleaning of shaft which may arise out during dewatering and carriage of machinery, material tools equipment safety measures and other including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	7.50	3778.10	(NR three thousand/Per running	28275.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of contracting and shuttering. All work up to plinth level 1:5:10 (one cement into five fine sand into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material in all loads and lifts as per the direction of Engineer-in-Charge. The rate including of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	26.32	4451.00	(NR Four thousand four hundred fifty one and Paise nil Only	117150.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	18.00	1285.60	(NR one thousand two hundred sixty five and Paise six zero Only	27781.00
7	Providing masonry holes in brick masonry /stone masonry, plain reinforced concrete abutment wing wall return wall with 100 mm. dia. PVC pipe extending through full of width of the structure with slope of (1% 200/1) towards downing face complete as per HPPWD specification including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	12.00	316.65	(NR three hundred sixteen and Paise six five Only	3800.00
Total:-					
Quoted Rate in Figures		% age			245473.00
Quoted Rate in Words					

Executive Engineer
Bundara Division
HPPWD Mumbai


SCHEDULE OF QUANTITY

Name of Work :- Co & Mt on link road from Badi to Badgoun Km 0.8 to 1.700 (SB- P/L
 being at RD 0/525 to 0/825) Under OTMNP.

Estimated cost:- \$229861.00
 Earnest Money:- \$25000.00
 Time allowed:- Three Month

Name of Bidder :-

Sr. No.		Description of items		Quantity	Rate		Unit	Amount
					Figures	words		
1	Preparation of sub-grade by dressing to camber (Earth work for the cutting method for sub-grade to be measured and paid for separately) depending upon the classification of soil complete as per H.P.W.D. Specification as per direction of Engineer-in-Charge. including carriage of material in all loads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes, duties, royalties, sale tax, octry. Total taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.			1055.25	1.75	NR one and point seven five only	Per square meter	1847.00
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at O.M.C. carriage of mixed material by tippers to work site, for all loads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and direction of Engineer-in-Charge. With material conforming to Grade-1 (size range 75 mm to 0.375 mm) having CBR Value > 30 including carriage of material in all loads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes, duties, royalties, sale tax, octry. Total taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.			100.50	2284.50	NR Two Thousand two Hundred forty eight and Four eight zero Only	Per Cubic Meter	22944.00
Total:-								22944.00
Quoted Rate in Figures				% age +/-				
Quoted Rate in Words								

Executive Engineer
 Roadways Division
 Hyderabad
 18/11/2018

SCHEDULE OF QUANTITIES

Name of Work :- Repair work at Health Sub-Centre Dabak GP Badgam Galla (SH). Construction of Boundary Wall, Providing and laying flooring tiles, Sanitary works etc.) Deepset Work.

Name of Bidder :-

Estimated cost:- ₹ 41,79,59.00	Order
Estimated Money:- ₹ 8,40,00.00	Only
Time allowed:- Three Month	

Sl. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 19 sqm in plan), including dressing of sides and ramming of bottom, lift up to 4m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within 1 m of bed. All kinds of soil, inclement, lift up to any height stacking excavated soil up to all beds and lifts clear from the edge of excavation and then excavating the stacked soil in fifteen consecutive back layer when required into pits, sides of foundation courses consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all beds and lifts complete in all respect.	9.4	230.10	(NDR two hundred and price one crore only)	Per cubic meter	1831.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level 1:4:8 (one Cement two four coarse sand) into eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials, tools and machinery with in all beds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.65	2802.90	(NDR five thousand Eighteen and price nine crore only)	Per cubic meter	8276.90
3	Providing and laying up to floor five level precast cement concrete slabs or having concrete, coping, bed plates, anchor blocks, plain window sills, shelves, beams, steps, stair cases, etc., including bedding and setting in position with cement mortar 1:3 (one Cement into three coarse sand), cost of required Centering complete 1:1.5:3 (one cement into one part four coarse sand) into three graded stone aggregate 20mm nominal size) including carriage of materials, tools and machinery with in all beds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.12	7504.90	(NDR seven thousand five hundred four and price nine crore only)	Per cubic meter	900.59
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level 1:1.5:3 (one Cement into one part four coarse sand) into three graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials, tools and machinery with in all beds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.61	7306.60	(NDR seven thousand eight hundred forty six and price ten crore only)	Per cubic meter	36473.00

5	Steel reinforcement for R.C.C. work including strengthening, cutting, bending, placing in position and bending all complete upto grade level. Thence mechanically treated bars of grade Fe-500D or more with in all leads, lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, access, Mobilization, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	534	Rs.600/NR, eighty eight and piece six zero only	Per Kilo gram	47312.000
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (one cement into four coarse sand) with in all leads, lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, access, Mobilization, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	114	7282.100/NR seven thousand two hundred sixty and piece one zero only	Per cubic	82771.000
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in cement mortar 1:4 (one cement into four coarse sand) with in all leads, lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, access, Mobilization, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.58	7282.100/NR seven thousand two hundred sixty two and piece two zero only	Per square	22781.000
8	Steel work as built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, bending, fitting in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete. Hot finished welded type tubes with in all leads, lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, access, Mobilization, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	400	127.200/NR one hundred twenty seven and piece two zero only	Per Kilo gram	50880.000
9	Steel work welded in built up sections/ braced work, including cutting, bending, fitting in position and applying a priming coat of approved steel primer using structural steel etc. as required in girders, frames, guard bar, tubular, railings, brackets, gates and similar works with in all leads, lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, access, Mobilization, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	600	113.800/NR one hundred thirteen and piece eight zero only	Per Kilo gram	68280.000
10	Providing and laying vitrified floor tiles, in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percentage) and conforming to IS:15622, of approved make, in all rooms and shades, laid on 20 mm (twenty millimeter) thick cement mortar 1:4 (one cement into four coarse sand), grouting with grey cement slurry @ 3.5 kg/ sqm (three point three kilo gram per square meter) including grouting the joints with white cement and matching pigments etc. complete size of tile 600 X 600 mm (six hundred into six hundred) with in all leads, lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, access, Mobilization, Toll tax, Goods and Service Tax, building and other construction works, welfare cost royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.45	1496.500/NR one thousand four hundred six and piece four zero only	Per square meter	58290.000

11	Providing and tying Verified licks in different sizes (thickness to be specified by the manufacturer), with water absorbency less than 0.08% (zero point zero eight percentage) and conforming to IS: 15622 of approved brand of manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15427, in average 6 mm (six millimeter) thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 (six hundred mm x six hundred mm) with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction works, welfare costs royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.27	1375.50 (NDR one thousand five hundred seventy five and paise five zero only)	Per square meter	17756.00
12	Providing and fixing best quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, beetle green, black of any size as approved by Engineer-in-Charge, in skirting, mess of steps and dadas, over 12 mm (twelve millimeter) thick bed of cement mortar 1:3 (one cement into three coarse sand) and grouting with grey cement slurry @ 3.3 kg per sqm, (three point three kilo gram per square meter) including painting in white cement mixed with pigment of matching shade complete, with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction works, welfare costs royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.29	993.60 (NDR nine hundred thirteen and paise six zero only)	Per square meter	14090.00
13	Providing on brick work or brick flooring with cement mortar 1:3 (one cement into three fine sand) Finish / Rubbed / Smooth or weathered pointing with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction works, welfare costs royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	91.73	128.10 (NDR one hundred twenty eight and paise one zero only)	Per square meter	12668.00
14	Disassembling with all bonded suitable disconnector of approved brand and manufacturer to give an even shade (new work (new or more coats) over and including water blinding priming coat with cement primer with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction works, welfare costs royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39	134.60 (NDR one hundred thirty four and paise four zero only)	Per square meter	1144.00
15	Finishing walls with water proofing cement paint of required shade (Two or more coats applied @ 3.84 kg/10 sqm) with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction works, welfare costs royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	107.71	70.50 (NDR seventy and paise five zero only)	Per square meter	7594.00

16	Regrouts to plaster of thickness 12 mm (provide minimum) to 20 mm (maximum) in patches of area 2.5 sq meters (one point five square meter) and under, including cutting the patch in proper shape, taking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With concrete mortar 1:4 (cement : sand) with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction worker, welfare cost, key or cross in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10	227.50 (NR three hundred twenty two and paise five zero only)	Per square meter	3225.00
17	Demolishing current concrete manually by mechanical means including disposal of material within all lead as per direction of Engineer - in - charge. Nominal concrete 1:2:6 or richer mix (for equivalent design mix) including carriage of materials, tools and machinery with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction worker, welfare cost, key or cross in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.66	1274.90 (NR one thousand two hundred seventy four and paise zero only)	Per cubic meter	2116.00
18	Providing and laying 60mm thick factory made cement concrete interlocking joint block of M -30 (class) grade made by hand making machine with strong vibratory compaction, of approved size, design & shape, laid in assigned colour and pattern over and including 50 mm (fifty millimeter) thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-Charge with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction worker, welfare cost, key or cross in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.5	783.20 (NR seven hundred eighty three and paise zero only)	Per square meter	24674.00
19	Providing and laying white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid 10 (ten) liter low level white F.V.C. flushing cistern, including flush pipe with externally controlled device (hande lever), conforming to IS : 7291, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction worker, welfare cost, key or cross in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2	4622.80 (NR four thousand six hundred fifty two and paise zero only)	Each	9244.00
20	Providing and fitting soil, waste and vent pipes. Sand cast iron S&AS pipe as per IS: 1779 with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other construction worker, welfare cost, key or cross in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2	980.60 (NR nine hundred eighty six and paise zero only)	Per running meter	1961.00


21	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, fit making good the walls etc. concealed pipes, including painting with anti-corrosive bituminous paint, cutting down and making good the wall 25 mm (thirty millimeter) dia nominal size with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, screw, Mithkhan, Telf tax, Goods and Service Tax, building and other construction work, welfare cess singly or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20	174.55 INR three hundred seventy four and paise only	Per running meter	2495.00
22	Providing and fixing C.P. brass angle valve for brass meter and geyser points of approved quality conforming to IS 8051 IS mm (fifteen millimeter) nominal bore with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, screw, Mithkhan, Telf tax, Goods and Service Tax, building and other construction work, welfare cess singly or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2	996.90 INR nine hundred six and paise nine zero only	Each	1834.80
23	Providing and fixing upsilaced PVC connection pipe with brass unions, 30 cm (thirty centimeter) length 1.5 mm (fifteen millimeter) nominal bore with in all leads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, screw, Mithkhan, Telf tax, Goods and Service Tax, building and other construction work, welfare cess singly or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2	72.85 INR seventy two and paise eight five only	Each	146.00
Total:-					
Quoted Rate in Figures:-		% Age +/-			417959.80
Quoted Rate in Words:-					

Exclusive Engineer
 Shashank Dandia
 HPPW-12, Bhubaneswar


SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:		Receipt of patch work on Kachhan to Jadda via Tachani Kachan in rate upto to 14/500 (Sfr. - repair of patch work in that 4200 to 6700)	Estimated cost: ₹	45171.00 Only	Earnest Money: ₹	90000 Only
Name of the bidder			Time allowed: one month			
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. p	Estimated Rate in words	TOTAL AMOUNT in words
	1) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN roller in stages to proper grade and camber, applying and brooming, crushable screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 m. per Technical Specification Clause 405, including carriage of materials with in all levels till and other incidents, as per direction of Engineer in Charge as per CPWD work manual / HP PWD specification 1990. The rate includes, octroi, Metakarna, Toll Tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.15	Cum	2354.0000	Two Thousand Three Hundred & Fifty four and Price Twenty Only	21547.20
	2) Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1204.2 including carriage of materials with in all levels till and other incidents as per direction of Engineer in Charge as per CPWD work manual / HP PWD specification 1990. The rate includes, octroi, Metakarna, Toll Tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1220	Sqm	336.2000	Three Hundred & Thirty Six and Price Twenty Only	40704.00
Grand Total in figures		Total in figures		Range: ✓	Amount	45171.00
Total:						

DMT No. 109
 Estimate No 94

Executive Engineer,
 Municipal Corporation,
 HP PWD,
 Bangalore


(8)

SCHEDULE OF QUANTITY

Name of Work :- M/T on Nakhla to Lathur via Paval road Km 6/8 to 5/255 (SH-20) F.D.U Cutting at RD 6/8 to 1/17/20, <u>M8888888</u>		Estimated cost:- ₹ 31,68,32,000		Only		
		Earnest Money:- ₹ 4,500,000		Only		
		Time allotted:- Two Month				
Name of Bidder :-						
Sr. No.	Description of Items	Quantity	Unit	Rate		
				Figures		
				Words		
1	Excavation in billy area in all heights and depths in all kinds of soil by manual (mechanical means) including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermedium classification of soil, setting out near to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 (Clause 302, 3603.1, 3603.2, and setting out useful material and stacking the same in all loads and lifts) on acquired width of the road and transportation of useful material for filling in road ways, canker embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animal transport or mechanical means, along with its leveling fine dressing and carriage of machines, materials, tools equipment and safety measures and other mechanical necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other costs (taxes, duties, royalties, sale tax, entry, Toll taxes of local bodies) and authorities that the contractor will have to pay for the performance of this contract. A measure of useful stones for 67.35 Cubic metre @ Rs. 6000/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1742.75	Cubic Meter	181,800	one hundred eighty one and eight eight zero only	316832000
Total:-						316832000
Quoted Rate in Figures :-		%age +/-				
Quoted Rate in Words :-						

Executing Engineer
 Municipal Corporation
 Hapur District
 Hapur District


SCHEDULE OF QUANTITY

Name of Work :- Construction of Sub road Bath Chabing to Bhorose of Purni Lal Sh. Asan Road Km 0.0 to 1.500 (SR). Construction of Canal way / Canal Drainage including beds side C / C / Provision at RD 6/3 to 8/165). *Debasit works*

Estimated cost:- ₹ 467803.00
Earnest Money:- ₹ 9400.00
Time allowed:- Three Month

Name of Bidder :-

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sign. in plant), including dressing of sides and trimming of bottoms, lift including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lift of 1.5 m of soil, including carriage of material in all loads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	37.12	298.50	Two Hundred and Ninety eight paise only	Per Cubic Meter	7429.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of contracting and subcontracting - All work up to finish level 1:4:8 (one Cement into four coarse sand into eight graded stone aggregate 40 mm (fourty millimeter) nominal size) including carriage of material in all loads and lifts, shoring and shuttering and curing complete including pumping or hauling out water (surface and sub soil water) up to all depths and any quantity of water including cleaning of slabs which may arise out during dismantling and carriage of machinery, material, tools equipment safety measures and other including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	37.12	4451.00	Four thousand four hundred fifty one and Paise only	Per Cubic Meter	165271.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of contracting and subcontracting - All work up to finish level 1:2:4 (one cement into two coarse sand into four graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials, tools and machinery with in all loads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahatma, Toll tax, Goods and Service Tax, building and other constructional work, surface cross royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.59	2982.20	Two thousand nine hundred and eighty two paise only	Per Cubic Meter	295354.00
Total:-						
Quoted Rate in Figures		% age +/-				
Quoted Rate in Words						
467903.00						

Executive Engineer
Bundara Division
HPPWD Bhopal

SCHEDULE OF QUANTITY

Name of Work :- Construction of PHC Building at Murotan Tehsil Jhasardeta Distt. Belasagar HP (SH)- Construction of Rain Harvesting Storage Tank of 25000 lit Capacity . Deposed work (BASD)		Estimated cost:- ₹ 38,092.00		Only	
		Earliest Money :- ₹ 61,00.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of Item	Quantity	Rate	Unit	Amount
		Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drain (not exceeding 1.5 m in width or 18 sqm in plan), including dressing of sides and trimming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a 10 days. All kinds of soil, incidentally, lift up to any height, stacking excavated soil up to all kinds and lifts clear from the edge of excavation and then returning the stacked soil in fibrous container thick layer when required into pits, sides of foundation etc. excavated earth to the disposal point within 10 days and lifts complete in all respect.	34.08		Per cubic metre	
2	Contracting and shoring including spreading, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahkama , Toll tax , Goods and Service Tax, building and other construction work, water cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.				
3	Grading (any thickness) including attached platform, buttresses, piers and wing concrete etc.	68.29		Per square metre	
4	Superimposed floor, roof, landings, balconies and access platform	1.96		Per square metre	
5	Providing and laying in position concrete concrete of specified grade excluding the cost of contracting and shoring . All work up to plinth level 1:3:10 time cement into fine sand into two graded and stone aggregate 40 mm (four millimeter) nominal size) including carriage of materials, tools and machinery, with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahkama , Toll tax , Goods and Service Tax, building and other construction work, water cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.53		Per cubic metre	
6	Providing and laying in position cement concrete of specified grade excluding the cost of contracting and shoring . All work up to plinth level 1:2:4 time Cement into two coarse sand) into four graded stone aggregate 40 mm (four millimeter) nominal size) including carriage of materials, tools and machinery, with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mahkama , Toll tax , Goods and Service Tax, building and other construction work, water cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.83		Per cubic metre	

5	Providing and laying in position specified grade of reinforced concrete, including the cost of casting, shuttering, finishing and reinforcement - All work up to plinth level 1:24 (one concrete into two course sand) into four graded stone aggregate 75 mm (thirty millimeter) nominal size) including carriage of materials, tools and machinery with in all loads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.41				Per cubic meter	
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Mild steel and Medium Tensile steel bars including carriage of materials, tools and machinery with in all loads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	164				Per Kilo gram	
7	Steel work, welded in built up sections/ framed work, including cutting, bending, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required, by grouting, frames, guard bar, ladder, ceilings, brackets, girds and similar works including carriage of materials, tools and machinery with in all loads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.4				Per Kilo gram	
8	Supplying and fixing C.I. cover without frame for manholes 500 mm (five hundred millimeter) diameter (C.I. cover (medium duty) the weight of the cover to be not less than 58 kg (fifty eight kilograms) including carriage of materials, tools and machinery with in all loads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1				Each	
9	Providing and fixing soil, waste and vent pipes 100 mm (one hundred millimeter) dia Sand cast iron S&S pipe as per IS: 11729 including carriage of materials, tools and machinery with in all loads lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Malikana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	100				per running meter	

7E

10	Constructing masonry Chamber 30x30x40 cm (thirty into thirty into fifty cent meter) inside. lay brick work in cement mortar 1:4 (one cement into four coarse sand) for step-cum, with C. I. surface. Box 100x100 x 25 mm (one hundred into one hundred into twenty five millimeter) (inside) with blazed cover fixed in cement concrete slab 1:2:4 mix (one cement into two coarse sand into four graded stone aggregate 20 mm (twenty millimeter) nominal size). The necessary excavation, foundation concrete 1:5:10 (one cement into five fine sand into ten graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:5 (one cement into three coarse sand) 12 mm (twelve millimeter) thick. finished with a flooring coat of wet cement concrete as per standard design with common burnt clay F.P.S (iron modular) bricks of class designation 7.5 (seven point five) including carriage of materials, tools and machinery with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mulkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess equally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6					Each	
11	Set of pumping machinery Turbo pump 1 (one) HP including all allied accessories with panel board not below the ISI standard including carriage of materials with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mulkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess equally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1					Each	
12	Construction of shed for pumping set, On filtration chamber, including carriage of materials with in all kinds lifts and other incidents as per direction of Engineer-in-Charge. The rate includes, octroi, Mulkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess equally or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1					Each	
Total:-								

Executive Engineer
Bundara Division
HPPWD, Bundara

SCHEDULE OF QUANTITIES

Name of work > Construction of Road Paved to Ashboon road Km 618 to 3400 (SSE). Construction of 2 both side wing wall of Existing HPC at RD 2859. Paved side to 3.500 mtr, Ashboon side L=3.500 mtr & R=wall at RD 2859 to 2968 B=2.50 mtr.)	Estimated cost: ₹1342912.00	Only
	Earned Money: ₹67900.00	Only
	Time allowed: Three Month	

OTMP

Name of Bidder :-					
Sl. No.	Description of items	Quantity	Rate		Amount
			Figures	words	
1	Earth work in excavation for structure as per drawing and technical specification clause 301.1 for setting out construction of abutment and bearing removal of wing and other dimension material and disposal upto a 10 level dressing of sides and bottom and back filling in trenches with excavated suitable material including savings of material in all back and lifts as per the direction of Engineer-in-Charge including carrying of materials, within all back and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes, duties, royalties, sale tax, excise. Total rates of local bodies and authorities that the contractor will have to pay for the performance of this contract.	31.23	200.00	Two Thousand and 00/100 Part one am/Only Meter	6245.80
2	Providing and laying cement concrete (1:2:10) (one cement one fine sand one kg graded stone 40 mm (fine millimeter nominal size) and tarring complete including the cost of form work in foundation and joints including the cost of setting & shuttering in foundation and joints including savings of materials, within all back and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes, duties, royalties, sale tax, excise. Total rates of local bodies and authorities that the contractor will have to pay for the performance of this contract.	69.17	4401.00	four Thousand and 00/100 Part one am/Only Meter	307876.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 304.3.3 Circular material including savings of materials, within all back and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes, duties, royalties, sale tax, excise. Total rates of local bodies and authorities that the contractor will have to pay for the performance of this contract.	11.99	3281.60	one thousand and 80/100 Part one am/Only Meter	15475.00
4	Providing wing holes in brick masonry inner masonry, plaster reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extending through full of width of the structure with slope of (V) 20(H) smooth drawing face complete as per BIDDING specification including savings of materials, within all back and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes, duties, royalties, sale tax, excise. Total rates of local bodies and authorities that the contractor will have to pay for the performance of this contract.	43.00	318.65	Three Hundred and 65/100 Part one am/Only Meter	13616.00
Total:					
Grand Total in Figures		%		₹1342912.00	
Grand Total in Words					

Authorized Engineer
 Signature
 Date

SCHEDULE OF QUANTITY

Name of Work :- Repair of Health Sub-Center Building at Dhalab of Rural Health Department (Self- Repair of Slab, C/o Biwall at RD 4/9 to 0030 & Boundary Wall) Deposit Work.		Estimated cost:- ₹ 473665.00		Only
		Earrest Money:- ₹ 9500.00		Only
Sr. No.	Description of Items	Time allowed:- Three Months		
		Quantity	Rate	Amount
		Figures	words	Unit
1	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm wide including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	35.10	145.400 (NR one hundred forty five and Paise four zero Only)	Per running Meter
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, seats, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sashes floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing L.I.P.C.S (1 cement : 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	3.65	7246.600 (NR seven thousand eight hundred forty six and Paise zero Only)	Per Cubic Meter
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto finish level. Mild steel and Medium Tensile steel bars, including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	285.75	86.200 (NR eighty six and Paise two zero Only)	Per Kilogram
4	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	33.56	200.100 (NR two hundred and Paise one zero Only)	Per Cubic Meter

5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:5:10 (1 cement : 5 course sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour costs, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	\$1.00	4451.000 INR Four thousand four hundred fifty one and Paise nil Only	Per Cubic Meter	2277001.000
6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:4:3 (1 Cement : 4 course sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour costs, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.06	5048.700 INR five thousand four hundred eighty eight and Paise seven zero Only	Per Cubic Meter	25546.000
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:5 (1 cement : 5 course sand) including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour costs, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	11.73	8341.300 INR eight thousand three hundred thirty one and Paise three zero Only	Per Cubic Meter	97843.000
8	1:5 mm cement plaster on the rough side of single or half brick wall of mix 1:5 (1 cement : 5 fine sand) including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour costs, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	108.90	728.100 INR two hundred thirty eight and Paise one zero Only	Per square Meter	25979.000
9	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. Water thinnable cement primer including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour costs, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	108.90	44.400 INR forty four and Paise four zero Only	Per square Meter	4835.000
10	Wall pointing with plastic emulsion paint of approved brand and manufacture to give an even shade. One or more coats on old work including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour costs, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	108.90	67.000 INR sixty seven and Paise nil Only	Per square Meter	7796.000

11	Structural steel work in single section, fixed with or without connecting plate, including cutting, bolting, fitting in position and applying a priming coat of approved steel primer all complete, including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	112.14	105.50	INR. one hundred five and Paise five zero Only	Per Kilogram	11831.00
12	Providing wrap holes in brick masonry /stone masonry, plain reinforced concrete abutment wing wall return wall with 150 mm. dia PVC pipe extending through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all heads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	26.00	316.65	INR. three hundred sixteen and Paise six five Only	Each	8233.80
Total:-						
Quoted Rate in Figures		% age +/-				
Quoted Rate in Words						
						473665.180

Executive Engineer,
 Bangalore District
 Highway Department
 Bangalore

SCHEDULE OF QUANTITIES						
Name of work	Repair of patch work on Tashkhan to Jaldy on Irkondan Kaban in Km 170 to 14500 (2nd repair of patch work in Km 1200 to 4100)	Estimated cost: ₹	601711 Only	Estimated labor: ₹	90702 Only	TOTAL AMOUNT WITH TAXES
Name of the Bidder						
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. / P	Estimated Rate in words	TOTAL AMOUNT WITH TAXES
1	1) Spreading, laying, spreading and compacting stone aggregates of specific size, to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with roller wheel 80-100 kN static roller in stages to proper grade and camber, applying and bouncing, crushable screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405, including carriage of materials with in all levels bits and other incidentals as per direction of Engineer in Charge as per CPWD work manual / HP PWD specification 1990. The rate includes, octroi, Malakana, Toll tax, Goods and Service Tax, building and other construction workers, welfare cost, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.15	Cum	2354.56	Two Thousand Three Hundred & Fifty Four and Fifty Twenty Only	21547.100
2	2) Repair to pot holes and removal of loose material, trimming of sides, dressing of surface by providing back coat, 20 mm thick pre-cast carpet and seal coat type B specification Clause 159A.2 including carriage of materials with in all levels bits and other incidentals as per direction of Engineer in Charge as per CPWD work manual / HP PWD specification 1990. The rate includes, octroi, Malakana, Toll tax, Goods and Service Tax, building and other construction workers, welfare cost, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1220	Sqm	336.20	Three Hundred & Thirty Six and Twenty Only	410554.000
Grand Total in Figures						431711.000
Grand Total in Figures						431711.000

Drawn No. 110
 Estimate No 95

Executive Engineer,
 Maharashtra Division,
 HP/WD
 Jalgaon

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road from Main road Project of Bhag Singh Jai Chauran has 0000 to 0000
 (SR:- On C Pavement at RD 0000 to 0000) Deposit Ward


Estimated cost:- ₹1299656.00

Earnest Money:- ₹5998.00

Time allowed:- Three Month

Name of Bidder :-

Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 m in length), including dressing of sides and measuring of bottoms, till up to all, including getting out the excavated soil and deposit of surplus excavated soil as directed, within 1 m bed. All kinds of soil including, till up to any height stacking excavated soil up to all beds and lifts clear from the edge of excavation and then returning the stacked soil in layers convenient, third layer when required into pits, sides of foundation trenches considering each deposited layers by ramming and watering and then depositing of all surplus excavated earth to the disposal point within all beds and lifts complete in all respect.	48.75	2000	thousand and two hundred and four square meter zero only	Per cubic meter	9755.00
2	Stone setting, properly hand packed filling interspersed with Khazariya stone and consolidating with grout mud either in the required gradient and concrete including spreading watering and rolling of bedding materials maximum or earth etc. complete as per HPWD specification, 100 mm spread thickness (finished work including materials and labour) including carriage of materials, within all beds and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes / duties, royalties, site tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	29.25	1440	thousand four hundred and forty and four square meter only	Per cubic meter	42135.00
3	Providing and laying design mix concrete of M 30 grade, in roads, taxi tracks, runways, using cement concrete as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing allowed bars with sleeve tie bars wherever required, laying at site, spreading and compacting mechanically by using roller and surface vibrators, bedding to required slope/ camber, finishing with required texture, including steel form work with slurry M 3.5, channel sections, curbs, making provision for contraction expansion, construction of longitudinal joints (10 mm wide x 50 mm deep) by grove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-Charge (bars of joint filler, sealants, allowed bars with sleeve tie bars to be paid separately). Note:- Cement concrete considered as M 30 is @ 340 kg/cum. Excess less cement used as per design mix is payable recoverable separately. Cement concrete prepared with batch mixing machine including carriage of materials, within all beds and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes / duties, royalties, site tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	31.29	7813	thousand eight hundred and thirteen square meter	Per cubic meter	243766.00
Total:-						299656.00
Quoted Rate in Figures						
Quoted Rate in Words						


 Engineer-in-Charge
 Municipal Corporation
 Bhag Singh Jai Chauran

1

SCHEDULE OF QUANTITY						
Name of Work:	Bill of materials to be used in the work	Estimated cost: ₹	Estimated quantity: m³	Estimated rate: ₹	Estimated cost: ₹	Estimated quantity: m³
Name of the Bidder						
SL No.	Item Description	Quantity	Units	Estimated Rate in Rs. p	Estimated Rate in Rupees	TOTAL AMOUNT (with Taxes)
1	Gravel, 10mm, spreading and compacting, stone aggregate of specific size to water bound medium specification including spreading in uniform thickness, hand packing, rolling with stone wheel 80-100 lit. static roller in stages to proper grade and camber, applying and brooming, crushable concrete to fill up the voids of coarse aggregate, watering and compacting to the required density (grading 3 as per Technical Specification Clause 405, including carriage of materials with in all kinds lifts and other incidents, as per direction of Engineer-in-Charge as per CPWD work manual / CPWD specification 1990. The rate includes, octroi, Malabar, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess, supply or any other tax, levy or cess in respect of input for or output by the contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.55	Cum	2354.90	Two Thousand Three Hundred & Fifty Four and Nine Twenty Only	2094.00
2	Gravel, 20mm, spreading and compacting, stone aggregate of specific size to water bound medium specification including spreading in uniform thickness, hand packing, rolling with stone wheel 80-100 lit. static roller in stages to proper grade and camber, applying and brooming, crushable concrete to fill up the voids of coarse aggregate, watering and compacting to the required density (grading 3 as per Technical Specification Clause 405, including carriage of materials with in all kinds lifts and other incidents, as per direction of Engineer-in-Charge as per CPWD work manual / CPWD specification 1990. The rate includes, octroi, Malabar, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess, supply or any other tax, levy or cess in respect of input for or output by the contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1400	Sqm	336.20	Three Hundred & Thirty Six and Two Only	47067.20
Total in figures						
Grand Total in figures		Total		Total		49754.20

Chart No. 107
Estimate No. 92

Executive Engineer,
Municipal Corporation,
Hyderabad.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY								
Name of Work:-		Estimated cost:- ₹		491245.00		Only		
Name of Bidder		Earnest Money:- ₹		10000.00		Only		
Sl. No.		Item Description		Quantity		Units		
1		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 Yd in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405, including carriage of material, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.		58.00	Per Cubic Meter	2354.90	INR Two Thousand Three Hundred & Fifty Four and Paise Ninety Only	136584.00
2		Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 lps/m using mechanical means as per Technical Specification Clause 500, including carriage of material, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.		1104.86	Per Square Meter	58.40	INR fifty eight and Paise fourty Only	64524.0
3		Providing and applying tack coat with Bitumen emulsion (BS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with primer & cleaned with hydraulic broom as per Technical Specification Clause 503, including carriage of material, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.		1104.86	Per Square Meter	19.30	INR Nineteen and Paise thirty Only	21324.0

4	Providing, laying and rolling of open graded premix carpet of 25 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 lit static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508 including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cost, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1104.86/Per Square Meter	178.10/INR	One Hundred seventy eight and Paise Ten Only	196776.00
5	Providing and laying seal coat sealing the works in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510 including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cost, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1104.86/Per Square Meter	65.20/INR	Sixty five and Paise twenty Only	72037.00
Total in Figures					
Quoted Rate in Figures	%age +/-				
Quoted Rate in Words					
					491245.00

DATT No. 116
Estimate No 107

Executive Engineer,
Bhandara Division,
HPPWD, Bhandara

SCHEDULE OF QUANTITY

Name of Work :- Civil work road from Berrish Sargol road to house of Kargol Shabir Sa.
 Meter Run Km 0 to 1.000 (SEE) P/L, sitting at R/D 0/775 to 1/000, Under SCDP.

Estimated cost:- ₹180938.00 Only
 Earnest Money:- ₹5600.00 Only
 Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figure	words		
1	Preparation of sub-grade by dressing to camber (Earth work for the cutting involved for sub-grade to be measured and paid for separately) depending upon the classification of soil complete as per H.P.P.W.D., Specification as per direction of Engineer-in-Charge, including carriage of material in all loads and lifts as per the direction of Engineer-in-Charge, including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes, duties, royalties, sale tax, octry. Full times of local bullocks and authorities that the contractor will have to pay for the performance of this contract.	791.46	1.75	One and four seven five only	Per square meter	1385.00
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at 0.4M, carriage of mixed material by tippers to work site, for all loads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having (BSE Value-3) including carriage of material in all loads and lifts as per direction of Engineer-in-Charge, including carriage of materials, within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes, duties, royalties, sale tax, octry. Full times of local bullocks and authorities that the contractor will have to pay for the performance of this contract.	79.146	258.80	Two hundred and five eight and four eight zero Only	Per Thousand Sq. Meter	179553.00
Grand Total in Figures		Total:-				180938.00
Grand Total in Words		% age +/-				

Executive Engineer
 Assistant Engineer
 SPM/CD Shabir

SCHEDULE OF QUANTITY

Estimated cost:- ₹ 152155.00 Only
 Earnest Money:- ₹ 15000.00 Only
 Time allowed:- One Month

Name of work :- C/PD link road from Dehad to village Dehwin road km. 0/10 to 3/10 (S&T- Formation Cutting in km. 1/915 to 2/165)

Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			Figures	Words		
1	Earth work in excavation by mechanical means (hydraulic excavator/manual means over areas exceeding 20 cm in depth, 1.5 m in width as well as 10 sqm in area) including getting out and disposal of excavated earth, haul upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge, and sorting out useful material and stacking the same in all loads and this on acquired width of the road and transportation of all useful material by filling in road, ways, canals, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including hired bullock or animal transport or mechanical means, alongside its leveling fine dressing and carriage of machines, materials, tools equipments and safety measures and other incidents necessary to complete the work by mechanical means and/or labour if required. Any loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials within all loads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, sales tax, duty, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for c/c Cubic metre @ Rs. 600/- per cubic metre shall be given on pro-rata basis from each running bill for this item.	1021.86	148.90	one hundred Forty Eight and Nine NINETY Only	Per Cubic Metre	152155.00
Total:-						152155.00
	Quoted Rate in Figure	Stage +/-				
	Quoted Rate in Words					

ESB-113
 DWIT-198

Executive Engineer,
 Bundles Division
 HPPWD, Jammu

19

SCHEDULE OF QUANTITY

Name of Work :- M/T on Nekkera to Lullur via Peral road Km 4/9 to 5/255
(SHE- R.O.F.D) Cutting at R.D 1/1/59 to 2/0/75) *UPPER RD*

Name of Bidder :-

Estimated cost:- ₹	366141.00	Only
Earnest Money:- ₹	7388.00	Only
Time allowed:- Two Months		

Sl. No.	Description of items	Quantity	Unit	Figures	Rate words	Amount
1	Excavation in billy area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/breaking out of rock (where blasting is prohibited) and other interlocking classification of soil, setting out true to the required line, grade with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302.1685 L1463.2 and surfacing with useful material and stacking the same in all loads and lifts in acquired width of the road and transportation of useful material for filling in road ways, embankment for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including local haul or animals transport or mechanical means, through its leveling fine dressing and carriage of machines, materials, tools, equipments and safety measures and other incidents necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all loads and lifts in per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other levies / taxes, duties, royalties, site tax, octroi, Toll charges of local bodies and authorities that the contractor will have to pay for the performance of this contract, a necessary of useful stones for 76.24 Cubic metre @ Rs. 6000 per cubic metre shall be done on pro-rata basis from each meeting bill for this item.	1795.46	Per Cubic Metre	209.77	INR two hundred nine and paise seven seven only	366141.00
Total:-						
Quoted Rate in Figures :-		Surge +1:-				366141.00
Quoted Rate in Words :-						

Estimate Engineer
Signature
Date
19/11/2019

SCHEDULE OF QUANTITY						
Name of Work:	Repair of patch work on kerbside to include all footways within the 15m to 14,500 Dm: repair of patch work in RM 5,000 to 14,500	Estimated cost: ₹	481711.00	Only	481711.00	Only
Name of the Bidder		Estimated cost: ₹	50790.00	Only	50790.00	Only
Item Description	Quantity	Estimated Rate in Rs. p	Estimated Rate in words	TOTAL AMOUNT with Taxes	Time allowed: one month	
1) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with roller wheel 80-100 kN static roller in stages to proper grade and camber, applying with dressing, crushable screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specifications Clause 425, including carriage of materials with in all loads, lifts and other incidents as per direction of Engineer in Charge As per CPWD work manual / HP PWD specification 1990. The rate includes, octroi, Malabar, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.15 Cum	2354.50	Two Thousand Three Hundred & Fifty Four and Paise Twenty Only	21547.00		
2) Repair to pot holes and removal of loose material, burning of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1206.2 including carriage of materials with in all loads, lifts and other incidents as per direction of Engineer in Charge As per CPWD work manual / HP PWD specification 1990. The rate includes, octroi, Malabar, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1220.5 sqm	336.20	Three Hundred & Thirty Six and Paise Twenty Only	41054.00		
Total in Figures		Total in Figures		481711.00		
Total:		Rs. p	Amount	481711.00		

Draft No. 108
Estimate No. 43

Executive Engineer
Bharatpur Division
10/10/2019
[Signature]

SCHEDULE OF QUANTITY

Name of Work :- Civil Road from Dokra to Neri via Rohat Km 0.0 to 2.600 (SH-1) Eriying at various RDBs 1:850 to 1:850 & Civil RCC Hume pipe culvert at RDB 1:700, Under SCDP.

Estimated cost:- ₹ 3286.47.00 Only
Earnest Money:- ₹ 6600.00 Only
Time allowed:- Three Months

Name of the Bidder :-

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 (i) setting and construction of shoring and bracing removal of slumps and other obstructions material and disposal upto a bed of 500 (fifty) mm, dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes / duties, cesses, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	148.52	128.15	ONE Hundred & Twenty Eight and Five Fifths Only	Per Cubic Meter	19051.00
2	Providing and laying cement concrete 1:4:8 (One cement into four sand into eight) graded stone aggregate, (Thermal/Corry) (submersed) nominal size) and curing compound including cost of form work in retaining walls/retaining walls, as per HYPWD specifications within all heads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes / duties, cesses, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	86.56	2337.20	ONE thousand three hundred thirty seven and paise twenty only	Per cubic meter	202208.00
3	Plain Cement Concrete M20 (1:2:8 nominal mix) in bedding course below open installation of flexal walls as per drawings & Technical Specification Clause 1109, including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but excluding labour cost, other taxes / duties, cesses, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	113.34	2928.35	ONE Thousand Nine Hundred & Twenty Eight and Five Paise Only	Per Cubic Meter	29064.00
4	Providing and laying reinforced cement concrete pipe 1075 for culverts on first class bedding of granular material in single row including forming culvert with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 900 mm including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes / duties, cesses, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	7.98	1773.70	ONE thousand seven hundred seventy three and Paise seventy Only	Per running Meter	14073.00
5	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded stone agg. 40 mm nominal size) and curing compound excluding the cost of form work in foundation and piers excluding the cost of excavating & shoring in foundation and piers including carriage of material in all heads and lifts as per the direction of Engineer-in-Charge, including carriage of materials, within all heads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cost, other taxes / duties, cesses, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	113.94	2968.20	ONE Thousand & Twenty Eight and Paise Twenty Only	Per Cubic Meter	29889.00

6	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V), 20(H) towards drawing face complete as per HPPWD specification including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	56.00	253.70	INR Two Hundred fifty Three and Paise Seventy Only	Each	14207.00
Total:-						
Quoted Rate in Figures :-						
Quoted Rate in Words:-						
Total:-						
328647.00						

Executive Engineer
Jharkhand Division
HPPWD, Jharkhand