



Himachal Pradesh  
Public Works Department



No. PW.CHD.CB.E-9/2022- 6001-03

Dated : 04/08/2022


To

The Executive Engineer (IT Cell),  
Nigam Vihar Shimla, H.P.

**Subject :- Publication of Tender Notice.**


Sir,

Enclosed please find herewith the tender notice of work(s) as given in the Notice Inviting Tender for uploading on departmental website as per notification vide Pr. Secy. (PW) to the Government of Himachal Pradesh letter No. PBW(B)1/2020 dated 27<sup>th</sup> May, 2021 and PBW(B)A(3)1/2020 dated 16<sup>th</sup> July, 2021 as the work(s) mentioned in the tender notice is(are) urgent in nature and in public interest.

  
Executive Engineer,  
Chopal Division,  
HPPWD Chopal.

**Copy forwarded for further necessary action to the :-**

1. The Superintending Engineer, 04<sup>th</sup> Circle, HPPWD Shimla;
2. Computer Cell O/o the Executive Engineer, (IT Cell) Nigam Vihar Shimla-2.

  
Executive Engineer,  
Chopal Division,  
HPPWD Chopal.




Himachal Pradesh  
Public Works Department



CERTIFICATE

Certified that the tenders of work(s) as called vide this office NIT  
No. PW.CHD.CB.C-9/2022- 5901-6000 dated 04/08/2022 are of  
urgent nature works.

  
Executive Engineer  
Chopal Div. HPPWD Chopal  
On behalf of Governor of HP 



Office 01783-260033

Email : [ee-cho-hp@nic.in](mailto:ee-cho-hp@nic.in)

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
INVITATION FOR BIDS (IFB)

NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HJPPWD. The tender shall be opened in the presence of the contractors/firms of their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 10.08.2022 11:00 AM to 04:00 PM
2. Date and time of issue of tender form : 10.08.2022 11:00 AM to 04:00 PM
3. Date and time of receipt of tenders : 11.08.2022 11:00 AM
4. Date and time of opening of tender : 11.08.2022 11:00 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for the purpose.

| Sl. No | Name of Work  | Estimated Cost | EMD    | Cost of tender | Time Limit | Eligible class of contractor |
|--------|---|----------------|--------|----------------|------------|------------------------------|
| 1.     | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Nerwa-I Section of Shallu Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)   | 155320/-       | 3500/- | 350/-          | Two Months | Class D or above             |
| 2.     | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Nerwa-II Section of Shallu Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)  | 150150/-       | 3500/- | 350/-          | Two Months | Class D or above             |
| 3.     | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Jhiknipul Section of Shallu Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain) | 151800/-       | 3500/- | 350/-          | Two Months | Class D or above             |
| 4.     | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Rewalpul Section of Shallu Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)  | 140250/-       | 3000/- | 350/-          | Two Months | Class D or above             |
| 5.     | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Naura Section of Kupvi Sub Division (SH: Removal of slips, dressing of road and clearance of drain)            | 153450/-       | 3500/- | 350/-          | Two Months | Class D or above             |
| 6.     | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Kupvi Section of Kupvi Sub Division (SH: Removal of slips, dressing of road and clearance of drain)            | 154000/-       | 3500/- | 350/-          | Two Months | Class D or above             |

|     |   |          |         |       |            |                  |
|-----|---|----------|---------|-------|------------|------------------|
| 7.  | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Sainjkhud Section of Kupvi Sub Division (SH: Removal of slips, dressing of road and clearance of drain)              | 151580/- | 3500/-  | 350/- | Two Months | Class D or above |
| 8.  | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Kuthar Section of PIU Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)             | 141059/- | 3000/-  | 350/- | Two Months | Class D or above |
| 9.  | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Shamtha Section of PIU Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)            | 142159/- | 3000/-  | 350/- | Two Months | Class D or above |
| 10. | Name of work :- Restoration of rain damages on various roads during monsoon season 2022-23 under Feeduj Section of PIU Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)             | 143300/- | 3000/-  | 350/- | Two Months | Class D or above |
| 11. | Name of work :- Improvement of black spot on Sainj Deha Chopal Nerwa Feduj road km. 0/0 to 90/0 (SH: Edge walls in PCC 1:5:10 and parapets in PCC 1:4:8 at various RDs as per site in between km. R.D. 40/0 to 50/0). | 491335/- | 10000/- | 350/- | Two Months | Class D or above |
| 12. | Name of work :- A/R & M/O Dewat to Kumbra road km. 0/0 to 1/300 (SH: C/o wire crated wall in between km. R.D. 0/445 to 0/495).  | 354719/- | 7500/-  | 350/- | Two Months | Class D or above |
| 13. | Name of work :- Improvement of black spot on Sainj Deha Chopal Nerwa Feduj road km. 0/0 to 90/0 (SH: Edge walls in PCC 1:5:10 and parapets in PCC 1:4:8 at various RDs as per site in between km. R.D. 30/0 to 40/0). | 488140/- | 10000/- | 350/- | Two Months | Class D or above |

#### **TERMS AND CONDITIONS :-**

- The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of form.
- The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
  - Latest enlistment/renewal orders with application;
  - GST Number issued by the Sale Tax Department;
  - PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
- The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s);
- The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor;
- The work will be completed by the contractor within the stipulated period;
- The contractor/firms are required to insert the rate of each item in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any overall tender;
- The tender shall be issued to only those contractor/firms who are eligible suitable and competent;
- The tender forms shall be issued to eligible contractors depending upon their past performance and work experience which shall be duly evaluated by the technical evaluation committee.



9. The contractor/firm having necessary documents and past adequate experience shall be preferred;
10. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms;
11. A contractor enlisted in a particular class be eligible to tender for his own class and one step below;
12. Only two number tender forms will issued to the eligible contractor;
13. If any kind of holiday to be happened, the tender shall be opened on the next working day at 11:30 a.m.
14. GST will be deducted as per rates fixed by the Government.

**CERTIFICATE**

It is to certify that tender for the above works are urgently required please.

No. PW.CHD.CB.E-9/2022- 5901-6000

Dated : 04/08/2022

Executive Engineer  
Chopal Div.HPPWD Chopal  
On behalf of Governor of HP

***Copy forwarded for information to the :-***

1. Chief Engineer (Shimla Zone) HPPWD Shimla;
2. Superintending Engineer, 04<sup>th</sup> Circle, HPPWD Shimla;
3. Deputy Commissioner, Shimla
4. SDO(C) Chopal Tehsil Chopal District Shimla HP
5. Tehsildar Chopal Tehsil Chopal District Shimla HP
6. BDO Chopal for information;
7. All the Assistant Engineers under this division;
8. All the intending contractors for information;
9. Notice Board.

Executive Engineer  
Chopal Div.HPPWD Chopal  
On behalf of Governor of HP


4

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 155320/-  
Earnest Money : Rs. 3500/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Nerwa-I Section of Shallu Sub  
Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1412.00 |           |           | Per Cubic Metre. |        |

  
Executive Engineer  
Division (B & M)  
H.P.W.D. Nepal


57

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 150150/-  
Earnest Money : Rs. 3500/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Nerwa-II Section of Shallu Sub  
Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)

| Sl.<br>No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|------------|---|---------|-----------|-----------|------------------|--------|
|            |   |         | In figure | In words. |                  |        |
| 1          | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1365.00 |           |           | Per Cubic Metre. |        |

  
~~Executive Engineer~~  
Chopal Division (B & R)  
H.P.W.D. Chopal

2

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 151800/-  
Earnest Money : Rs. 3500/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Jhiknipul Section of Shallu  
Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1380.00 |           |           | Per Cubic Metre. |        |

  
**Executive Engineer**  
Chopal Division (B & M)  
H.P.W.D. Chopal



DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 140250/-  
Earnest Money : Rs. 3000/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Rewalpul Section of Shailu  
Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all heads as per the direction of Engineer in charge at site. | 1275.00 |           |           | Per Cubic Metre. |        |

  
Executive Engineer  
Rewalpul Division (B & R)  
H.P.W.D. Chaudhary

8

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 153450/-  
Earnest Money : Rs. 3500/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Naura Section of Kupvi Sub  
Division (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1395.00 |           |           | Per Cubic Metre. |        |

Engineer  
Division (B & R)  
H.P.W.D. Chopal

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 154000/-  
Earnest Money : Rs. 3500/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Kupvi Section of Kupvi Sub  
Division (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1400.00 |           |           | Per Cubic Metre. |        |


  
Executive Engineer  
Choppal Division (B & R)  
H.P.P.W.D. Choppal

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 151580/-  
Earnest Money : Rs. 3500/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Sainjikhud Section of Kupvi  
Sub Division (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1378.00 |           |           | Per Cubic Metre. |        |

  
Executive Engineer  
Chopal Division (B & R)  
P.P.W.D. Etahol




24

DNIT/SCHEDULED OF QUANTITY.

Estimated Cost : Rs. 141059/-  
Earnest Money : Rs. 3000/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Kuthar Section of PIU Sub  
Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1282.35 |           |           | Per Cubic Metre. |        |

  
Executive Engineer  
Chowal Division (B & P)  
H.P.W.D. Chowal


DNIT/SCHEDULED OF QUANTITY.

(12)

Estimated Cost : Rs. 142159/-  
Earnest Money : Rs. 3000/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Shamtha Section of PIU Sub Division Nerwa (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1292.35 |           |           | Per Cubic Metre. |        |


  
Engineer  
Chowki Division (B & M)  
H.P.W.D. Chowki

**DNIT/SCHEDULED OF QUANTITY.**

Estimated Cost : Rs. 143300/-  
Earnest Money : Rs. 3000/-  
Time allowed Two months.

NAME OF WORK : Restoration of rain damages on various roads during monsoon season 2022-23 under Feeduj Section of PIU Sub  
Division Nerva (SH: Removal of slips, dressing of road and clearance of drain)

| Sl. No. | Description of item   | Qty.    | Rate      |           | Unit.            | Amount |
|---------|---|---------|-----------|-----------|------------------|--------|
|         |   |         | In figure | In words. |                  |        |
| 1       | Removal of slips, boulders etc. and disposing it to the valley sides as per norms and IRC specification 48-1998 including carriage of all labour material and equipments to various location through all mode of transportation as per HPPWD specification 1990 volume first in all leads as per the direction of Engineer in charge at site. | 1302.72 |           |           | Per Cubic Metre. |        |

  
Executive Engineer  
Chopal Division (B & D)  
H.P.W.D. Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost  
Earnest Money  
Time Allowed

Rs. ~~496122/-~~ 487109/-  
Rs. 10000/-  
Two months

Name of work : Improvement of black spot on Saini Deha Chopal Nerwa Feduj road km. 0/0 to 90/0 (SH: Edge walls in PCC 1:5:10 and parapets in PCC 1:4:8 at various RDs as per site in between km. R.D. 30/0 to 40/0).

| Sl. No. | Description of item   | Qty.                             | Rate | Unit             | Amount |
|---------|---|----------------------------------|------|------------------|--------|
| 1       | Earth work in exavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring bracing and removal of stumps and other deleterious material and disposal up to 50m lead dressing of side slope and bottom back filling in trenches with excavated suitable material and including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.   | 61.39                            |      | Per cubic metre. |        |
| 2       | P/I concrete to plain reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm nominal size) mixing by mechanical concrete mixture 0.40/0.28 cubic metre and vibrated mechanically so as to give a compressive strength and curng complete including the cost of form work as per drawing and technical specification clause 802, 803,1202, 1203.including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts. | <del>54.60</del><br><u>56.80</u> |      | Per cubic metre. |        |
| 3       | P/I concrete to plain reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 25mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803,1202, 1203 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.   | 52.95                            |      | Per cubic metre. |        |

Executive Engineer  
Regional Division (H & M)  
P.R.W.D, Chopal



DRAFT/SCHEDULED OF QUANTITY.

2

Estimated Cost Rs. 354719/-  
Earnest Money Rs. 7500/-  
Time Allowed Two months

Name of work : A/R & M/O Dewat to Kumbra road km. 0/0 to 1/300 (SH: C/o wire crated wall in between km. R.D. 0/445 to 0/495).

| Sl. No. | Description of item  | Qty.   | Rate |  | Unit             | Amount |
|---------|--|--------|------|--|------------------|--------|
| 1       | Excavation in earth work at site including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.  | 56.25  |      |  | Per cubic metre. |        |
| 2       | Providing and laying of boulder apron laid in wire crate with 4mm dia conforming to IS 280 and 48.26 mesh design including joints laid in boulder weighing not less than 25 kg each as per drawing and dtechnical specification clause 1301 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts. | 156.25 |      |  | Per cubic metre. |        |

  
Executive Engineer  
Chopal Division (B & R)  
H.P.P.W.D. Chopal

## SCHEDULED OF QUANTITY.

Estimated Cost  
Earnest Money  
Time Allowed

Rs. 488140/-  
Rs. 10000/-  
Two months

Name of work : Improvement of black spot on Sainj Deha Chopal Nerwa Feduj road km. 0/0 to 90/0 (SH: Edge walls in PCC 1:5:10 and parapets in PCC 1:4:8 at various RDs as per site in between km. R.D. 40/0 to 50/0).

| Sl. No. | Description of item  | Qty.  | Rate |  | Unit             | Amount |
|---------|--|-------|------|--|------------------|--------|
| 1       | Earth work in exavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring bracing and removal of stumps and other deleterious material and disposal up to 50m lead dressing of side slope and bottom back filling in trenches with excavated suitable material and including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.  | 48.08 |      |  | Per cubic metre. |        |
| 2       | P/I concrete to plain reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm nominal size) mixing by mechanical concrete mixture 0.40/0.28 cubic metre and vibrated mechanically so as to give a compressive strength and curing complete including the cost of form work as per drawing and technical specification clause 802, 803, 1202, 1203, including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts. | 28.52 |      |  | Per cubic metre. |        |
| 3       | P/I concrete to plain reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 25mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803, 1202, 1203 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.   | 78.67 |      |  | Per cubic metre. |        |

**Executive Engineer**  
Chopra Division R & M  
H.P.W.D. Ch. D. 40