



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 20/08/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 18.08.2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Restoration of Rain damages on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- Maintenance of drain, hume pipe culverts and berms in Km. 2/0 to 4/0).	Rs. 94,707/-	Rs. 1900/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on various roads under Swarghat Sub-Division (Swahan section) (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain various RD) for the year 2022-23 Job No. 10	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
3	Restoration of Rain damages on various roads under Swarghat Sub-Division (Bagchhal section) (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain various RD) for the year 2022-23 Job No. 6	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
4	Restoration of Rain damages on various roads under Swarghat Sub-Division (Baner section) (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain various RD) for the year 2022-23 Job No. 8	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
5	Restoration of Rain damages on Sh. Naina Devi Ji to Toba road Km. 0/0 to 9/225 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 2/0 to 9/0) for the year 2022-23 Job No. 8	Rs. 1,02,310/-	Rs. 2,100/-	Rs. 350/-	One Month
6	Restoration of Rain damages on Galwa Galthai road Km. 0/0 to 35/0 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 9/0 to 25/0) for the year 2022-23 Job No. 7	Rs. 1,02,310/-	Rs. 2,100/-	Rs. 350/-	One Month
7	Restoration of road damages on Deoth to Lagghat road Km. 0/0 to 8/0 (SH:-Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips and dressing of berms at various RDs)	Rs. 71,316/-	Rs. 1,500/-	Rs. 350/-	One Month
8	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 19/0 to 25/0) for the year 2022-23 Job No. 6	Rs. 1,02,310/-	Rs. 2,100/-	Rs. 350/-	One Month
9	Restoration of Rain damages on various roads under Swarghat Sub-Division (Swahan section) (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain various RD) for the year 2022-23 Job No. 10	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
10	Restoration of Rain damages on NH-205 CMM road Km. 86/0 to 105/0 (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) for the year 2022-23 Job No. 9	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month

11	Restoration of Rain damages on various road under Swarghat Sub-Division HPPWD Swarghat (SH:- Hiring of Tractor with Trolley for removal of slips at various RDs) for the year 2022-23 Job No. 3	Rs. 99,360/-	Rs. 2,000/-	Rs. 350/-	One Month
12	Restoration of Rain damages on various roads under Sub-Division No. III HPPWD Bilaspur (Kothipura Section) (SH:- Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips, clearing of culverts/drain and dressing of berms at various RDs)	Rs. 71,316/-	Rs. 1,500/-	Rs. 350/-	One Month
13	Restoration of Rain damages on various roads under Kharsi Section (SH:- Hiring of JCB for removal of slips and clearance of drain at various RDs under Kharsi section) for the year 2022-23 Job No. 3	Rs. 99,162/-	Rs. 2,000/-	Rs. 350/-	One Month
14	Improvement of Navgaon Beri road Km. 4/350 to 23/700 (SH:- P/L 30mm thick bituminous concrete at RD 10/315 to 10/355 at Malokher Chowk)	Rs. 73,883/-	Rs. 1,500/-	Rs. 350/-	Three Month
15	Restoration of Rain damages on various roads under Namhol section (SH:- Hiring of JCB for removal of slips and clearance of drain at various RDs under Namhol section) for the year 2022-23 Job No. 1	Rs. 99,162/-	Rs. 2,000/-	Rs. 350/-	One Month
16	Restoration of Rain damages on various roads under Jukhala section (SH:- Hiring of JCB for removal of slips and clearance of drain at various RDs under Jukhala section) for the year 2022-23 Job No. 2	Rs. 99,162/-	Rs. 2,000/-	Rs. 350/-	One Month
17	A/R & M/O on Kutehla Kirayain Bagchhal road Km. 0/0 to 10/815 (SH:- C/o P.C.C as a R/wall at RD 8/142 to 8/157)	Rs. 89,434/-	Rs. 1,800/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of

Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall summarily rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2022- 6949-55

Dated:- 6-8-2022

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-1
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email:- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office.
7. Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.94,707/-Only.

Earnest Money :- Rs.1,900/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:- Maintenance of drain , hume pipe culverts and berms in km 2/00 to 4/00)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3705.00	4	5	6 Per Square Meter	7
2	Maintenance of drain include erosion, clearing , cleaning,reshaping, regarding, despending of side drain as well as catch water drains as per technical specification clause 1907 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1950.00			Per Running metre.	
3	Maintenance of Hume pipe culvert by way of clearing, cleaning erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification clause 1908 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00			Each.	
Total						

Executive Engineer,
Bilaspur Division No. II,
P.W.D., Bilaspur.

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=99,949 /-Only.
						Earnest Money:- Rs.= 2,000/-
						Time:- one Months.
Name of work :- Restoration of Rain Damages on various roads under Swarghat Sub-Division (Swahan Section)(SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-10						
Sr No.	Description of items.	Quantity	Rate In In Figure In words.	Unit	Amount	
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00 Hours	5	Per Hours	6	
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Sub-Division Engineer
 Sub-Division No. 8
 HPPWD Bilaspur-17400
 B

SCHEDULE OF QUANTITY.									
				Estimated Cost:- Rs.=99,949 /-Only.					
				Earnest Money:- Rs.= 2,000/-					
				Time:- one Months.					
Name of work :- Restoration of Rain Damages on various roads under Swarghat Sub-Division (Bagchhal Section)(SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-6									
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount		
				In Figure	In words.				
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4	127.00	5	Hours	Per Hours		6	
Terms and Condition:-									
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge								
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery								
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period								
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work								
Total									


 Engineer in Charge
 HPPWD Bilaspur-174001
 (B)

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain Damages on various roads under Swarghat Sub-Division (Baner Section)(SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-8						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3	4	5		Per Hours	6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	127.00		Hours		
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						


 Engineer Division No. 6
 HPPWD Bilaspur-17400


SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=1,02,310 /-Only.		
				Earnest Money:- Rs.= 2,100/-		
				Time:- one Months.		
Name of work :- Restoration of Rain Damages on Sh. Naina Devi ji to Toba road km 0/00 to 9/225 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 2/00 to 9/00) For the Year 2022-23 Job No.-8						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 130.00	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						


 Executive Engineer,
 District Engineer's Office,
 H.P.P.W.D., Shimoga.

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=1,02,310 /-Only.	
						Earnest Money:- Rs.= 2,100/-	
						Time:- one Months.	
Name of work :- Restoration of Rain Damages on Galwa Goolthai road km 0/00 to 35/000 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 9/00 to 25/00) For the Year 2022-23 Job No.-7							
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	3	4		5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	130.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
Bilaspur Division No. II,
B.R. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=71,316 /-Only.			
				Earnest Money:- Rs.= 1,500/-			
				Time:- one Months.			
Name of work :- Restoration of Road Damages on Deoth to Lagghat road km 0/00 to 8/00 (SH:-Hiring of Excavator cum loader/JCB and tractor with trolly for removal of slips and dressing of berms at various Rds)							
Sr No.	Description of items.	Quantity	Rate In Figure	In words.	Unit	Amount	
1	3	4	5			6	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00			Per Hours		
2	Providing one number tractor with trolly in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00			Per Hours		
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The tractor with trolly will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=1,02,310 /-Only.		
				Earnest Money:- Rs.= 2,100/-		
				Time:- one Months.		
Name of work :- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 19/00 to 25/00) For the Year 2022-23 Job No.-6						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3	4	5		Per Hours	6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavey or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	130.00				
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bilaspur Division Mo. II,
H.P.W.D., Bilaspur H.P.

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,949 /-Only.

Earnest Money:- Rs.= 2,000/-

Time:- one Months.

Name of work :- Restoration of Rain Damages on various roads under Swarghat Sub-Division (Swahan Section)(SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-7

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
				In Figure	In words.		
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4	127.00	5	Hours	Per Hours	6
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Swarghat Sub-Division
HPPWD Bilaspur-17400
Bh

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.			
				Earnest Money:- Rs.= 2,000/-			
				Time:- one Months.			
Name of work :- Restoration of Rain Damages on NH-205 CMM road km 86/00 to 105/00(SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-9							
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
		In Figure	In words.				
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00	5 Hours			Per Hours	6
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							


 Engineer
 PWD Division No. 4
 PWD Bilaspur-17400
 Bk

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,360 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain damages on Various road under Swarghat Sub Division HPPWD Swarghat (SH:- Hiring of Tractor with trolley for removal of slips at various RDs)For the Year 2022-23 Job No.-3						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3	4	5			6
1	Providing one number tractor with trolley in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavey or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	288.00	Hours		Per Hours	
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						


 Engineer
 Sub Division No. 3
 HPPWD Bilaspur-174001
 (B)

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=71,316 /-Only.

Earnest Money:- Rs.= 1,500/-

Time:- one Months.

Name of work :- Restoration of Rain Damages on various roads under Sub-Division No.-III HPPWD Bilaspur (Kothipura Section) (SH:-Hiring of Excavator cum loader/JCB and tractor with trolley for removal of slips, clearing of culverts/ drain and dressing of berms at various Rds)

Sr No.	Description of items.	Quantity		Rate		Unit	Amount
				In Figure	In words.		
1	3	4		5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00	Hours			Per Hours	
2	Providing one number tractor with trolley in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer
Kothipura Division No. 1
HPPWD Bilaspur

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=99,162 /-Only.	
						Earnest Money:- Rs.= 2,000/-	
						Time:- one Months.	
Name of work :- Restoration of Rain Damages on various roads under Kharsi Section (SH:- Hiring of JCB for removal of slips and clearance of drain at various RDs Under Kharsi Section). For the Year 2022-23(JobNo.-3)							
Sr No.	Description of items.	Quantity		Rate		Unit	Amount
				In Figure	In words.		
1	3	4		5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	126.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. II,
Bilaspur

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs. 73,883/-Only.		Earnest Money:- Rs.=1,500/-		Time:- Three Months.	
Name of Work:-Improvement of Navgoan Beri road km 4/350 to 23/700 (SH:- P/L 30 mm thick bitumionious concrete at R.D. 10/315 to 10/355 at Malokhar Chowk)							
Sr. No.	Item of work.	Quantity	Rates in		Unit.	Amount.	
			Figure.	Words.			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of slides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.00	Cubic Metre		Per Cubic Metre		
2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mounts grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density complete as per Technical Specification Clause -401 For Grading-1 material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	Cubic Metre		Per Cubic Metre		
3	Providing, laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with waterat OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and technical specification clause 406 by Mechanical means with 1km lead including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	14.00	Cubic metres		Per Cubic metre		
4	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five) per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of materials, within all leads, lifts and other incidentals as per Direction of Engineer-in-charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.00	Square metre		Per Square metre.		


5	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.60(Zero point six zero)Kilogram per Square metre . Using Manual means as per Technical Specification Clause-502 including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	140.00	Square metre		Per Square metre.
6	Providing and laying bituminous concrete 30 (Thirty) millimetr thick with 100-120 TPH batch type hot mix plant producing an average output of 75(Seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4(Five point four) to 5.6(Five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.20	Cubic metre.		Per Cubic metre
					Total:-


 Executive Engineer,
 Bilaspur Division Hq. II,
 BILASPUR P.W.D., Bilaspur M.P.

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=99,162 /-Only.	
							Earnest Money:- Rs.= 2,000/-	
Name of work :- Restoration of Rain Damages on various roads under Namhol Section (SH:- Hiring of JCB for removal of slips and clearance of drain at various RDs Under Namhol Section). For the Year 2022-23(Job No.-1)							Time:- one Months.	
Sr No.	Description of items.		Quantity		Rate In		Unit	Amount
			In Figure	In words.				
1	3	4	5					
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavey or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	126.00	Hours			Per Hours		6
Terms and Condition:-								
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge							
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period							
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work							
		Total						

Executive Engineer,
Bilaspur Division No. II,
H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,162 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain Damages on various roads under Jukhala Section (SH:- Hiring of JCB for removal of slips and clearance of drain at various RDs UnderJukhalal Section). For the Year 2022-23(JobNo.-2)						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 126.00 Hours	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						


 Engineer-in-charge,
 Bilaspur Division No. II,
 H.P.W.D., Bilaspur.

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=89,434 /-Only.	
							Earnest Money:- Rs.= 1,800/-	
							Time:- Three Months.	
Name of work :- A/R & M/O on Kutehla Kiyarian Bagchhal Road km 0/00 to 10/815 (SH:-C/O P.C.C as a R/Wall at RD 8/142 to 8/157)								
Sr No	Description of items.	Quantity		Rate In		Unit	Amount	
		In Figure	In words.	In Figure	In words.			
1	3 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 11.85	Cubic Metre	5		Per Cubic Metre	6	
2	Providing and laying cement concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803 ,1202 and 1203 Grade M-10 (1:5:10)without plum (One cement five sand ten graded stone aggregate) ,should not be less than 130 kg. (One hundred thirty kilogramme)per cum including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	37.79	Cubic metre			Per Cubic metre		
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.95	Cubic Metre			Per Cubic Metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos.			Each		
Total								

Executive Engineer,
Bilaspur Division No. II,
H.R. PWD., Bilaspur P