



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 05/09/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 03.09.2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Restoration of Rain damages on Bathoh to Neri road Km. 0/0 to 4/120 (SH:- P/L interlocking concrete block pavement in Km. 2/768 to 2/809.70 and 2/876 to 2/927).	Rs. 3,70,668/-	Rs. 7,500/-	Rs. 350/-	Three Month
2	A/R & M/O link road to village Kanguwali Km. 0/0 to 1/960 (SH:- C/o Breast wall at RD 1/765 to 1/795)	Rs. 1,56,396/-	Rs. 3200/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on S.N.B. road Km. 0/0 to 37/300 (SH:- C/o PCC as a R/wall at RD 11/855 to 11/865).	Rs. 2,54,417/-	Rs. 5100/-	Rs. 350/-	Three Month
4	Balance work for C/o Govt. Sr. Sec. School Soldha (SH:- Providing and laying Interlocking concrete block pavement at playground and providing and laying ceiling over Verandah) Deposit work	Rs. 4,98,462/-	Rs. 10000/-	Rs. 350/-	Three Month
5	Construction of Ambulance road from NH-205 to village Dagech (Moksh Dham) Km. 0/0 to 0/915 (SH:- C/o R/wall at RD 0/845 to 0/860 and 0/895 to 0/905) Deposit work	Rs. 3,70,008/-	Rs. 7400/-	Rs. 350/-	Three Month
6	Restoration of Rain damages of CMM NH-205 ?90ld NH-21) Km. 105/0 to 127/0 (SH:- Supplying of mixed material at HMP in Km. 105/0 to 127/0).	Rs. 4,99,552/-	Rs. 10000/-	Rs. 350/-	One Month
7	Constriction of Balance work of link road to village Suin Km. 0/0 to 0/900 (SH:- C/o R/wall at RD 0/685 to 0/713) Deposit work	Rs. 2,74,751/-	Rs. 5500/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on C.M.M. road NH-205 Km. 86/0 to 105/0 (SH:- C/o wire crate as a B/wall at RD 87/650 to 87/671.25)	Rs. 97,969/-	Rs. 2000/-	Rs. 350/-	Three Month
9	A/R & M/O Laraghat Bathoh Bholi road Km. 0/0 to 10/500 (SH:- C/o P.C.C. Parapets at Km. 2/300 to 2/400).	Rs. 36,174/-	Rs. 8,00/-	Rs. 350/-	Three Month
10	Restoration of Rain damages of Rajpura Chilla Charanmore road Km. 0/0 to 5/210 (SH:- C/o R/wall at RD 2/834 to 2/842)	Rs. 99,981/-	Rs. 2,000/-	Rs. 350/-	Three Month
11	A/R & M/O on link road to Deoth Dabar Km. 0/0 to 10/960 (SH:- Hiring of Excavator cum loader for removal of slips and clearance of drain and dressing of berms in Km. 3/0 to 10/960)	Rs. 55,090/-	Rs. 1,150/-	Rs. 350/-	One Month
12	Restoration of Rain damages on Laraghat Bathoh Bholi road Km. 0/0 to 10/500 (SH:- C/o R/wall at RD 1/285 to 1/291.50)	Rs. 98,694/-	Rs. 2,000/-	Rs. 350/-	Three Month
13	Restoration of Rain damages on C.M.M. road NH-205 Km. 86/0 to 105/0 (SH:- C/o wire crate as B/wall at RD 87/625 to 87/646.25)	Rs. 98,351/-	Rs. 2000/-	Rs. 350/-	Three Month
14	Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Maintenance of drain, hume pipe culverts and berms in Km. 6/0 to 8/0)	Rs. 99,739/-	Rs. 2,000/-	Rs. 350/-	Three Month
15	Widening of Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- Improvement of curve in Km. 16/320 to 16/390 and 16/420 to 16/495)	Rs. 75,927/-	Rs. 1,600/-	Rs. 350/-	Three Month
16	Restoration of Rain damages on Bathoh Jeora road Km. 0/0 to 6/0 portion Km. 3/0 to 6/0) (SH:- Hiring of Excavator cum loader/JCB for Katcha drain removal at slips and dressing of road in km. 3/0 to 4/900)	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
17	Restoration of Kothipura Parohi Deoth road Km. 0/0 to 8/780 (SH:- C/o B/wall at RD 0/225 to 0/240) Reliance Deposit	Rs. 80,328/-	Rs. 1,700/-	Rs. 350/-	Three Month

18	Repair and Maintenance on Navgaon Beri road Km. 4/350 to 23/700 (SH:- Providing and laying Interlocking concrete pavement at RD 10/910 to 10/923).	Rs. 89,395/-	Rs. 1,800/-	Rs. 350/-	Three Month
19	Repair and Maintenance of Veterinary Hospital in Deoth Bhajoon Building in Distt. Bilaspur (HP) (SH:- Repair of Plaster and Distempering) DC Deposit	Rs. 37,405/-	Rs. 800/-	Rs. 350/-	Three Month
20	Restoration of Rain damages on Rajpura Chilla Charamore road Km. 0/0 to 4/400 (SH:- C/o R/wall at RD 2/114 to 2/123)	Rs. 49,988/-	Rs. 1000/-	Rs. 350/-	Three Month
21	Construction of Govt. Sr. Secondary School Ranikotla in Distt. Bilaspur (HP) (SH:- P/F G.I. wire in boundary wall RD 0/0 to 0/030) Deposit work	Rs. 48,215/-	Rs. 1000/-	Rs. 350/-	Three Month
22	Restoration of Rain damages on Namhol Ashamajari road Km. 0/0 to 10/555 (SH:- C/o R/wall at RDs 8/440 to 8/488)	Rs. 99,903/-	Rs. 2000/-	Rs. 350/-	Three Month
23	Restoration of Rain damages link road to village Kikranwali Km. 0/0 to 1/960 (SH:- C/o wire crate as a B/wall at RD 1/585 to 1/606.25)	Rs. 98,596/-	Rs. 2000/-	Rs. 350/-	Three Month
24	Restoration of Rain damages link road to village Bada Saloor Kauranwali Km. 0/0 to 2/155 (SH:- C/o wire crate as a B/wall at RD 0/600 to 0/621.25)	Rs. 98,024/-	Rs. 2000/-	Rs. 350/-	Three Month
25	Restoration of Rain damages on link road Kothipura Parohi Deoth road Km. 0/0 to 8/600 (SH:- C/o R/wall at RD 1/930 to 1/940).	Rs. 98,961/-	Rs. 2000/-	Rs. 350/-	Three Month
26	Restoration of Rain damages on Bathoh to Neri road Km. 0/0 to 4/120 (SH:- P/L Interlocking concrete block pavement in Km. 2/927 to 2/953.50)	Rs. 97,587/-	Rs. 2000/-	Rs. 350/-	Three Month
27	Restoration of Rain damages on link road to Brampukher Deoth Sheli Km. 0/0 to 11/300 (SH:- Hiring of Excavator cum loader for removal of slips, clearing of road side drain and dressing of berm Km. 5/0 to 8/0) for the year 2022-23 Job No. 6	Rs. 99,949/-	Rs. 2000/-	Rs. 350/-	One Month
28	Restoration of Rain damages on CMM road NH-205 Km. 86/0 to 127/0 (SH:- Hiring of Excavator cum loader for removal of slips, clearing of road side drain and dressing of berm Km. 105/0 to 116/0) for the year 2022-23 Job No. 4	Rs. 99,949/-	Rs. 2000/-	Rs. 350/-	One Month
29	Restoration of Rain damages on link road to Deoth Dabbar road Km. 0/0 to 10/960 (SH:- Hiring of Excavator cum loader for removal of slips, clearing of road side drain and dressing of berm Km. 6/0 to 10/960) for the year 2022-23 Job No. 3	Rs. 99,949/-	Rs. 2000/-	Rs. 350/-	One Month
30	Restoration of Rain damages on link road to Deoth Dabbar road Km. 0/0 to 10/960 (SH:- Hiring of Excavator cum loader for removal of slips, clearing of road side drain and dressing of berm Km. 0/0 to 6/0) for the year 2022-23 Job No. 2	Rs. 99,162/-	Rs. 2000/-	Rs. 350/-	One Month
31	Construction of link road to village Tarambadi Km. 0/0 to 1/0 (SH:- C/o Hume pipe culvert 900mm dia with wing wall at RD 0/480 near house of Sh. Sant Ram) Deposit work	Rs. 84,705/-	Rs. 2000/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall summarily rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

Dated:- 25-08-2022

No.PW/NBT/CB/Tender-State/EA-1/2022- 7797-803

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-1
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email:- eeict-pwd-shi@hp.gov.in along with copy of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD Bilaspur.

SCHEDULE OF QUANTITY.

Estimated cost:- 3,70,668/-Only.

Earnest Money :- 7,500/-

Time:- Three Months.

Name of work :- Restoration of Rain damages on Bathoh to Neri road km.0/0 to 4/120 (SH:-P/L interlocking concrete block pavement in km. 2/768 to 2/809.70 and 2/876 to 2/927)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Scarifying existing surface to a depth of 50 mm by manual means scarifying existing granular surface to a depth of 50 mm and disposal of scarified material within a lift upto 3 meters and lead upto 1000 m as per Technical Specification Clause including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge .The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	458.84	Square metre.		Per Square metre.	7
2	Construction of gravel/soil aggregates, sub-base (base/ providing well graded material of nominal maximum size grading 80mm as per Table 2.3 of IRC SP 77-2008, spreading in uniform layers with tractor mount appropriate grading arrangement on prepared surface mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specification contained in Para 2.2.3.7 and 3.7 of IRC SP 77-2008 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge .The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	68.83	Cubic metres		Per Cubic metre	
3	Providing, laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with waterat OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and technical specification clause 406 by Mechanical means with 1km lead including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	45.88	Cubic metres		Per Cubic metre	
4	Providing and laying Interlocking concrete block pavement, having thickness, 80mm (Eighty millimetre) as per drawings and Technical Specification clause 1504, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	458.84	Square metre.		Per Square metre.	
Total						

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.1,56,396/-Only.
						Earnest Money :- Rs.3200/-
						Time:- Three Months.
NAME OF WORK:- A/R & M/O link road to Village Kanguwali km. 0/0 to 1/960(SH):- C/O Breast wall at R.D. 1/765 to 1/795).						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1,603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing ,and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of blasting work/soft rock and 1/10th of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.70	Cubic Metre		Per Cubic Metre	
2	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil,ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. Any loss to the public/private	17.10	Cubic Metre		Per Cubic Metre	
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.52	Cubic metre.		Per Cubic metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the	25.00	Nos.		Each.	
						Total:-
						Division No. II,

Bilaspur Division No. II,
HP, PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.2,54,417/-Only.			
		Earnest Money :- Rs.5,100/-			
		Time:- Three Months.			
NAME OF WORK:- Restoration of Rain damages on S.N.B road km 0/00 to 37/300 (SH:-C/O PCC as a R/Wall at RD 11/855 to 11/865)					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2	3	4	5	6
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.70	Cubic Metre		Per Cubic Metre
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1:5:10) without plum. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	111.80	Cubic metre.		Per Cubic metre
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.10	Cubic metre.		Per Cubic Metre
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.		Each
Total					

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,98,462/-Only.

Earnest Money :- Rs.10,000/-

Time:- Three Months.

NAME OF WORK:- Balance Work for C/O Govt. Sr. Sec.School Soldha (SH:- Providing and Laying Interlocking concrete block pavement at play ground and Providing & Laying ceiling over verandah) (Deposit Work)

Sr No. Description of items.

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	128.40	Cubic Metre		Per Cubic Metre	7
2	Stone soling properly hand packed filling interstices with kharanja Stone and consolidating with power road road to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.20	Cubic metres		Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete, for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8)(One Cement four sand eight graded crushed stone aggregate) 40mm (Forty millimetre size) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802,803,1203 and 1205.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges. The rates includes octroi, royalty, Malkhana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.15	Cubic metres		Per Cubic metre	
4	Providing and laying Interlocking concrete block pavement, having thickness, 60mm (Sixty millimetre) as per drawings and Technical Specification clause 1504, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	642.00	Square metre.		Per Square metre.	

5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings, framed guards, bars ladders, railing brackets and similar work, including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.26	Quintal.		Per Quintal.
6	Providing and fixing M.S. BP Sheet 1.66mm One point sixty six millimetre (Two) millimetre thick in eaves board /facia /soffit /ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge. (Base members of steel work shall be measured & paid separately) including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.46	Square Meter		Per Square metre
7	Applying priming coat over new steel and other metal surfaces after and including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wood scrapers and sand paper complete with readymixed priming paint brushing red lead, Red oxide/zinc oxide chrome including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.46	Square Meter		Per Square Meter
8	Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter :- Ready mixed paint other than white including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.46	Square Meter		Per Square Meter
Total					

Executive Engineer,
Bilaspur Division No. II,
H.P. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,70,008/-Only.

Earnest Money :- Rs.7,400/-

Time:- Three Months.

NAME OF WORK:- Construction of Ambulance road from NH-205 to Village Dagsech (Moksh Dham) km 0/00 to 0/915 (SH:- C/O R/Wall at RD 0/845 to 0/860 and 0/895 to 0/905) (Deposit work)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2	3	4	5	6	7	
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	69.40	Cubic Metre			Per Cubic Metre	7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1:5:10) without plumb, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	158.95	Cubic metre.			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.00	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.00	Nos.			Each.	
Total							

SCHEDULE OF QUANTITY.						
			Estimated Cost:- Rs.=4,99,552-Only.			
			Earnest Money:- Rs. 10,000/-			
			Time:- One Month.			
Name of work :- Restoration of Rain Damages of CMIM NH-205 (old NH-21) Km 105/00 to 127/00 (SH:- Supplying of mixed material at HMP in Km 105/00 to 127/00)						
Sr.No	Sub-head and item of work.	Quantity	Rate		Unit	Amount
			Figure	words.		
1	Providing Mixed material for bitumenious concrete with 100-120 TPH batch type nearest Hot Mix plant producing an average output of 75 Tonnes per hour using crushed aggregates of specified grading ,premixed with bitumenious binder@ 5.4 to 5.6 percent of mix as per Morth specification clause No.503 complete in all respects The bitumenious, aggregate,sand and filler will be arranged by the supplier in all leads and lifts including loading of mixed material at Hot Mix plant . The mixed material will be carried by departmental tipper and work will be executed as per direction and entire satisfaction of Engineer in charge.	64.60			per cubic metre	
					Total Rs	

Executive Engineer,
Bilaspur Division No. II,
HP, PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.2,74,751/-Only.									
Earnest Money :- Rs.5,500/-									
Time:- Three Months.									
NAME OF WORK:- Construction of Balance work of link road to village Suin km 0/00 to 0/900 (SH:-C/OR/Wall at RD 0/685 to 0/713) (Deposit Work)									
Sr No.									
Description of items.									
Quantity									
Rates in									
Figure.									
Words.									
Unit									
Amount									
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.60	Cubic Metre			Per Cubic Metre	7		
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	116.48	Cubic metre.			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.24	Cubic metre.			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.00	Nos			Each.			
Total									

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.			Estimated cost:- Rs.97,969/-Only.			
			Earnest Money :- Rs.2,000/-			
			Time:- Three Months.			
NAME OF WORK:-Restoration of Rain-damages on C.M.M road NH-205 km 86/00 to 105/00(SH:- C/O Wire crate as a B/wall at RD 87/650 to 87/671.25)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
		3	4	5	6	7
1	2	31.02	Cubic Metre		Per Cubic Metre	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Cubic Metre				
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301, including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.45	Cubic metre		Per Cubic metre	
						Total:-

Executive Engineer,
Bilaspur Division No. II,
H.P./PWD., Bilaspur

SCHEDULE OF QUANTITY.							
					Estimated Cost:- Rs.=36,174/-Only.		
					Earnest money:-Rs. 8,00/-		
					Time:- Three Months.		
NAME OF WORK:- A/R & M/O Laraghat Bathoh Bholi road km 0/00 to 10/500 (SH:- C/O PCC Parapets at km 2/300 to 2/400)							
Sr No.	Description of items.	Quantity		Rates in.		Unit	Amount
				Figure	Words.		
1	2	3	4	5	6	7	
1	Earth work in Excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D Technical specification Clause 305.1 and as per direction of the Engineer-in-charge including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty milimetres) compacted thickness including shorting and strutting and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out duing dewatering as per the direction of Engineer-in-Charge and carriage of materials within all leads and lifts. The rate includes octori, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.36	Cubic Metre		Per Cubic Metre		
2	Providing and laying mechanically mixed and vibrated concrete, for plain concrete in open foundations for all type of structure complete of plain cement concrete grade M-10(Nominal mixed 1:3:6)(One Cement three sand six graded /crushed stone aggregate)20mm(Twenty millimetre)nominal size)on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802.803,1202 and 1203 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.25	Cubic metre.		Per Cubic Metre		
						Total:-	

Executive Engineer,
Bilaspur Division No. II,
H.P. P.W.D., Bilaspur.

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.99,981/-Only.									
Earnest Money :- Rs.2,000/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain damages on Rajpura Chilla Charnmore Road km 0/00 to 5/210 (SH:-C/O R/wall at RD 2/834 to 2/842)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
		Figure.	Words.	Figure.	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.72	Cubic Metre		Per Cubic Metre				
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1.5.10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.32	Cubic metre.		Per Cubic metre				
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.		Each.				
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.84	Cubic metre.		Per Cubic Metre				
Total									

Executive Engineer,
Bhaspar Division No. II,
H.R. PWD., Bhaspar

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs. =-55090-Only.
				Earnest Money:- Rs. -1150/-only
				Time:- One Month.
Name of work :- A/R& M/O on Link Road to Deoth Dabar Km 0/0 to 10/960 (SH:- Hiring of Excavator cum Loader for removal of slips and clearance of drain & Dressing of berms in Km 3/00 to 10/960)				
Sr.No	Sub-head and item of work.	Quantity	Rate Figure words.	Unit Amount
1	Providing one number Excavator cum loader /JCB in good conditions on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer-in-Charge .	70.00		per hours
Terms & Conditions				
1	The work will be executed as per H.P.P.W.D specifications and as per the direction of Engineer-in-Charge.			Total Rs.
2	The excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery.			
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period			
4	The contractor will be fully responsible for any loss/damages to any private Govt.property during the execution of work.			

Executive Engineer
Bilaspur Division No. 1,
H.P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.98,694/-Only.

Earnest Money :- Rs.2,000/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain damages on Laraghat Bathoh Bholi road km 0/00 to 10/500 (SH:-C/O R/Wall at RD 1/285 to 1/291.50)

Sr No.

Description of items.

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2	3	4	5	6	7	
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.57	Cubic Metre			Per Cubic Metre	7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1:5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.64	Cubic metre.			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.70	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Nos.			Each.	
Total							

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.									
NAME OF WORK:-Restoration of Rain-damages on C.M.M road NH-205 km 86/00 to 105/00(SH):- C/O Wire crate as a B/wall at RD 87/625 to 87/646.25)									
Sr No. Description of items.									
Estimated cost:- Rs.98,351/-Only.									
Earnest Money :- Rs.2000/-									
Time:- Three Months.									
Quantity									
Rates in									
Figure. Words.									
Unit									
Amount									
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiselling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.00	Cubic Metre		Per Cubic Metre				
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.45	Cubic metre		Per Cubic metre				
Total:-									

Executive Engineer,
Bilaspur Division No. II,
H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.99,739/-Only.

Earnest Money :- Rs.2,000/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Navgoan Beri road km 4/350 to 23/700 (SH:- Maintenance of drain , hume pipe culverts and berms in km 6/00 to 8/00)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 3927.00	4 Square Meter	5	6 Per Square Meter	7
2	Maintenance of drain include erosion, clearing , cleaning,reshaping, regarding, deepending of side drain as well as catch water drains as per technical specification clause 1907 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1870.00	Running metre		Per Running metre.	
3	Maintenance of Hume pipe culvert by way of clearing, cleaning erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification clause 1908 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Nos.		Each.	
Total						

Executed by signature of,
Bilaspur Division No. II,
H.P. PWD., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.75,927/-Only.						
Earnest Money :- Rs.1,600/-						
Time:- Three Months.						
NAME OF WORK:- - Widening of Thatch Sikroha Neri Jukhala road km 0/0 to 18/690 (SH:- Improvement of curve in km 16/320 to 16/390 and 16/420 to 16/495)						
Sr No.	Description of items.	Quantity	Figure.	Words.	Unit	Amount
1		3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing .and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 34.61 cubic metre @ Rs. 170/- Per cubic metre shall be done on pro-rata basis in each running bill for this item	692.13	Cubic metres.		Per Cubic metre	
			Total			


 Executive Engineer,
 Bilaspur Division No. II,
 H.P. PWD., Bilaspur H.P.

SCHEDULE OF QUANTITY.

16

Name of work :- Restoration of Rain damages on Bathoh Jeora Road km 0/00 to 6/00 (portion km 3/00 to 4/900)
removal at slips and dressing of road in km 3/00 to 4/900)

Estimated Cost:- Rs.=99,949 /-Only.
Earnest Money:- Rs.= 2,000/-
Time:- one Months.

Sr No. (SH:- Hiring of Excavator cum loader/JCB for katcha drain

Description of items.

1	Quantity	Rate In		Unit	Amount
		In Figure	In words.		
1	2	3	4	5	6
1	127.00	Hours	7	8	
Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
Total					

Executive Engineer,
Bilaspur Division No. 11,
HP/PWD., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs. 80,328/-Only.

Earnest Money :- Rs.1,700/-

Time:- Three Months.

Reliance Deposit

NAME OF WORK:- Restoration on Kothipura Prohi Deoth road km 0/00 to 8/780 (SH:- C/O B/wall at RD 0/225 to 0/240). Reliance Deposit

Sr No. Description of items.

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable compacted thickness including shorting and shuttering and pumping not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	4	5	6	7
2	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300, 1603.1, 1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road way camber, embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) of blasting work/soft rock and 1/10th of jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.36	Cubic Metre		Per Cubic Metre	
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1:5:10) without plumb including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.58	Cubic Metre		Per Cubic Metre	
		35.25	Cubic metre.		Per Cubic metre	

4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octon, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.			Each.	
Total							


 Suburban Division No. 4
 WWD Bilaspur-468

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.89,395/-Only.
Earnest Money :- Rs.1,800/-
Time:- Three Months.

NAME OF WORK:- Repair and Maintenance on Navgaon Beri road km 4/350 to 23/700(SH):-Providing and Laying Interlocking concrete block pavement at RD 10/910 to 10/923)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
		3	4	5	6	7
1	2 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable compacted thickness including shorting and shuttering and pumping not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.43			Per Cubic Metre	
2	Providing, laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with waterat OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and technical specification clause 406.by Mechanical means with 1km lead including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.21			Per Cubic metre	
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203, P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand : six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.21			Per Cubic Metre	
4	Providing and laying Interlocking concrete block pavement, having thickness, 80mm (Eighty millimetre) as per drawings and Technical Specification clause 1504, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	74.75			Per Square metre.	
Total						



SCHEDULE OF QUANTITY.

19

Estimated cost:- Rs.37,405/-Only.
Earnest Money :- Rs.8,00/-
Time:- Three Months.

NAME OF WORK:- Repair & Maintenance of Vetnary Hospital in Deoth Bajoon Building in Distt Bilaspur (HP) (SH):- Repair of plaster & Distempering) (D.C Deposit)

Sr No.

Description of items.

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Repair of plaster in patches of 2.50 Sqm. and under 10 to 15mm thick including cutting the patch in proper shape and replastering the surface with cement mortar 1:4(One Cement four sand) of the wall including disposal of rubbish to the dumping ground with in all leads including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	3 92.97	Square Meter	5	Per Square metre.	7
2	Distempering two coats with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	513.52	Square Meter		Per Square Meter	
3	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease, dirt and other foreign matter sand papering and knotting with ready mix paint brushing with white lead for priming including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	74.82	Square Meter		Per Square Meter	
4	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matters, sand papering and stopping including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	74.82	Square Meter		Per Square Meter	
5	Providing and fixing M.S. BP Sheet 1.66mm One point sixty six milimetre)to 2mm (Two)milimetre thick in eaves board /facia /soffit s/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge. (Base members of steel work shall be measured & paid separately) including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	6.00	Square Meter		Per Square metre	
Total						

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.49,988/-Only.

Earnest Money :- Rs.1,000/-

Time:- Three Months.

R/Wall at RD 2/114 to 2/123)

NAME OF WORK:- Restoration of Rain damages on Rajpura Chilla Charnmore Road km 0/00 to 4/400 (SH:-C/O

Description of items.

Sr No.	Quantity	Figure.	Words.	Unit	Amount
1	3	4	5	6	7
1	7.43	Cubic Metre		Per Cubic Metre	7
2					
3	21.78	Cubic metre.		Per Cubic metre	
4	10.00	Nos		Each.	
	3.02	Cubic metre.		Per Cubic Metre	
Total					

2

Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of slides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

2

Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses.802.803,1202 and 1203 (1:5:10) without plum. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

3

Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

4

Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.						
		Estimated Cost:- Rs.=48,215/-Only.				
		Earnest Money:-Rs.=1,000/-				
		Time:- Three Months				
Name of Work :- Construction of Govt. Senior Secondary School Ranikotla in Distt.Bilaspur(HP).(SH:- P/F G.I wire in boundary wall Rd 0/00 to 0/030) (Deposit Work)						
Sr. No.	Description	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Steel work welded in built up sections, trusses and framed work, including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint In gratings framed guards , bars ladders , railing brackets and similar work including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.08	Quintal.		Per Quintal.	
2	Supplying and fixing wovenplains G.I. wire fencing of mesh 50mm to 150mm to any type of standard rails, straining bolts, etc including provision of binding wire, staples including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other constuction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Square metre.		Per Square metre.	
3	Painting two costs (excluding priming cost on new steel and other metal surfaces eith enamel paint brushin to give an even shade including cleaning the surface of all dirt,dust and other foregin matters :- Enamel paint other than white ,including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other constuction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	108.00	Square Meter		Per Square Meter	
Total:-						

Bilaspur (H.P.)

 No. 1

 D.D. No. 1/2017

SCHEDULE OF QUANTITY.

22

SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,903 /-Only.			
		Earnest Money:- Rs.= 2,000/-			
		Time:- Three Months.			
Name of work :- Restoration of Rain damages on Namhol Ashamajhari road km 0/0 to 10/555) (SH:- C/o R/wall at RDs 8/440 to 8/488)					
Sr No.	Description of items.	Quantity	Rate In In Figure In words.	Unit	Amount
1	3 1 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 19.84	5	Cubic Metre Per Cubic Metre	6
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203(1.5:10) without plum, including carriage of material within all leads, lifts and other incidentals as per direction of Engineer -in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.32		Cubic Metre Per Cubic Metre	
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00		Cubic Metre Per Cubic Metre	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00		Nos. Each	
Total					


 Government of Karnataka
 Highway Division
 BTL/WD/BTL/WD/1/2014

SCHEDULE OF QUANTITY.

	SCHEDULE OF QUANTITY.					Estimated cost:- Rs.98,596/-Only.
						Earnest Money :- Rs.2,000/-
						Time:- Three Months.
NAME OF WORK:-Restoration of Rain-damages link road to village kikanwali km 0/00 to 1/960(SH):- C/O Wire crate as a B/wall at RD1/585 to 1/606.25)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsand lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.91	Cubic Metre		Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.45	Cubic metre		Per Cubic metre	
					Total:-	

Executive Engineer,
Bilaspur Division No. II,
HP. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

		SCHEDULE OF QUANTITY.		Estimated cost:- Rs.98,024/-Only.		
				Earnest Money :- Rs.2,000/-		
				Time:- Three Months.		
NAME OF WORK:-Restoration of Rain-damages link road to village Bada Saloor Kauranwali km 0/00 to 2/155(SH):- C/O Wire crate as a B/wall at RD 0/600 to 0/621.25)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification .2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax. levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.45	Cubic Metre		Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301, including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.45	Cubic metre		Per Cubic metre	
						Total:-

Executive Engineer,
Bilaspur Division No. II,
HP. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.98,961/-Only. Earnest Money :- Rs.2,000/- Time:- Three Months.				
NAME OF WORK:- Restoration of Rain damages on link road Kothipura Parohi Deoth road km 0/00 to 8/600 (SH:-C/O R/Wall at RD 1/930 to 1/940)						
Sr No.	Description of items.	Quantity	Figure.	Words.	Unit	Amount
1	2 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials upto any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 15.60	4 Cubic Metre	5 5	6 Per Cubic Metre	7 7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1-5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.65	Cubic metre.		Per Cubic metre	
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.00	Nos.		Each.	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.25	Cubic metre.		Per Cubic Metre	
Total						

SCHEDULE OF QUANTITY.

Estimated cost:- 97,587/-Only.

Earnest Money :- 2,000/-

Time:- Three Months.

Name of work :- Restoration of Rain damages on Bathoh to Neri road km.0/0 to 4/120 (SH:-P/L interlocking concrete block pavement in km. 2/927 to 2/953.50)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Scarifying existing surface to a depth of 50 mm by manual means scarifying existing granular surface to a depth of 50 mm and disposal of scarified material within a lift upto 3 meters and lead upto 1000 m as per Technical Specification Clause including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 120.80	4	5	6 Per Square metre.	7
2	Construction of gravel/soil aggregates, sub-base (base) providing well graded material of nominal maximum size gading 80mm as per Table 2.3 of IRC SP 77-2008, spreading in uniform layers with tractor mount appropriate grading arrangement on prepared surface mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specification contained in Para 2.2.3.7 and 3.7 of IRC SP 77-2008 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.12			Per Cubic metre	
3	Providing, laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with waterat OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 KN weight to achieve the desired density including lighting, barncading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and technical specification clause 406 by Mechanical means with 1km lead including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	12.08			Per Cubic metre	
4	Providing and laying Interlocking concrete block pavement, having thickness, 80mm (Eighty millimetre) as per drawings and Technical Specification clause 1504, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	120.80			Per Square metre.	
Total						

Executive Engineer,
Bilaspur Division No. II,
HP. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=99,949 /-Only.	
						Earnest Money:- Rs.= 2,000/-	
						Time:- one Months.	
Name of work :- Restoration of Rain damages on link road to Brampukhar Deoth Shelli km 0/00 to 11/300 (SH:- Hiring of Excavator cum loader for removal of slips , clearing of road side drain & dressing of berm km 5/00 to 8/00) For the Year 2022-23 Job No.-6							
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
		In Figure		In words.			
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00	Hours	5		Per Hours	6
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
Bilaspur Division No. II,
HP, PWD, Bilaspur (H.P.)

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=99,949 /-Only.
							Earnest Money:- Rs.= 2,000/-
							Time:- one Months.
Name of work :- Restoration of Rain damages on CMM road NH-205 km 86/00 to 127/00 (SH:- Hiring of Excavator cum loader for removal of slips , clearing of road side drain & dressing of berm km105/00 to 116/00) For the Year 2022-23 Job No.-4							
Sr No.	Description of items.	Quantity	Rate In In Figure	In words.	Unit	Amount	
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00	5	Hours	Per Hours	6	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
Bilaspur Division No. II,
HP. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=99,949 /-Only.	
						Earnest Money:- Rs.= 2,000/-	
						Time:- one Months.	
Name of work :- Restoration of Rain damages on link road to Deoth Dabbar road km 0/00 to 10/960 (SH:- Hiring of Excavator cum loader for removal of slips , clearing of road side drain & dressing of berm km 6/00 to 10/960) For the Year 2022-23 Job No.-3							
Sr No.	Description of items.	Quantity		Rate In In Figure	In words.	Unit	Amount
1	3	4		5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavey or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	127.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. II,
HP, PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,162 /-Only. Earnest Money:- Rs.= 2,000/- Time:- one Months.		
Name of work :- Restoration of Rain damages on link road to Deoth Dabbar road km 0/00 to 10/960 (SH:- Hiring of Excavator cum loader for removal of slips , clearing of road side drain & dressing of berm km 0/00 to 6/00) For the Year 2022-23 Job No.-2						
Sr No.	Description of items.	Quantity	Rate In In Figure	In words.	Unit	Amount
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 126.00	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bilaspur Division No. II,
H.P. PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs. 84,705/-Only.

Earnest Money :- Rs.1,700/-

Time:- Three Months.

NAME OF WORK:- Construction of link road to Village Tarambadi km 0/00 to 1/00 (SH:- C/O Hume pipe culvert 900 mm dia with wing wall at Rd 0/480 Near house of Sh. Sant Ram) (Deposit

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 38.17	4 Cubic Metre	5 Per Cubic Metre	6 Per Cubic Metre	7 7
2	Providing and laying mechanically mixed and vibrated concrete, for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8)(One Cement four sand eight graded crushed stone aggregate) 40mm (Forty millimetre size) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802,803,1203and 1205.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.81	Cubic metres	Per Cubic metre		
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 .P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement three sand :six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.31	Cubic metres	Per Cubic metre		
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses 802,803,1202 and 1203 (1:5:10) without plum. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.40	Cubic metre.	Per Cubic metre		

5	Providing and laying(to level or slopes)900mm dia(Nine hundred millimetre dia)reinforced cement concrete pipe I.S.Class NP2 for culverts on first class bedding of granular material in single row, including fixing collars, with cement mortar 1:2(One Cement two sand)but excluding the cost of excavation, M.O.R.D Technical specification clause 1108 (including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges. The rates includes octroi,royalty ,Malkana toll tax goods and service tax,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Running metre.		Per Running metre.	
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.80	Cubic metre.		Per Cubic Metre	
7	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.		Each.	
Total						

Executive Engineer
 Bypass Division No. 1
 B.P.V.D. Bilaspur-174001