

**Himachal Pradesh
Public Works Department**

NO/PW/SNG/CB/E-16/Tender/22- 6625- 50

Dated: -18.08.2022

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.
eeict-pwd-shi@hp.gov.in

Subject: -Publication of Tender Notice.

Sir,

Enclosed please find herewith notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla -2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

Encl: -NIT and Schedule of Quantity

Yours faithfully,


Executive Engineer
Sangrah Division
HPPWD Sangrah

Copy forwarded to the following for information and necessary action :-

1. The Engineer -in- Chief, , HPPWD Shimla-2 please
2. The Chief Engineer (SZ), HPPWD Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. Sirmour at Nahan Please.
4. The SDM Sangrah please.
5. The Superintending Engineer, 12th Circle HPPWD Nahan please.
6. The BDO Sangrah please.
7. All the Assistant Engineers under this division to display on their respective Notice Boards.
8. The Notice Board.


Executive Engineer
Sangrah Division
HPPWD Sangrah

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
SHORT TERM NOTICE INVITING TENDERS**

Sealed item rate tender on from 6 & 8 are hereby invited by the Executive Engineer, Sangrah Division, HP.PWD. Sangrah on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form-23.08.2022 up to 04:00 PM

Date and time of issue/Sale of tender form-25.08.2020 up to 11:00 AM

Date and time of receipt of tender form-26.08.2022 up to 11:00 AM

Date and time of opening tender form-26.08.2022 at 11:30 AM

The tender form can be had from the office of the Executive Engineer against Cash (**Non-refundable**). The earnest money should be in the shape of National Saving Certificate/Time deposit/Saving Account in any of the Post office in H.P. duly pledged in favour of the Executive Engineer Sangrah Division HPPWD Sangrah must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for **75 days**. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.

Sr. No.	Name of work	Estimated cost	EMD	Cost of Tender	Time Allowed	Class of Contractor
1.	Restoration of rain damages on C/O link road to village Bogdhar to Manal km. 0/00 to 4/450 (SH:- Hiring of JCB for removal of slips)	1,53,000/-	3,100/-	Rs. 350/-	03 Months	Class C & D only.

2.	Construction of Helipad Ground Near Gali Cutting at Bogdhar (SH:- Formation cutting in earth work 0/015 to 0/030) Under Deposit	4,81,926/-	9,700/-	Rs. 350/-	03 Months	Class C & D only.
3.	Construction of link road from Tonda Panjah Arlu road km. 0/00 to 0/00 to 9/00 (C/O 5/7 mtr wide formation cutting in km. 8/745 to 9/00) Under MNP	4,73,402/-	9,500/-	Rs. 350/-	03 Months	Class C & D only.
4.	Restoration of rain damages on Link road to Village Tali to Nau km. 0/00 to 2/515 (SH:- Hiring of JCB for removal of slips)	60,300/-	1,300/-	Rs. 350/-	03 Months	Class C & D only.
5.	R/R damages on Haripurdhar Korag Bedol Road Km. 0/00 to 11/500 (SH:- C/O B/wall in PCC at RD. 5/925 to 5/947)	2,04,145/-	4,100/-	Rs. 350/-	03 Months	Class C & D only.
6.	Restoration of Rain Damages on various road under Nohradhar Sub-Division. (SH:- Removal of slips)	2,50,000/-	5000/-	Rs. 350/-	03 Months	Class C & D only.
7.	C/O PHC Building at Jarag Distt. Sirmour (H.P) (SH: Flooring, Gate, Railing, Painting & Distempering etc)	2,39,884/-	4,800/-	Rs. 350/-	03 Months	Class C & D only.

Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ latest GST No / EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
- 1 Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected.

- 2 The offer shall remain valid up to 75 days.
- 3 The contractors/ firm must quote their rates in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
- 4 The tender of those contractors/firm will not considered whose previous performance is not found satisfactory.
- 5 Note: - All the rates are including Octroi, Royalty, Malkhana, Tolltax, GST or other taxes imposes by the Govt.

The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable. Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021.


Executive Engineer,
Sangrah Division,
HP.PWD, Sangrah.

NO/PW/SNG/CB/E-16/Tender/22-

Dated:-

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-2 please.
2. The Chief Engineer (SZ) HPPWD Shimla-2 please.
3. The Deputy Commissioner Distt. at Nahan please.
4. The Superintending Engineers 12th Circle HPPWD Nahan please.
5. The SDM/BDO, Sangrah please.
6. All the Assistant Engineers under this Division.
7. The Drawing Branch of this office.
8. Notice Board.


Executive Engineer,
Sangrah Division,
HP.PWD, Sangrah.

1

SCHEDULE OF QUANTITY

Estimated Cost:- 1,53,000/-
Earnest Money:- 3,100/-
Time :- Two Month

Name of work:- Restoration of rain damages on C/O link road to village Bogdhar to Manal km. 0/00 to 4/450 (SH:- Hiring of JCB for removal of slips)

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Hiring of excavator-cum-loader for removal of land slide, slip clearance including cutting and trimming of slopes and disposal of cut materials of all kinds of soil with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. No breakdown will be included in hire charges due to any kind of hindrance. The work shall be executed as per the HP PWD specifications within all leads, lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	170.00	per Hour			
Total						


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

SCHEDULE OF QUANTITY

Name of Work:- Construction of Helipad Ground Near Gali Cutting at Bogdhar (SH:- Formation cutting in earth work 0/015 to 0/030)
Under Deposit

Estimated Cost:- 4,81,926/-			
Earnest Money:- 9,700/-			
Time :- Two Month			
Sr. No	Description of Item	Net Quantity	Unit
1	Excavation in earth work in hilly area all height and depths and in all kinds of soils including saturated soil comprising of mixed soil ordinary rock and hard rock. All works road rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chieseling and wedging out rock(where blasting is prohibited). All earth work in cutting/ excavation, including rock excavation shall be carried out true to lines grades sides slopes width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge in conformity with the requirement of technical specification of Rural road August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable cut material and specified manner, including arrangement of dumping site trimming, filling of unvenness blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads, and lifts at the locatuion specified in the tender document or as directed by the Engineer-in-Charge for smooth riding. The recovery for stones where useful or not i.e. 239.62(TWO HUNDRED THIRTY NINE POINT SIXTY TWO)cubic metre @ 170/- (Rs. ONE HUNDRED SEVENTY) only per cubic metre shall be effected on pro-rata basis Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	3993.75	cubic metre
			Per cubic metre
Total			


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

(3)

SCHEDULE OF QUANTITY

Name of Work:- Construction of link road from Tonda Panjah Arlu road km. 0/00 to 9/00 (C/O 5/7 mtr wide formation cutting in km. 8/745 to 9/00) Under MNP				Estimated Cost:- 4,73,402/-		
				Earnest Money:- 9,500/-		
				Time :- Two Month		
Sr. No	Description of item	Net Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Excavation in earth work in in hilly area all height and depths and in all kinds of soils including saturated soil comprising of mixed soil ordinary rock and hard rock. All works road rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc, and to protect stability of hill side.Rock shall be excavated with chieseling and wedging out rock(where blasting is prohibited).All earth work in cutting/ excavation, including rock excavation shall be carried out true to lines grades sides slopes,width, camber,super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge in conformity with the requirement of technical specification of Rural road August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable cut material and specified manner,including arrangement of dumping site trimming,filling of unvenness blindage and finishing of the road to specified diamensions including disposal of surplus materials with all leads, and lifts at the locatuion specified in the tender document or as directed by the Engineer-in-Charge for smooth riding. The recovery for stones where useful or not i.e. 317.16(THREE HUNDRED SEVENTEEN POINT SIXTEEN)cubic metre @ 170/- (Rs. ONE HUNDRED SEVENTY) only per cubic metre shall be effected on pro-rata basis.Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor,which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer-in - Charge.	3379.51	cubic metre			
Total						


Executive Engineer
H.P. P.W.D. Division
Sangrah - 173023

(6)

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Link road to Village Tali to Nau km. 0/00 to 2/515 (SH:- Hiring of JCB for removal of slips)					Estimated Cost:- 60,300/-	
					Earnest Money:- 1,300/-	
					Time :- Two Month	
S.No	Description of Item	Quantity	Unit	Rate		Amount
				In words	In figure	
1	Hiring of excavator-cum-loader for removal of land slide, slip clearance including cutting and trimming of slopes and disposal of cut materials of all kinds of soil with minimum capacity 18 to 25.00 cum/ per hour & minimum 6 hours per day including services of operating staff as required including full time chowkidar for guarding the machine, POL charges & maintenance. Any loss or damage causes to machinery during transit or at site of work shall be borne by the contractor at his own cost. Any type of damage to private and Govt. property is the whole responsibility of the contractor. No breakdown will be included in hire charges due to any kind of hinderance. The work shall be executed as per the HP.PWD specifications within all leads, lifts and carriage of materials as per the entire satisfaction & direction of the Engineer-in-charge.	67.00	Hrs			
	Total:-					


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah - 173023

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Haripurdhar Korag Bedol Road Km. 0/00 to 11/500 (SH:- C/O B/wall in PCC at RD. 5/925 to 5/947)				Estimated Cost:- 2,04,145/-		
				Earnest Money:- 4,100/-		
				Time :- Two Month		
Sr. No	Description of item	Net Quantity	Unit	Rate		Amount
				In Figure	In Words	
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	10.00	Cum			
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the usefull materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transpsortation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechneries materials, tools, equipments and incidental necessary to complete the work by mechanized means and labour(if any required).All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	10.56	Cum			

3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1.4 8 40mm (Forty millimetre) nominal size) and curing complete including cost of form work and hauling/ carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer- in-Charge .	53.02	Cum	Per Cum			
4	Providing weep holes in brick masonry/stone masonry plain cement concrete , wing wall, return wall with 100 mm (One hundred millimetre) dia P V C. pipe extended through the full width of the structure with slop of one in vertical and Twenty in horizontal towards drawing face complete as per drawing and technical specification of Ministry of rural Development for rural roads August 2004 (Two thousand four) clause 614.709, 1204.3.7 (Six hundred fourteen, Seven hundred nine, One thousand two hundred four point three point seven) and curbing complete including the cost of form work and hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	20	Nos	Each			
Total:-							


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah - 173023

6

Schedule of quantity

Name of work:- Restoration of Rain Damages on various road under Nohradhar Sub-Division. (SH:- Removal of slips)

ESTIMATED COST :- Rs. 2,50,000/- Only
EARNEST MONEY :- Rs. 5000/- Only
TIME :- Two month.

S No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Removal of slips and land slide in all kinds of soil (including saturated soil , boulder and rocky portion requiring blasting) by mechanical means including cutting and trimming of side slopes and disposal of unserviceable cut materials in all leads and lifts, as per technical specification clause 302.3.5 and 1611 including all leads, lifts and carriage of materials as per the entire satisfaction of the Engineer-in Charge.	3571.43	m3	per Cubic Metre		
Total:-						


Executive Engineer
Sangrah Division,
HP.PWD., Sangrah.

6

Schedule of Quantity					Estimate cost:-2,39,884/-		
Name of Work:- C/O PHC Building at Jarag Distt. Sirmour (H.P) (SH:Flooring, Gate, Railing, Painting & Distemping etc)					Earnest Money:-4,800/-		
					Time period:- one Month		
Sr/No	Sub Head and item of work	Qty	Unit	Amount	Rate in		
					Figure	Words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.	2.25	cum	Per cubic metre			0
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	0.435	cum	Per cubic metre			0
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand) including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	16.45	cum	Per cubic metre			0
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size)	0.92	cum	Per cubic metre			0
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	322.56	kg	per Kilogramme			0
6	15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand) including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	140.24	sqm	Per square metre			0

7	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	30.57	Sqm	Per square metre		0
8	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	30.57	Sqm	Per square metre		0
9	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	140.20	Sqm	Per square metre		0
10	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	188.00	sqm	Per Square metre		0
Total:-						0


 Executive Engineer
 H.P. P.W.D. Division
 Sangrah 173023