



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23-
To

-10548-57

Dated:- *16-08*
2022

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in


Phone No:- 01972-288041
Fax No. 01972-288041.

NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **30.08.2022 up to 10.30 A.M.** and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **27.08-2022 upto 4.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **29.08.2022** during office hours till **4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	A/R & M/O 47.20 Mtr. Span Bridge Over Baliah Khad at RD. 3/900, 63.00 Mtr. Span Bridge Over Garli Khad at RD. 7/200 on Mehre Garli Road up to Bijhari & 31.80 Mtr. Span Bridge Over Garli Khad at RD. 0/190 i/c Approaches on Kheri Mangnoti Road. (SH:- P/L 25mm Thick Mastic Asphalt Wearing Course at Various Bridges).	Rs. 4,70,278.00 Only	Rs. 9,500.00 Only	One Month
2	A/R & M/O 34.0 Mtr. Span Bridge Over Baliah Khad at RD. 2/550 on Ghumarwin to G.P.S. Bara Baliah, 46.30 Mtr. Span Bridge Over Khawja Khad at RD. 0/800 on Bani Garli Road, 60.00 Mtr. Span Bridge Over Sirhali Khad at RD. 1/030 i/c Approaches on Malehra Rapper Nain Road. (SH:- P/L 25mm Thick Mastic Asphalt Wearing Course at Various Bridges).	Rs. 4,67,293.00 Only	Rs. 9,400.00	One Month
3	A/R & M/O on Various Road Barsar Sub Division (Section Barsar-II). (SH:- Bush Cutting at Various Road at Various RDs).	Rs. 2,00,400.00 Only	Rs. 4,100.00 Only	One Month
4.	C/O Link Road to Village Kharal. (SH:- P/L Cement Concrete Pavement at RD. 0/290 to 0/372) (D.C Deposit).	Rs. 4,90,302.00 Only	Rs. 9,900 Only	One Month

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
Barsar Division
HPPWD Barsar.


On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-105/2022-23-

10548-57 dated 16/8/2022


Executive Engineer
Barsar Division
HPPWD Barsar.

DNIT

Job No:- 1

Estimated Cost Rs:-4,70,278.00

Earnest Money Rs:-9500.00

Time Limit :- One Month

Name of work:- A/R&M/O 47.20 mtr span bridge over Baliah khad at Rd 3/900 , 63.00 mtr span bridge over Garli khad at Rd 7/200 on Mehre Garli road up to Bijhari & 31.80 mtr span bridge over Garli khad at Rd 0/190 including approaches on Kheri Mangnoti road.

(SH:- Providing and Laying 25 mm thick mastic asphalt wearing course)

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.85kg (Zero point eight five kilogram)per square metre using mechanical means as per technical Specification Clause 502 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	603.50	Square metre		Per square Metre	
2	Providing and laying 25mm (fifty millimetre thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500- 29 prepared by using mastic cooker and laid to required level and slope after cleaning the surface including providing antiskid surface with bitumen precoated fine grained hard stone chipping of 13.2 mm nominal size at the rate 0.005 cubic metre per 10% square metre and at an approximate apacing of 10 centimetre center to center in both direction s pressed into surface when the temperature of surfaces is not less than 1000.C protruding 1mm to 4mm over mastic surface alll complete as per Clause 515including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	603.50	Square metre		Per square Metre	
					Total	

(Signature)

Executive Engineer
Barsar Division
HPPWD Barsar

Job No:- 2

Estimated Cost Rs:-467293.00

Earnest Money Rs:-9400.00

Time Limit :- One Month

Schedule of quantity

Name of work:- A/R&M/O 34.80 mtr.span bridge over Baliah Khad at Rd 2/550 on Ghumarwin to G.P.S Bara Baliah , .

46.30 mtr span bridge over Khawaja khad at Rd 0/800 on Bani Garli road ,60.00 mtr span bridge over Sirhali

khad at Rd 1/030 i/c approaches on Malehra Rapper Nain road (SH:- Providing and Laying 25 mm thick mastic asphalt wearing course)

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words	Figure	words		
1	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.85kg (Zero point eight five kilogram)per square metre using mechanical means as per technical Specification Clause 502 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	599.67	Square metre			Per square Metre	
2	Providing and laying 25mm (fifty milimetre thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500- 29 prepared by using mastic cooker and laid to required level and slope after cleaning the surface including providing antiskid surface with bitumen precoated fine grained hard stone chiping of 13.2 mm nominal size at the rate 0.005 cubic metre per 10% square metre and at an approximate apacing of 10 centimetre center to center in both direction s pressed into surface when the temperature of surfaces is not less than 1000.C protruding 1mm to 4mm over mastic surface all complete as per Clause 515including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	599.67	Square metre			Per square Metre	
						Total	

(Signature)

Executive Engineer

Barsar Division

HPPWD Barsar

DNIT

Name of work:- A/R&M/O on various roads under HPPWD Sub Division Barsar (section Barsar-11)
(SH :- Bush cutting at Various roads at various RDs)

Job No:-3

Estimated Cost Rs:-200400.00

Earnest Money Rs:- 4100.00

Time Limit :- One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c		Unit	Amount
			Figure	G.S.T words		
1	Clearing and grubbing road land including uprooting wild vegetation grass, bushes, shrubs, saplings and trees of grith upto 300mm (three hundred millimetre) removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned , upto a lead of 1000 metre(one thousand metre) including removal and disposal of top organic soil not exceeding 150mm(one hundred millimetre) in thickness as per Technical Specification Clause 201 including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	24000.00	Square metre		Per Cubic Metre	
					Total:-	


Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- C/O link road to village Kharal.

Job No:- 4

Estimated Cost Rs:-490302.00

Earnest Money Rs:-9900.00


Time Limit :- One Month

(SH:- P/L cement concrete pavement at Rd 0/290 to 0/372) (D.C Deposit work)

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	32.80		Per Cubic Metre	
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading –I material including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	49.20		per cubic metre	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	32.80		Per Cubic Metre	

4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can persibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	32.80	Cubic metre				Per Cubic Metre	
								Total:-

71


 Executive Engineer
 Barsar Division
 HPPWD Barsar