



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**




Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22 **7088-94**
To

Dated **12-08-22**


The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.


Subject:-

Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division,
HP.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140

Fax No. 01904-255740


NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on **25.08.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on **24.08.2022** between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **24.08.2022** between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

1	A/R & M/O link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435 (SH:- P/L Paver Block at RD 1/390 to 1/418) and 1/300 to 1/308 under deposit of Telecom department).	299102.00	6000.00	Three months	350/-
2	A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (Sub Head:- C/O PCC retaining wall at RD 16/765 to 16/795) under deposit of telecom deptt.	333203.00	8000.00	Two months	350/-
3	A/R & M/O Arsu Deem Sheel road km. 0/00 to 8/150. (SH:- C/O wire crated R/Wall at RD. 6/150 to 6/170)	157541.00	4000.00	One month	350/-
4	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00. (SH:- C/O P.C.C. B/Walls at RD. 25/008 to 25/028)	297470.00	6000.00	Two months	350/-
5	A/R & M/O Rest House Building at Baga Sarhan Distt Kullu H P (SH-- Panting , Distempering, Tile work and Man Gate etc)	258741.00	6000.00	Three months	350/-

6	M/T works on link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435 under MNP (SH:- P/L WBM G-I for surface correction between km. 2/720 to 3/00)	445332.00	10000.00	Three months	350/-
7	M/T works on link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435 under MNP (SH:- P/L WBM G-I for surface correction between km. 3/00 to 4/200	492124.00	10000.00	Three months	350/-
8	R/R Damage on various roads under Brow Sub-Division deposit work (SH:- Hiring of JCB for removal of slips, dressing of road surface and construction of road side kutchra drain in various roads under Brow Sub-Division) for monsoon season 2022.	345000.00	8000.00	Two months	350/-

It is certified that the above tenders i.e Sr. No 1 to 8 are very urgent nature, So may be uploaded on department website in public interest


 Executive Engineer
 Outer Seraj Division
 H.P. PWD, Nirmand
 on behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435. (SH:- P/L Paver Block at RD 1/390 to 1/418) and 1/300 to 1/308 under deposit of Telecom department)

Estimated Cost:- 299102.00

Earnest money:- 6000.00

Time:- Three months

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	21.23	Per Cubic Meter			
2	Providing and laying 80mm (eighty millimetre) factory made chamfered edge Cement Concrete paver blocks of NTC or equivalent in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge and including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	132.35	Per Square Meter			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 Nominal mix (1:2:4) (one cement : two sand: four graded stone aggregates twenty millimetre nominal size) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.26	Per Cubic Meter			
Total:-						

Executive Engineer,
Outer Section Division,
HP.PWD, Nirmand.

2

Schedule of quantity


Name of Work: A/R & M/O Wazir Bowali Nimmand Arsu Sarahan road km. 0/00 to 34/00 (Sub Head:- C/O PCC retaining wall at RD 16/765 to 16/795) under deposit of telecom deptt.									
Sl. No.	Description of work	Qty.	Unit	Estimated cost:-			AMOUNT		
				Figures	RATE				
					Words	Time			
					Earnest Money	8000			
						Two months			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.00	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.15	Cubic Metre						
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	64.50	Cubic Metre						
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	30.00	Each						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	8.00	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Saraj Division
 HPPMD, PZ
 PZ

(3)

Schedule of quantity

Name of Work: A/R & M/O Arsu Deem Sheel road km. 0/0/0 to 8/150. (SH:- C/O wire crated R/Wall at RD. 6/150 to 6/170)						
				Estimated cost:-		157541.00
				Earnest Money		4000
				Time		One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.60	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	14.40	Cubic Metre			
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Wire crate will be supplied by the department free of cost)	86.40	Cubic Metre			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	13.50	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Sarai District
 H.P. & M.D.

Schedule of quantity

Name of Work:- A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00. (SH:- C/O P.C.C. B/Walls at RD. 25/008 to 25/028)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Earnest Money		279470.0
				Time	Two month	6000
Figures	RATE	Words	AMOUN			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	46	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	27.20	Cubic Metre			
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	62.60	Cubic Metre			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each			
Total in Figures						


 Executive Engineer
 Outer Serai Division
 H.P.P.W.D., Muzaffargarh

5

Schedule of quantity

Name of Work:-A.R & M.O Rest House Building at Baga Sarhan Dist Kullu (H P) (SH-- Painting , Distempering, Tile work and Man Gate etc)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Figures	RATE	
					Words	AMOUNT
					Time	Three
					Earnest Money	6000
1	Painting with oil type wood preservative of approved brand and manufacture inclusive of carriage of materials in all leads and lifts and as per directions of The Engineer-in-Charge complete.	279.200	Per Square Metre			
2	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	277.800	Per Square Metre			
3	Distempering with 1st quality acrylic distemper (ready made) having VOC content less than 50 gm per lit. Of approved manufacturer and of required shade and colour complete. as per r'er's ecification 13.108.1 One or more coats on old work including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	458.000	Per Square Metre			
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under. including cutting the patch in proper shape. raking out joints and preparing and plastering the surface of the lls complete. including disposal of rubbish to the dumping ground. all pleie as per direction of gineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand) including curing and carriage of materials in all leads and lifts all levels and heights and as per directions of The Engineer-in-Charge	20.100	Per Square Metre			
5	Providing and fixing panelled or panelled and glazed shutters for doors, windows and dows fixing with butt hinges of required size with necessary screws, excluding paneling which will be paid for separately. all complete as per direction of Engineer-in-charge. Kiln seasoned and chemically treated hollock wood 30 mm thick including carriage of materials in all leads and lifts all levels and heights and as per directions of The Engineer-in-Charge complete.	73.200	Per Square Metre			
6	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete : 9.40.1 2nd class teak wood 50x12 mm including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete in:-	37.200	Per Metre			
7	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of ement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, udling pointing in white cement mixed with pigment of matching shade including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge	33.760	Per Square Metre			

Signature of Tondaror with seal

21/01/2021

8	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing 13.33.1 Flush/ Ruled pointing including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	63.340	Per Square Metre			
9	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches ordains including dressing of sides and ramming of bottoms, lift upto all heights, including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	1.620	Cubic Metre			
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement : five fine sand : ten graded stone aggregate 40 mm nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	0.162	Per Cubic Metre			
11	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm nominal size) upto plinth level including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	0.770	Per Cubic Metre			
12	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and up to floor five level Masonry work (second sort), in cement mortar 1:6 (one cement: six coarse sand) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	0.600	Per Cubic Metre			
13	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	0.090	Per Cubic Metre			
14	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	178.000	Per Kilo-gramme			
	Total:-					

Executive Engineer,
Outer Section Division,
HP PWD, Jirmand.

Signature of Tenderer with seal

SCHEDULE OF QUANTITY						
NAME OF WORK:- M/T works on link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435. under MNP (SH:- P/L Metalling and tarring in km. 00000 to 12000 2/720 to 3/w)					Estimated Cost:-445332.00	
					Earnest money:- 10000.00	
					Time:- Three months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 By Mechanical Means including carriage of materials through all modes of transportation with in all leads and lifts as per directions of the Engineer-In-Charge.	165.60	Per Cubic Metre			

to 4/435. under MNP (SH:- P/L Metalling and tarring in km. ~~00835510-43000~~ 2/720 to 3/12)

Earnest money:- 10000.00

Amount

Per Cubic
Metre

165.60

Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 By Mechanical Means including carriage of materials through all modes of transportation with in all leads and lifts as per directions of the Engineer-In-Charge.

HP.PWD. Nirman. 4


SCHEDULE OF QUANTITY

NAME OF WORK:- M/T works on link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435. under MNP (SH:- P/L Metalling and tarring in km. 3/00 to 4/200)

Estimated Cost:-429124.00
Earnest money:- 10000.00

Time:- Three months

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 By Mechanical Means including carriage of materials through all modes of transportaion with in all leads and lifts as per directions of the Engineer-In-Charge.	183.00	Per Cubic Metre			


 Executive Engineer,
 Outer Seraj Division,
 HP.PWD, Nirmand

DRAFT SCHEDULE OF QUANTITY

Name of work :-R/O & M/O various roads under B-Sub-Division (SH:- Hiring of JCB for removal of slips, dressing of road surface and construction of road side kutchha drain in various roads under B-Sub-Division) for monsoon season 2022.

Estimated Cost Rs. 345000.00
Earnest Money Rs. 7000.00
Time :- Three months.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. The scroll hour of the machine up to site of work will fully be born by the contractor.	300.00	1150.00	Rupees one thousand one hundred fifty only.	Per Hour	345,000.00
Total						345,000.00

Draft Schedule of quantity approved for Rs. 345,000.00

Executive Engineer,
Outer Serai Division,
HP. PWD. Mandi.