

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2022-23- 6722-23

Dated:- 04/08/2022

To

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 12.08.2022.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Scaled items rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 12.08.2022 up to 12.30 PM and shall be opened on 12.08.2022 the same day at 12:45 P.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 11.08.2022 for which the applications should reach in this office up to 4.00 PM on 10.03.2022. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.1/490 to 1/685).Under MNP.	Rs. 448600/-	Rs. 10000/-	One Month.	350/-	C & D
2	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.1/685 to 1/805).Under MNP.	Rs. 482700/-	Rs. 10000/-	One Month.	350/-	C & D
3	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.1/805 to 2/210).Under MNP.	Rs. 489000/-	Rs. 10000/-	One Month.	350/-	C & D
4	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.2/210 to 2/445).Under MNP.	Rs. 480200/-	Rs. 10000/-	One Month.	350/-	C & D
5	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from	Rs. 489100/-	Rs. 10000/-	One Month.	350/-	C & D


	km.2/445 to 2/615).Under MNP.					
-6	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.2/615 to 2/975).Under MNP.	Rs. 495200/-	Rs. 10000/-	One Month.	350/-	C & D

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number and GST clearance certificate from GST depart.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number.
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis.
10. Only two tender form will be issued to one contractor.


Executive Engineer,
Paonta B&R Division,
HP.PWD., Paonta Sahib.

Dated:- 04/08/2022

No.PWP/CB-Tender Notice/2022-23- 6724-6773
Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
11. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP.PWD., Paonta Sahib.

Job No-1

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwar Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 1/490 to 1/685).

Estimated Cost: 448590/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 143.23 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	2,864.60 Cum	Per cubic metre			
					Total:	


Executive Engineer,
Paonta (B&R) Division,
H.P.PWD, Paonta Sahib.

Jeb No- 2

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 1/685 to 1/805).

Estimated Cost: 48,300/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 154.11 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,082.20 Cum	Per cubic metre			
					Total:	

Executive Engineer,
Paonta (B&R) Division,
HP-PWD, Paonta Sahib.


Job No-3

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 1/805 to 2/210).

Estimated Cost: 489089/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 156.15 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,123.15 Cum	Per cubic metre			
					Total:	


Executive Engineer,
Paonta (B&R) Division,
H.P.PWD, Paonta Sahib.

Job No-4

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 2/210 to 2/445).

Estimated Cost: 480160/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 153.31 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,066.20 Cum	Per cubic metre		One Hundred Fifty six and sixty paise only	
					Total:	

Executive Engineer,
Paonta (B&R) Division,
H.P. PWD, Paonta Sahib.

Job No- 5

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 2/445 to 2/615).

Estimated Cost: 48910/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 156.16 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,123.25 Cum	Per cubic metre			
					Total:	


Executive Engineer,
Paonta (B&R) Division,
YHP-PWD, Paonta Sahib.

Job No-6

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 2/615 to 2/975).

Estimated Cost: 495200/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 158.11 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,162.20 Cum	Per cubic meter			
					Total:	

Executive Engineer
Paonta (B&R) Division,
HP.PWD, Paonta Sahib.