



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

Office 01783-260033

Email : ee-cho-hp@nic.in

No. PW.CHD.CB.E-9/2022- 9011-9060

Dated : 27/09/2022

NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender : 11.10.2022 11:00 AM to 04:00 PM form
2. Date and time of issue of tender form : 11.10.2022 11:00 AM to 04:00 PM
3. Date and time of receipt of tenders : 12.10.2022 11:30 AM
4. Date and time of opening of tender : 12.10.2022 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for the purpose.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contract
1.	Name of work :- Improvement of black spot on Sainj Chopal Nerwa Feduj road km. 20/0 to 90/0 (SH: C/o Edge wall and parapets in between km. R.D. 32/0 to 32/500).	497634/-	10000/-	350/-	Two months.	Class D or above
2.	Name of work :- A/R & M/O road from Pujarli to Janog via Ranghol km. 0/0 to 3/0 (SH: C/o Wire crated wall in between different R.D. 1/915 to 1/945).	203234/-	5000/-	350/-	Two months.	Class D or above
3.	Name of work :- A/R & M/O Manu to Irra road km. 0/0 to 8/200 (SH: C/o PCC B/wall in between km. R.D. 1/830 to 1/855).	218974/-	4500/-	350/-	Two months.	Class D or above
4.	Name of work :- A/R & M/O BMT road km. 0/0 to 18/0 (SH: C/o wire crated R/wall in between km. R.D. 15/418 to 15/433 and 15/508 to 15/528).	463974/-	10000/-	350/-	Two months.	Class D or above

TERMS AND CONDITIONS :-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of form.

2. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application;
 - b. GST Number issued by the Sale Tax Department;
 - c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
3. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s);
4. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor;
5. The work will be completed by the contractor within the stipulated period;
6. The contractor/firms are required to insert the rate of each item in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any overall tender;
7. The tender shall be issued to only those contractor/firms who are eligible suitable and competent;
8. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience which shall be duly evaluated by the technical evaluation committee.
9. The contractor/firm having necessary documents and past adequate experience shall be preferred;
10. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms;
11. A contractor enlisted in a particular class be eligible to tender for his own class and one step below;
12. Only two number tender forms will issued to the eligible contractor;
13. If any kind of holiday to be happened, the tender shall be opened on the next working day at 11:30 a.m.
14. GST will be deducted as per rates fixed by the Government.

CERTIFICATE


It is to certify that tender for the above works are urgently required please.

Executive Engineer
Chopal Div.HPPWD Chopal
On behalf of Governor of
H.P.

Copy forwarded for information to the :-

1. Chief Engineer (Shimla Zone) HPPWD Shimla.
2. Superintending Engineer, 04th Circle, HPPWD Shimla.
3. Deputy Commissioner, Shimla.
4. SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. Tehsildar Chopal Tehsil Chopal District Shimla H.P.
6. BDO Chopal Tehsil Chopal District Shimla H.P.
7. All the Assistant Engineers working under this division.
8. All the intending contractors in HPPWD.
9. Notice Board.

Executive Engineer
Chopal Div.HPPWD Chopal
On behalf of Governor of
H.P.



No. PW.CHD.CB.E-9/2022- 9061-63

Dated : 27/09/2022

To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla, H.P.

Subject :- Publication of Tender Notice.

Sir,


Enclosed please find herewith the tender notice of work(s) as given in the Notice Inviting Tender for uploading on departmental website as per notification vide Pr. Secy. (PW) to the Government of Himachal Pradesh letter No. PBW(B)1/2020 dated 27th May, 2021 and PBW(B)A(3)1/2020 dated 16th July, 2021 as the work(s) mentioned in the tender notice is(are) urgent in nature and in public interest.

Executive Engineer,
Chopal Division,
HPPWD Chopal.

Copy forwarded for further necessary action to the :-



1. The Superintending Engineer, 04th Circle, HPPWD Shimla;
2. Computer Cell O/o the Executive Engineer, (IT Cell) Nigam Vihar Shimla-2.

Executive Engineer,
Chopal Division,
HPPWD Chopal.



CERTIFICATE

Certified that the tender(s) of work(s) as called vide this
office NIT No. PW.CHD.CB.C-9/2022- 9011-9060 dated
27/09/2022 are of urgent nature work(s).


Executive Engineer
Chopal Div. HPPWD Chopal
On behalf of Governor of H.P. 

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost
Earnest Money
Time Allowed

Rs. 497634/-
Rs. 10000/-
Two months

Name of work : Improvement of black spot on Sainj Chopal Nerwa Feduj road km. 20/0 to 90/0 (SH: C/o Edge wall and parapets in between km. R.D. 32/0 to 32/500)

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
1	Earth work in exavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring bracing and removal of slumps and other deleterious material and disposal up to 50m lead dressing of side slope and bottom back filling in trenches with excavated suitable material and including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	72.84			Per cubic metre.	
2	P/I concrete to plain reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm nominal size) mixing by mechanical concrete mixture 0.40/0.28 cubic metre and vibrated mechanically so as to give a compressive strength and curing complete including the cost of form work as per drawing and technical specification clause 802, 803,1202, 1203.including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	73.13			Per cubic metre.	
3	P/I concrete to plain reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 25mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803,1202, 1203 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	41.65			Per cubic metre.	
TOTAL						

Executive Engineer
Chowki Division (B & D)
H.P.P.W.D. Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost
Earnest Money
Time Allowed

Rs. 203234/-
Rs. 5000/-
Two Months

Name of work : A/R & M/O road from Pujarili to Janog via Ranghol km. 0/0 to 3/0 (SH: C/o Wire crated wall in between different R.D. 1/915 to 1/945).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in earth work and disposal of all excavated earth up to a lead of 20 metre lift up to 1.50 metre disposed earth to be levelled and neatly dressed pick and jumper work within all leads and lifts including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts (a) pick and jumper work.	47.10			Per cubic metre.	
2	Providing and laying of boulder apron laid in wire crate with 4mm dia conforming to IS 280 and 48.26 mesh design including joints laid in boulder weighing not less than 25 kg each as per drawing and dtechnical specification clause 1301 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	93.750			Per cubic metre.	
TOTAL						

Erector Engineer
Shri. P. W. D. Chopal
B.P.P.W.D. Chopal

8

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost
Earnest Money
Time Allowed

Rs. 218974/-
Rs. 4500/-
Two Months

Name of work : A/R & M/O Manu to Irra road km. 0/0 to 8/200 (SH: C/o PCC B/wall in between km. R.D. 1/830 to 1/855).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom backfilling in trenches with excavated suitable material ordinary soil upto 3.00 m depth including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	34.15			Per cubic metre.	
2	P/L concrete to plain reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 25mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803,1202, 1203 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	48.18			Per cubic metre.	
3	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	4.50			Per cubic metre.	
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment, wing wall, return wall 100mm dia PVC pipe extending through out the full width of the structure with slopes of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.4 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	20.00			Per running metre	

Engineer
Division (B & R)
H P P W D, Choppa

DRAFT/SCHEDULED OF QUANTITY.

4

Estimated Cost
Earnest Money
Time Allowed

Rs. 463974/-
Rs. 100000/-
One month

Name of work : A/R & M/O BMT road km. 0/0 to 18/0 (SH: C/o wire crated R/wall in between km. R.D. 15/418 to 15/433 and 15/508 to 15/528).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
1	Earth work in exavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring bracing and removal of stumps and other deleterious material and disposal up to 50m lead dressing of side slope and bottom back filling in trenches with excavated suitable material and including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	59.15			Per cubic metre.	
2	Providing and laying of boulder apron laid in wire crate with 4mm dia conforming to IS 280 and 48.26 mesh design including joints laid in boulder weighing not less than 25 kg each as per drawing and dtechnical specification clause 1301 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	218.750			Per cubic metre.	
3	Stone filling behind wall including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	16.60			Per cubic metre.	
TOTAL						

Executive Engineer
City Division (B & R)
H P W D Charge