

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item rates tender are hereby invited by the Executive Engineer, Ghumarwin Division, HP-PWD. Ghumarwin for the following works from the registered contractors of appropriate class enlisted in HP-PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act. 1968. The important date of tender are as under:-

Date of application
Date of sale of tender.

24/09/2022
25/09/2022

The tender shall be received up to 11:00A.M. on 26/09/2022 and will be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 25/09/2022.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Ghumarwin Division, HP-PWD, Ghumarwin must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Period	Tender Cost
1	C/o PHC building at Hatwar (SH:- C/o D/S for siltin arrangement of worth CM programme for inauguration ceremony of this building).	117108/-	2500/-	Two month	350/-
2	C/o link road from Muhana to Lanjhata km 0/0 to 1/200 (SH:- C/o super structure for 3.00 mtr R.C.C slab culvert at R.D 0/507).	495068/-	10000/-	Two month	350/-
3	Repair & Restoration of approach and drain of Him Fed Godam Ghumarwin at Patta Distt. Bilaspur HP (SH:- P/L laying 80mm thick paver block in court yard and development of its is procurement center Ghumarwin at Patta and painting etc).	491299/-	9900/-	One month	350/-
4	C/o 15 mtr span steel truss over head Foot Bridge near hospital Ghumarwin Distt. Bilaspur (HP) (SH:- P/L GSB C.C work PGI sheet roofing priming coat etc.)	421356/-	8500/-	Two month	350/-
5	C/o link road Dangar to Dakhuit Nichla road km 0/0 to 2/0 (SH:- C/o B/wall at R.D 1/910 to 1/917.40, 1/918 to 1/925.40).	177451/-	3600/-	Two month	350/-
6	C/o Bum Dipper Hatwar road km 0/0 to 3/0 (SH:- C/o wire crate at R.D 2/200 to 2/230)	452587/-	9100/-	Two month	350/-
7	C/o PHC Panol (Amarpur) (SH:- C/o Main Gate and railing work etc)etc	384555/-	8000/-	Two month	350/-
8	C/o Rain Shelter at Bhadrog on Patta Mosringhi road at Jol on Rohal Khad Ghandiwan Lehri Serial road and at Patta Ranotan on Bum Jahu road.	448836/-	9000/-	Two month	350/-
9	C/o Parking in Ward No.2 Near Rehan Basera at Ghumarwin Distt. Bilaspur (HP) (SH:- P/L 40x40x12mm thick exterior grade vitrified floor tile in terrace).	498575/-	10000/-	Two month	350/-
10	C/o L/R H/Basti Barota School to house of Purshotam Dutt km 0/0 to 1/0 (SH:- C/o R/wall at R.D 0/105 to 0/118 and 0/320 to 0/330)	461233/-	9300/-	Two month	350/-
11	A/R & M/O various road under GSD (SH:- P/F of high intensity engineering prismatic sheeting on crash barrier at various roads) reflective tape	99000/-	3900/-	One month	350/-
12	C/o office Accommodation DA, ADA & PP at Ghumarwin Distt. Bilaspur HP (SH:- P/Fixing GRC Jail 35mm thick & GRC wall cladding size 10.5'5 of stone series shade Gray/cream etc.	499360/-	9980/-	One month	350/-
13	C/o L/R from water supply Tank Dakri to H/Basti Chuwari via H.B Dakri Bahli (SH:-C/o V-shape drain in km 0/050 to 0/230 & U-shape at R.D 0/230 to 0/400).	440647/-	8900/-	Two month	350/-
14	C/o Ghumarwin Dabla Morisngi road km 0/0 to 8/0 (SH:- C/o U-shape drain at R.D 0/030 to 0/813 and wing wall for hume pipe at R.D 4/195 and 3/210(D/S).	498593/-	10000/-	one month	350/-
15	RRD on link road Rewal Tal to Chappri (SH:- P/L 80mm thick paver block km 0/0 to 0/48).	207579/-	4200/-	One month	350/-
16	C/o link road to Nalti to Dugli gram Panchyat Fatoh (SH:- F/c in km 0/0 to 1/540).	366955/-	7400/-	Two month	350/-
17	C/o link road to village Trountra Ghumarwin km 0/0 to 0/600 (SH:- C/o C.C pavement at R.D 0/335 to 0/390 and edge wall at R.D.0/435 to 0/452).	356833/-	7200/-	Two month	350/-
18	RRD on Harlog Mehran Tiun Khas road km 0/0 to 5/500 (SH:- C/o R/wall at R.D 1/631 to 1/643).	228714/-	4600/-	Two month	350/-
19	Repair and maintenance on Vijaypur Amarpur Dahad Jaman Ghumarwin road km 0/0 to 7/500 (SH:- P/L GSB G-III and tarring work at R.D 7/380 to 7/500).	168217/-	3500/-	Two month	350/-
20	A/R & M/O HP.PWD Rest house at Bharari Tehsil Ghumarwin Distt. Bilaspur (HP) (SH:- White washing Distempering and painting etc).	130418/-	2700/-	Two month	350/-
21	R/R Damage on Bhager Fatoh road km 0/0 to 2/0 (SH:- C/o R/wall at R.D 0/656 to 0/668.80)	499756/-	9996/-	One month	350/-
22	C/o additional accommodation of commerce block at G.D Collage at Ghumarwin (SH:- Balance work of toilet block porch & painting etc).	269654/-	5400/-	One month	350/-
23	C/o link road Kallar Plasla km 0/0 to 2/500 (SH:- C/o solid cause way at R.D 0/065 to 0/435 and RCC H/pipe culvert at R.D 0/720 along with wing walls both side).	467570/-	9400/-	Two month	350/-
24	C/o Mohra Sunali Gallian Sukker Khad road km 0/0 to 6/150 in Distt. Bilaspur HP	279825/-	5600/-	One month	350/-
25	Repair of Veer Sohan Singh Marg in Village Ballu Kharyala G.P. Bakroa (SH:- P/L cement concrete pavement in km 0/110 to 0/146.60)	149861/-	3000/-	Two month	350/-

26	A/R & M/o Bum Dipper Hatwar road km 0/0 to 3/0 (SH:-C/o Granular Filling at R.D 0/200 to 0/360).	348304/-	7000/-	Two month	350/-
27	R/R on Sumari to Lower Bhapral road km 0/0 to 6/0 (SH:- P/L Interlocking tiles at R.D 4/160 to 4/230).	334096/-	6700/-	Two month	350/-
28	C/o From Ghumarwin Dabra Mersinghi road to Vill. Baddu (SH:- C/o B/wall at R.D. 0/331 to 0/348)(OTMNP)	178992/-	3600/-	Two month	350/-
29	C/o link road Chokhna to Vill. Dakhuit upto house of Freedom fighter Late Sh. Ram Singh G.P Dangar Distt. Bilaspur (HP) (SH:- P/L c.C pavement at essential reaches in km 0/0 to 0/500)	240532/-	4900/-	Two month	350/-
30	Amp for the year 2022-23 for rural road (village road) (SH:- P/L 30mm thick bituminous concrete on link road Badhaghat to Kotla km 4/400 to 4/800).	499026/-	10000/-	Two month	350/-
31	C/o link road from Rideo Gadod Badrog Bhapral road km 0/0 to 3/0 (SH:- P/L soling wearing tarring at R.D 2/685 to 2/820).	410840/-	8300/-	One month	350/-
32	C/o link road Samlohal to Chadol via Pikkle Factory km 0/0 to 2/660(SH:- balance work of RCC Slab culvert 3.00mtr span at R.D 2/621) under SCSP	274061/-	5500/-	Two month	350/-
33	C/o link road Mihare to Dalote Kwadra Lohat km 0/0 to 5/0 (SH:-C/o R/wall at R.D 2/175 to 2/195 & 2/165 to 2/1750).	462902/-	9300/-	Two month	350/-
34	R/R damages on link road Silh to Nain Km 0/0 to 3/285 (SH:-C/o R/wall at RD 2/768 to 2/780)	379698/-	7600/-	Two month	350/-
35	C/o link road from H/Basti Bum to Glah Galahi Hatwar Hambot (SH:- P/L C.C pavement at R.D 0/0 to 0/028).	499692/-	10000/-	Two month	350/-

- The XEN reserve the right to accept or reject the tenders without assigning any reason.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
- The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should be accompanied with application.
- Earnest money should be accompanied with application. Application without earnest money will not be entertained.

CERTIFICATE
Certified that the tenders have been invited in exigencies/ emergency of work.

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

No.PW/GHD/CB/Tender/2022-

15147-53

Dated:- 14/09/2022

Copy along with Notice Inviting Tender list is forwarded to:-

1. The Engineer-in-Chief HPPWD Shimla-2
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineer, 10th Circle, HPPWD Bilaspur
4. The Executive Engineer (IT) O/O Engineer-in-Chief/HPPWD Shimla-2 eeict-pwd-shi[at]hp[dot]gov.in a/w schedule of quantity to download on the department portal.
5. Drawing Branch
6. Account Branch

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Estimated Cost:- Rs. 1,17,108.00

Earnest Money:- Rs. 2,500.00

Time:- Two Month

Schedule of Quantity

Name of Work:-

C/O P.H.C Building at Hatwar (SH - C/O Bus for siting arrangement of working CMA Programme for inauguration Ceremony of this building ~~and other~~

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. ordinary rock. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.52	Per cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40 mm (forty millimetre nominal size) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.52	Per cubic metre			
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : in cement mortar 1:6 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.01	Per cubic metre			
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.88	Per cubic metre			
5	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification clause 1204.3.8 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.78	Per cubic metre			
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.91	Per cubic metre			
Total:-						

Executive Engineer
Ghumarwin Division
H.P.P.W.D. Ghumarwin

Schedule of Quantity

Schedule of Quantity

Estimated Cost:- Rs. 4,95,068.00

Earnest Money:- Rs. 10,000.00

Time:- Two Month

Estimated Cost:- Rs. 4,95,068.00

Earnest Money:- Rs. 10,000.00

Time:- Two Month

2

C/O link road from Muhana to Lanjhita km 0/00 to 1/200 (SH:- C/O super structure for 3.00 mtr R.C.C slab culvert at RD 0/507)

Sr.No.	Description Item	Unit	Rates		Quantity	Unit	Rates		Amount
			In figure	In words			In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.37	Per cubic metre						
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40 mm (forty millimetre nominal size) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.45	Per cubic metre						
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement : three coarse sand) : six graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.39	Per cubic metre						
4	Reinforced cement concrete: 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	8.52	Per cubic metre						
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1124.60	Per kg						

Concrete wear of 6:1 Technical specification of Goods and Service Tax, or other tax, levy or cess in re- spect of the same.	Providing and Laying cement concrete wearing course M-30 grade including reinforcement complete as per drawing and technical specification clauses 800 and 1206.3 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.71	Per cubic metre				
Rate of M-25 grade in cast in situ with 20mm nominal size aggregate true to line and grade tolerance of vertical railing post not to exceed 1 in 500 centre to centre spacing between vertical posts not to exceed 2000 mm as per drawing and technical specification clauses 800, 900, 1208.3. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Construction of R.C.C railing of M-25 grade in cast in situ with 20mm nominal size aggregate true to line and grade tolerance of vertical railing post not to exceed 1 in 500 centre to centre spacing between vertical posts not to exceed 2000 mm as per drawing and technical specification clauses 800, 900, 1208.3. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Per Rmt				
Drainage spouts complete as per drawing and technical specification clause 1209 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Drainage spouts complete as per drawing and technical specification clause 1209 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	each				
Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls; return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls; return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	231.00	Per Square metre				
Total:-	Total:-						

Executive Engineer
Ghumaria Division
H.P.W.D. Ghumaria

Schedule of Quantity

Estimated Cost:- Rs. 4,91,299.00

Earnest Money:- Rs. 9,900.00


Time :- One Month

3

Name of Work:- Repair & Restoration of approach and drain of Him Fed Godam Ghumarwin at Patta distt. Bilaspur HP. (SH:- P/L Laying 80mm thick paver block in court yard and development of it is precurement center Ghumarwin at Patta) and painting etc.)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	233.81	Per square metre			
2	Providing and laying cement concrete 1:3:6 (one cement: three sand: six graded stone aggregate 40mm (forty millimetre) nominal size) excluding cost of centring and shuttering in Foundations and plinth as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.38	per Cubic metre			
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in - Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	221.24	per square mtr			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (one Cement: 1½ one and half coarse sand) : three graded stone aggregate 20 mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.22	Per cubic metre			
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	83.31	Per square metre			
6	Distempering with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	95.32	Per square metre			
7	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	95.32	Per square metre			

8	Finishing walls with water proofing cement paint of required shade - New work (Two or more coats applied @ 3.84 kg/10 sqm) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	68.93	Per square metre			
9	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	287.98	Per square metre			
Total:-						0.00


 Executive Engineer
 Ghumarwin Division
 H.P.W.D. Ghumarwin

4

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs 421356/- ONLY.

EARNEST MONEY:- Rs 8500/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:- C/O 15.00 mtr span steel truss over head Foot Bridge near Hospital Ghumarwin Distt. Bilaspur (HP) (SH:-providing and laying GSB, C.C. work, PGI sheet Roofing, priming coat etc.)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular subbase by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408.(i) Using naturally including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government. occuring gravel	58.21			Per cubic meter	
2	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-10 (1:3:6) (One cement: three sand: six graded crushed stone aggregate 40mm (Forty millimeter) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	13.12			Per cubic metre	
3	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 Grade-M25 (1:1.5:3) (One cement: one point five sand: three graded crushed stone aggregate 20mm (twenty millimeter) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	10.16			Per cubic metre	
4	Providing and laying curb stone of grade M-20 (1:1.5:3)(1 cement : 1.5: Sand : 3 graded stone aggregate 20 mm nominal size) and curing complete having size 300x300x15mm size including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	90.00			each	
5	Providing and fixing 0.60mm thick prepainted steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polister (RNP) organic coating of 20 microns over 5microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accesoriees as required as per the directed by the Engineer-in-charge .Providing and laying M-20 grade concrete with cement concrete work 1:2:4(O cement:Two nsand:Four graded stone aggregate 20mm(Twenty millimetre nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	151.72			Per Square Metre.	

6	Providing and fixing ridges or hips 60 cm (sixty centimetre) overall with 0.60mm(zero point six zero millimetre) thick preapainted steel sheets of TATA or its equivalent make in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns(twenty microns) over 5 microns (five microns) primer coating + back coat of polyester of 5 microns (five microns) over 5 microns (five microns) primer coating including fixing with preapainted iron J or L hooks, bolts & nuts 6mm(six millimetre) dia & preapainted G.I. limpet and bitumen washers complete with all accessories as required including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of Input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. As per HP,PWD specification 1990 vol-I clause 14.2.	101.60			Per running metre.	
7	Providing and fixing 0.47mm thick preapainted liner steel sheet in ceiling with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP)organic coating of 20 microns over 5microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with preapainted iron J or L hooks, bolts and nuts 6mm dia metre with preapainted limpet and rubber washers complete with all accessories as required as per the directed by the Engineer-in-charge. Providing and laying M-20 grade concrete with cement concrete work 1:2:4 (O cement:Two nsand:Four graded stone aggregate 20mm(Twenty millimetre nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete.	145.74			Per Square Metre	
8	Brick work using conventional 2nd class common burnt clay building brick in super structure above plinth level upto all floors level in cement mortar 1:6(1 cement::6 sand)/c curing complete. Including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1.27			Per Cubic Metre	
9	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose material and other foreign matter and papered smooth to give final matter finished to the surface complete including carriage of material within all leads and lifts as directed by the Engineer-in-charge.	341.19			Per Square Metre	
10	Applying one coat of Acrylic primer (Spectrum or equivalent of Superior quality) on new concrete/masonry/plastered surfaces after and including preparing the surface by thoroughly brushing the surface free from mortar droppings and other foreign matters, sand papering the surface smooth complete. including carriage of material within all leads and lifts as per directed by the Engineer-in-charge.	341.19			Per Square Metre.	
11	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarled on undecorated wall surfaces (two coats) to give an even shade and finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc. including sand paper smooth complete including carriage of material within all leads and lifts as per directed by the Engineer-in-charge.	341.19			Per Square Metre	
Total=						

Executive Engineer
Ghumaria Division
HPPWD Ghumaria

Schedule of Quantity

Estimated Cost:- Rs. 1,77,451.00


Earnest Money:- Rs. 3,600.00

Time :- Two Month

Name of Work:- C/O link road Dangar to Dakhuit Nichla road km 0/0 to 2/0 (SH:- C/O B/wall at RD 1/910 to 1/917.40, 1/918 to 1/925.40)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan) including getting out and disposal of excavated earth upto any lead and lift as directed by Engineer-in-charge. All kinds of soil as per Technical Specification Clause 301.5 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.1	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	11.98	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.76	Per cubic metre			
4	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.26	Per square metre			

5	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slop of 1(V) : 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Each			
	Total:-					


Executive Engineer
Shumanin Division
 HPPWD, GATEWAY

Schedule of Quantity

Estimated Cost:- Rs. 4,52,587.00
Earnest Money:- Rs. 9,100.00
Time :- Two Month

Name of Work: Construction of Bum dipper Hatwar road km 0/00 to 3/00 (SH:-C/O Wire crate at RD 2/200 to 2/230)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.9	Per cubic metre			
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (ten into twelve) (D=100 mm with tolerance of $\pm 2\%$) Zinc + PVC coated, Mesh wire diameter 2.7 / 3.7mm, mechanically edged / selvedged with partitions at every 1m (one metre) interval and shall have minimum 10 (ten) numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2/3.2mm(ID/OD), supplied @3% (three percentage) by weight of Gabion boxes, filled with boulders with least dimension of 200 mm (two hundred millimetre), as per drawing, all complete as per directions of Engineer-in-charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	129.60	Per cubic metre			
Total:-						

Executive Engineer
Ghumana Division
HPPMD Ghumana

Schedule of Quantity

⑦

Estimated Cost:- Rs. 3,84,555.00

Earnest Money:- Rs. 8,000.00

Time:- Two Month

Name of Work:- Construction of PHC Panol (Amarpur). (SI:- C/O Main Gate and railing work etc.)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Demolishing lime concrete manually/ by mechanical means and disposal of material within 50 metres lead as per direction of Engineer-in-charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.65	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.43	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to all level 1:4:8 (one Cement : four coarse sand : eight graded stone aggregate 40 mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.43	Per cubic metre			
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (one cement : One point five coarse sand) : three graded stone aggregate 20 (twenty) mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.97	Per cubic metre			
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2255.00	Per Kilogram			
6	Providing and fixing moulded hand rail of M.S. hollow pipe 50mm dia welded in straight length over M.S. flat at top of vertical balusters including one coat of red oxide priming coat complete (M.S. flat & balusters of railings shall be measured & paid separately. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.00	Per Rmt			
7	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.44	Per square metre			
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (one cement : six coarse sand) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.19	Per cubic metre			
9	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (one cement : four coarse sand) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.05	Per square metre			

10	Finishing walls with water proofing cement paint of required shade. New work (Two or more coats applied @ 3.84 kg/10 sqm) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.05	Per square metre			
11	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Per square metre			
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.50	Per Kilogram			
13	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.70	Per square metre			
14	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 300x16 mm (Three hundred into sixteen milimetre). The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Each			
Total:-						

Executive Engineer,
Ghumarwin Division,
H.P, P.W.D. Ghumarwin.

Schedule of Quantity

Estimated Cost:- Rs. 4,48,836.00

Earnest Money:- Rs. 9,000.00


Time :- Two Month

(8)

Name of Work:- C/o rain Shelter at Bhadrog on Patta morshingi road at Jole on Rohal Khad Ghandalwin lehri Sarial road and at Patta Ranotan on Bum Jandot road

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kind of Soil The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.25	Per cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for: Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.67	Per square metre			
3	P/L cement concrete - all works upto plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.12	Per cubic metre			
4	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204 3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each			
5	P/L cement concrete - all works upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.26	Per cubic metre			
6	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification clause 1204.3.8 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.20	Per cubic metre			
7	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1: 4 (1 cement : 4 coarse sand) : 25 mm thick. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.25	Per square metre			
8	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	843.30	per KG			
9	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 0.63 mm thick with zinc coating not less than 275 gm/ m ² The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.95	Per square metre			

10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1152.45	per KG			
11	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	100.20	Per square metre			
Total:-						


 Executive Engineer
 Chumarwin Division
 1. Chumarwin

9

SCHEDULE OF QUANTITY


ESTIMATED COST:- Rs 498575/- ONLY.

EARNEST MONEY:- Rs.10000/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-C/O Parking in ward No 2 near Rehan Basera at Ghumarwin Distt. Bilaspur (HP) (SH:-Providing and laying 40x40x12mm thick Exterior Grade vitrified floor tile in terrace

Sr.No	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 400x400 mm including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	367.41			Per square metre	
	Total=					


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .461233/-ONLY.

EARNEST MONEY:- Rs 9300/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-C/O L/R Harijan Basti Barota School to House of purshotam dult . km 0/0 to 1/0 (SH:-C/O R/Wall at RD. 0/105 to 0/118 and 0/320 to 0/330)

Sr.No.	Sub-Head and Item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	31.69			Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for; Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.ncluding carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	128.92			Per square metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	100.48			Per cubic metre	
4	Providing weep holes in brickmasonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	56.00			Each	
	Total=					

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

11

Estimated Cost:-Rs. 99000/- Only.

Earnest Money:- Rs. 3900/- only.

Time allowed:- One Month.

schedule of quantity

Name of work:- A/R land M/O various road under Ghumarwin Sub Division (Sub-Head:- Providing and Fixing of high intensity engineering prismatic sheeting on crash barrier at various roads) **reflective Tap**

Sr.No	Description of item.	Quantity	Rates in		Unit	Amount
			Figures	Words.		
	Providing and Fixing of high intensity engineering grade prismatic sheeting on the front side existing "W" Metal beam crash barrier size 300x450 (three hundred in to four hundred fifty) in yellow and black colour at site complete in all respect, including carriage of materials including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	350.00			per Running Meter	
	Total=					

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

(12)

SCHEDULE OF QUANTITY						
Name of work:-Construction of office Accomadation DA, ADA &P.P at Ghumarwin, Distt. Bilaspur HP.(SH:- Providing and Fixing GRC Jalli 35mm thick& GRC wall cladding size 10*5.5" of stone series shade Grey/cream etc.)					Estimated Cost: Rs499360/- only Earnest money: Rs9980 /- only Time: One Month	
Sr No	Sub Head/Item of works	Quantity	Unit	Rate in figure	Rate in word	Amount
1	Providing and Fixing NTC/ Equavallent Tiles GRC wall cladding size 10*5.5" of stone series shade magnesio Grey (14 nos/ shade cream (4No) or any othr shade if required on RCC surface side as on faces of Arch masonry wall wieh bed thickness of adhesive 3mm (Three millimetre) i/c scaffolding etc. complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer- in Charge.	71.30				
2	Providing and Fixing 35mm Thick NTC/ Equavallent Glass Reiforced Concrete (GRC) screen of approved quality and are in accordance with technical specification i/c scaffolding etc. complete including carriage of materials with in all leads lifts andother incidentals as per direction of Engineer- in Charge.	39.45				

Executive Engineer
Ghumarwin Division
HPPWD, Ghumarwin

SCHEDULE OF QUANTITY

(13)
ESTIMATED COST:- Rs .440647/- ONLY.

EARNEST MONEY:- Rs 8900/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-C/O L/R From Water Supply Tank Dakri to H/B Chuwari via H.B. dakri Bahli. (SH:-C/O V-shape drain in km 0/050 to 0/230 & U-shape at RD. 0/230 to 0/400)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil, including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	118.00			Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for, Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.ncluding carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	216.00			Per square metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	67.43			Per cubic metre	
	Total=					

2
Executive Engineer
Ghumanwin Division
RPPWD Ghumanwin

Schedule of Quantity

Estimated Cost:- Rs. 4,98,593.00

Earnest Money:- Rs. 10,000.00

Time :- One Month

Name of Work:- Construction of Ghumarwin Dabla Morsinghi road km 0/0 to 8/0 (SH:- Construction of U-Shape drain at RD 0/030 to 0/813 and wing wall for hume pipe at RD 4/195 and 3/210 (D/S)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto all leads and lift. dressing of sides and bottom and back filling in trenches with excavated suitable material as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	288.08	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated cement concrete for plain/reinforced concrete in open foundations for all type of structure complete of plain cement concrete grade M-10(M-Ten) nominal mix 1:3:6(One cement: Three sand: Six graded crushed stone aggregate) 20mm(Twenty millimetre size) in or under water and curing complete including pumping of bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D. technical specification clause 802,803,1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	145.23	Per cubic metre			
3	Providing and Laying concrete 1:5:10 (one cement: five sand:ten crushed stone aggregate) 40 mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.16	Per cubic metre			
4	Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using naturally occurring gravel as per Technical Specification Clause 502 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.66	Per cubic metre			
5	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Each			

Executive Engineer
Ghumarwin Division
HPPWD Chumarwin

6	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108.as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. (i)900 mm dia (nine hundred millimetre).	1.25	Per running metre			
	Total:-					


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

15

Estimated Cost - Rs. 207,577.00
 Earnest Money - Rs. 4,200.00
 Time - One Month

- Name of Work:- Restoration of rain damage on link road Rewal Tal to Chappri (SH:- Providing and laying 80mm thick paver block km 0/0 to 0/48

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1 : 4 : 8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.98	Per cubic metre			
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	146.40	per square mtr			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1 : 2 : 4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.39	Per square metre			
	Total:-					

Executive Engineer
 Ghumarwin Division
 P.P.W.D. Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST - Rs 366955/- ONLY

EARNEST MONEY - Rs 7400/- Only

TIME ALLOWED - TWO MONTH.

NAME OF WORK - C/o link road in Naiti to Dugli gram panchayat Fatch (SH:-Formation cutting in km 0/0 to 1/540)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount
			Figures	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-charge at site according to the M.O.R.D. Technical specification clause 300,1603.1,1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber embankments for grade improvements and disposal of all useful/surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing and carriage of machineries, materials tools equipments and execution shall be the absolute responsibility of all the contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-charge including carriage of material with in all leads and lifts. The rate including octroi, royalty, Makrana, toll tax, sale tax or other taxes imposed by the Government. A recovery of useful stone for 41.82 cubic metre at the rate of Rs.300/- (Rupees one hundred seventy) per cubic metre shall be done on pro-rata basis in each running bill for this item	2263.20			Per cubic metre	
Total=						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 356833/- ONLY.

EARNEST MONEY:- Rs. 7200/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:- C/O link to Village Trountra Ghumarwin km 0/0 to 0/600 (SH:-C/O G.C. pavement at RD. 0/335 to 0/390 and Edge wall at RD.0/435 to 0/452)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil, including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	10.63			Per squaremetre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for; Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	30.6			Per cubic metre	
3	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres including carriage of material within all leads and lifts as directed by the Engineer-in-charge.	184.25			Per square metre	
4	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	27.64			Per cubic metre	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	23.87			Per cubic metre	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level C.C. 1:4:8 : (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge.	18.43			Per cubic metre	
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	18.43			Per cubic metre	
8	Providing weep holes in brickmasonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	10.00			Each	
	Total=					

Executive Engineer
Ghumarwin Division
R.P.O. Ghumarwin

18

Schedule of Quantity

Estimated Cost:- Rs. 2,28,714.00

Earnest Money:- Rs. 4,600.00

Time :- Two Month

Name of Work: R/R Damages on Harlog Mehran Tlun Khas road km 0/00 to 5/500 (SH:- C/O R/wall at RD 1/631 to 1/643)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of	21.91	Per cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.00	Per square metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.99	Per cubic metre			
4	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Each			
	Total:-					

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

Schedule of Quantity

Estimated Cost:- Rs. 1,68,217.00

Earnest Money:- Rs. 3,500.00

Time:- Two Month

Name of Work:- Repair and maintainance on Vijaypur Amarpur Dhad Jamman Ghumarwin road km 0/00 to 7/500 (SH:- P/I GSB, G-III and tarring work at RD 7/380 to 7/500)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per cubic metre			
2	Construction of granular sub- base by providing close graded material confirming to specifications, mixing in amechanical mix plant at OMC, carriage of mixed material by tippers to work site for all leads & lifts spreading in uniform layers of specified thicknesss with motor grader on prepared surface and compacting with vibratory powerr roller to achieve the desired density complete to grade -I (size range 75 mm to 0.075 mm) Having CBR value -30 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.00	Per cubic metre			
3	Supplying and stacking at site G-III 53 mm to 22.4 mm size stone aggregate with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.50	Per cubic metre			
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.50	Per cubic metre			

	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 technical specification clause 502. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre			
6	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. On W.B.M / W.M.M. @ 0.4kg/sqm with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre			
7	2 cm premix carpet surfacing with 1.8 cum and 0.90 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 with no solvent with in all leads and lifts and other incidentals. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre			
8	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	180.00	Per Square metre			
Total:-						


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

20

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs.130418/-ONLY.

EARNEST MONEY:- Rs.2700/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK: A/R & M/O HP, PWD Rest House at Bharari Tehsil Ghumarwin Distt. Bilaspur (HP) (SH:-White washing, Distempring and painting etc.)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	609.56			Per square metre	
2	White washing with lime to give an even shade :Old work (two or more coats) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	138.18			Per square metre	
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	470.98			Per square metre	
4	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 ltrs/10 sqm complete including cost of Priming coat. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	524.61			Per square metre	
5	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	248.73			Per square metre	
6	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Old work (one or more coats) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	207.4			Per square metre	
	Total=					

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

SCHEDULE OF QUANTITY

Estimated Cost: Rs.499756 /- only
Earnest money: Rs.9996 /- only
Time: One Month

Name of work:- R/R Damage on Bhager Fatch Road Km 0/0 to 2/0 (SH:- Construction of R/ wall at Rd 0/656 to 0/668.80)

Sr No	Sub Head/Item of works	Quantity	Unit	Rate in figure	Rate in word	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil complete including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge The rate includes all Taxis Imposed by the Governments	113.22	Per Cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge. The rate includes all Taxis Imposed by the Governments	111.36	sqm			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 Cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge The rate includes all Taxis Imposed by the Governments	103.68	Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7. including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge. The rate includes all Taxis Imposed by the Governments	40.00	Per Cubic metre Each			
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge. The rate includes all Taxis Imposed by the Governments	30.4	cum			

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

22

SCHEDULE OF QUANTITY						
Name of work:-C/O additional accomadtion of commarece block at G.D.Colleg at Ghumarwin (SH:- Balance work of toilet block.porch& Panting etc)						Estimated Cost: Rs269654- Earnest money: Rs.5400 /- Time: One Month
Sr No	Sub Head/Item of works	Quantity	Unit	Rate in figure	Rate in word	Amount
1	Excavation in foundations, trenches etc., in earth work, lift upto 1.50 Metres stacking the eacavated soil not more than 3 metres clear from the edge of the excavation and then returning the stacked soil in 15cm. layers, when required in to plinths sides of undations etc., consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres.Including carriage of matrials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Goverments	15.35	cum			
2	Providing and laying cement concrete 1:4:8 (1 cement:4 sand:8 graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in:Foundation and plinth: Including carriage of matrials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Goverments	5.76	cum			
3	Stone filling Under Floor hand Packed Tightly.Including carriage of matrials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Goverments	8.64	cum			
4	Brick work using common burnt clay building bricks in foundation and plinth in :-Cement Mortar 1:6 (1 Cement : 6 Sand) Second Class Bricks Including carriage of matrials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Goverments	0.69	cum			
5	Half brick masonry in common burnt clay building bricks in :-Cement Mortar 1:4 (1 cement:4 sand) Second Class BricksIncluding carriage of matrials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Goverments	9.6	sqm			
6	Providing and laying cement concrete 1:1.5:3 (1cement :1.5 sand :3 graded stone aggregate 20mm. nominal size) and curingcomplete excluding cost of form work and reinforcement for feinforced concrete work in:Suspended floors roofs, landings and shelves and their upports, balconies, beams, girders, bressumers and cantilevers upto floor two level.Including carriage of matrials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Goverments	4.46	cum			

7	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M- 50 grade i/c border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for seperatiy)for 60mm thick inter locking blocks Including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Governments	57.60	sqm		
8	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement :3 sand) and jointed with cement slurry. Including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Governments	19.19	sqm		
9	Providing and fixing PVC water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting up to all heights above ground level :-ii) 1000 litres net capacity tank Including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Governments	1.00	Each		
10	Providing and fixing Brass bib tap 15 mm bib tap with long nose. Including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Governments	5.00	Each		
11	Steel work welded in built up sections, trusses and framed work, including cutting , hoisting , fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. Including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Governments	0.369	Qtl		
12	Applying one coat of Acrylic Washable emulsion Spectrum quartz king or equivalent finish for painting with brushes plain smooth finish composed of acrylic polymere in emulsion inorganic/special pigment siliceous aggregate anti fungicides anti-rusting & foaming in two coat i/c necessary putty to give smooth even surface, sand papered smooth complete. Including carriage of materials with in all Leads and Lift as per direction of Engineer- in- Charge.The rate includes all Taxis Imposed by the Governments	1735.60	sqm		

13	1:2:4 mix in 1 cement 2 sand 4 graded stone agg. 20 mm nominal size foundation concrete 1:4:8 (1 cement : 4 sand : 8 graded stone agg. 40 mm nominal size) in side plastering 15 mm thick with cement mortar 1:3 (1 cement : 3 sand) Finished with a floating coat of neat cement and making channels in concrete 1:2:4 mix (one cement ; two sand ; four graded stone agg.) 20 mm nominal size) finished smooth complete including curing and testing ; inside size 800mm x 800 mm and 500 mm deep including C.I cover with frame (light duty single seal pattern -1) 455 mm 610 mm Internal dimension total wait of cover and frame to be note less that 38 kg 9 wait of cover 23 kg and weight of frame 15 kg). With 200 mm thick walls of brick massonary using common brunt clay building bricks in cement mortar 1:3 sand)The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Each		
14	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipe ISI marked including fitting with approved adhesive etc. complete 110 mm. dia (one hundred ten millimeter) dia. including hoisting up to all heights above ground level. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Per Rmt		

Executive Engineer
 Civil Engineering
 HPI WFO

Dy. Engineer
 Civil Engineering
 HPI WFO

23
SCHEDULE OF QUANTITY

ESTIMATED COST - Rs. 467570/- ONLY

EARNEST MONEY - Rs 9400/- Only

TIME ALLOWED - TWO MONTH

NAME OF WORK:-C/o link road Kallar Plasla km 0/0 to 2/500 (SH:-C/O solid cause way at RD. 0/065, 0/435 and RCC H/Pipe culvert at RD. 0/720 along with wing walls both side) OTMNP

Sr No	Sub-Head and item of work.	Quantity	rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government	51.77			Per cubic metre	
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	10.05			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level C.C. 1:4:8 : (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government	32.48			Per cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	10.53			Per cubic metre	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	7.65			Per cubic metre	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	18.93			Per cubic metre	
7	Centering and shuttering including strutting, propping etc. and removal of form work for; Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. ncluding carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	196.5			Per square metre	

8	Providing weep holes in brickmasonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	9 00			Each	
9	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :900 mm dia. R.C.C. pipe including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	6.25			Running metre	
10	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204 3.8 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	7 20			Per cubic metre	
Total=						

Executive Engineer
Ghumana Division
HPPWB Ghumana

Schedule of Quantity

(24)

Estimated Cost:- Rs. 2,79,825.00

Earnest Money:- Rs. 5,600.00

Time :- One Month

Name of Work:- C/O Mohra Sunali Gallian Sukker Khad road Km 0/00 to 6/150 In Distt. Bilaspur HP.

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation of Geo reference Digital map and collecting of the data for proposed site including field visit, preparation of KML file with Geo coordinates along with marking of habitations to be benefited by construction of project and dumping area for proposed site marking the alignment in soft copy and submission in hard copy including carriage of all equipments with in all leads and lifts as as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octrol, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.150				
2	Processing the case for preparation of forest diversion under forest conservation act 1980 including preparation of revenue paper for land acquire in the project and collection of other field data and relevent document/formats mandotary required to be attached with the case as per latest requirement of ministry of envlorment and forest conservation Govt. of India Dehradun, after getting the joint inspection of site including computer typing of six copies of the case binding complete and getting in through from DFO including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accureatly fillin in all the formats/documents online submissions rectifing observation (if any) and receiving approvals in all respect as peras per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octrol, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.150				
Total:-						

Note:- GST will be paid extra as applicated as per Government rate @ 18%

Terms and condition

- 1 40% payment on receipt of acknowledgement from MOEF website.
- 2 40% payment on transger of case from DFO to C.F Bilaspur.
- 3 20% payment of receipt of principal approval.

Executive Engineer
Ghumarwin Division
H.P.P.W.D. Ghumarwin

Schedule of Quantity


Estimated Cost- Rs. 1,49,861.00

Earnest Money- Rs. 3,000.00

Time :- Two Month

Name of Work: Repair of Veer Sohan Singh Marg in Village Ballu Kharyala G.P. Bakroa (SH:- P/L cement concrete pavement in km 0/110 to 0/146.60)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to a depth of 22.5 cm (twenty two point five centimetre) depth dressing to camber and consolidating with road roller including making good the surface etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	122.61	Per square metre			
2	Construction of granular sub- base by providing close graded material conforming to specifications, mixing in a mechanical mix plant at OMC, cartage of mixed material by tippers to work site for all leads & lifts spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density complete to (size range 75 mm to 0.075 mm) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.39	Per Square metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to all level 1:4:8 (one Cement : four coarse sand : eight graded stone aggregate 40 mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.26	Per cubic metre			
4	Providing and laying cement concrete for plain / reinforced concrete in open foundations complete as per technical specifications clauses 802, 803, 1202 and 1203 1:2:4 (one cement : two sand : four crushed stone aggregate) PCC Grade M-20 (twenty) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.20	Per cubic metre			
Total:-						


 Executive Engineer
 Ghumarwin Division,
 HP, PWD, Ghumarwin.

(26)

Schedule of Quantity


Estimated Cost:- Rs. 3,48,304.00

Earnest Money:- Rs. 7,000.00

Time :- Two Month

Name of Work:- A/R & M/O Bum Dipper Hatwar road km 0/00 to 3/00 (Sh:- C/O Granuller Filling at RD 0/200 to 0/360).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Construction of granular sub- base by providing close graded material confirming to specifications, mixing in amechanical mix plant at OMC, carriage of mixed material by tippers to work site for all leads & lifts spreading in uniform layers of specified thicknesss with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density complete to (size range 75 mm to 0.075 mm) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constreution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	212.90	Per cubic metre			
	Total:-					


Executive Engineer
Ghumarwin Division
E.P.P.W.D. Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST - Rs. 334096/- ONLY.

EARNEST MONEY - Rs. 6700/- Only

TIME ALLOWED - TWO MONTH.

IF WORK -R/R on Sumari to Lower Bhapral road km 0/0 to 6/0 (SH.-P/L interlocking tiles at RD ~~4/16 to 4/17~~ 4/16 to 4/230)

Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
		Figures	Words.		
Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5m including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	245.00			Per square metre	
Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	24.50			Per cubic metre	
Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern, complete allincluding carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	203.00			Per cubic metre	
Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:3 (1 Cement : 1 1/2 coarse sand) : 3 graded stone aggregate 20 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer in charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	4.14			Per cubic metre	
Total=					

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Estimated Cost:- Rs. 1,78,992.00
 Earnest Money:- Rs. 3,600.00
 Time :- Two Month

Schedule of Quantity

Name of Work:- C/O From Ghumarwin Dabla, Morshingi road to vill Baddu(SH:- C/O B/wall at RD 0/331 to 0/348) (OTMNP)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	20.74	Per cubic metre			
2	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Each			
3	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.97	Per square metre			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.12	Per cubic metre			
Total:-						

Executive Engineer
 Ghumarwin Division
 H.P.D. Ghumarwin

SCHEDULE OF QUANTITY

29

ESTIMATED COST:- Rs 240532/- ONLY

EARNEST MONEY - Rs 4900/- Only

TIME ALLOWED - TWO MONTH

NAME OF WORK - C/O link road Chokhna to vill. Dakhuit upto House of Freedom Fighter Late Sh. Ram Singh GP Dangar Distt. Bilaspur (HP) (SH - P/L C.C. pavement at essential reaches in km 0/0 to 0/500) Deposit work.

Sr No	Sub-Head and item of work	Quantity	rates in		Unit	Amount
			Figures	Words		
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	250.00			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level C.C. 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	25.00			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	18.96			Per cubic metre	
Total=						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

30

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 499026/-only

Earnest Money:- Rs. 10000/-only

Time allowed:- Two month

Name of Work:-- Annual Maintenance Plan for the year 2022-23 for rural road (Village Road) (SH:-Providing and laying 30mm thick bituminous concrete on link road Badhaghat to Kotla km4/400 to 4/800).						
Sr. No.	Description of Item	Quantity	Unit	Rates including GST		Amount
				In figures	In words	
1	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 (Eighty-one hundred) KN static roller to achieve the desired degree of compaction as per Technical Specification Clause 506. 50mm (Fifty Millimeter) thick Bitumen VG-30 (Thirty) . (Viscosity grade- thirty) .including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constnction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.22	Per square metre			
2	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. On bituminous surface @ 0.25kg/sqm (zero point two five kilograme/Square metre) including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constnction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1281.00	Per square metre			
3	Providing and laying Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equiped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge. 30 mm (thirty milimetre) compacted thickness with bitumen of grade VG-30 (Viscosity grade- thirty) @ 5.5% (Five point five precentage) (percentage by weight of total mix) and lime filler @ 3% (Three precentage) (percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100-120 (hundred-one hundred twenty) TPH capacity. .including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constnction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	38.43	Per cubic metre			
Total=						

Executive Engineer
Shumanwin Division
Jodhpur

Estimated Cost:- Rs. 4,10,840.00

Earnest Money:- Rs. 8,300.00

Time :- One Month

Schedule of Quantity**Name of Work:-** C/O link road from Ridoo Gadod Badog Bhapral road km 0/00 to 3/00 .(SH:- Providing and laying soling wearing Tarring at RD 2/685 to 2/820)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (eight to twelve tonne) capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	474.86	Per square metre			
2	Supplying and stacking at site 90 mm (ninty metre) to 45 mm (fourty five metre) size stone aggregate. per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.88	per Cubic metre			
3	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density .with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	112.35	per Cubic metre			
4	Supplying and stacking at site 63 mm to 45 mm size stone aggregate with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.74	Per cubic metre			
5	Supplying and stacking at site 53 mm to 22 mm size stone aggregate with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.43	Per cubic metre			

6	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. On W.B.M / W.M.M. @ 0.4kg/sqm.	432.340	Per cubic metre			
7	2 cm premix carpet surfacing with 1.8 cum and 0.90 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 with no solvent.	432.34	Per cubic metre			
8	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete.	432.34	Per square metre			
Total:-						0.00


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 2,74,061.00

Earnest Money:- Rs. 5,500.00

Time :- Two Month

Name of Work:- Construction of link road Samlohal to Chadol via Pickle Factory km 0/00 to 2/660 (SI:- balance work of RCC slab culvert 3.00mtr span at RD 2/621) under SCSP.

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.94	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.45	Per cubic metre			
3	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Suspended floors, roofs, landings, balconies and access platform The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.20	Per sqm			
4	Edges of slabs and breaks in floors and wallsAbove 20 cm wideThe rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.75	per sqm			
5	Providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specification clauses 800 and 1206.3 The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.025	Per cubic metre			
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe 500D or more.The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1279.97	Per Kg			
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	78.72	Per Kg			

8	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. G.I. pipes The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	137.70	Per Kg			
9	Drainage spouts complete as per drawing and technical specifications clause 1209 The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.10	Per RMT			
Total:-						

Executive Engineer
 Sewerage Division
 P.W.D. Bhujwala
 Bhujwala

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs 462902/- ONLY

EARNEST MONEY:- Rs 9300/- Only

TIME ALLOWED:- TWO MONTH

NAME OF WORK:- C/O link road Mihare to Dalote Kwadra Lohat km 0/0 to 5/0 (SH:-C/O R/Wall at RD 2/175 to 2/195 & 2/165 to 2/175)

Sr.No	Sub-Head and item of work.	Quantity	rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	11.69			Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for; Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	126.54			Per square metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	79.70			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	51.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	37.96			Per cubic metre	
6	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with 1/2 tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	101.27			Per cubic metre	
	Total=					

Executive Engineer
Ghumarwin Division
HPPWD Ghumara

Schedule of Quantity

Name of Work:- R/R damages on link road Silh to Nain km 0/00 to 3/285(SH:-C/O R/wall at RD 2/768 to 2/780).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	31.08	Per cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	115.68	Per square metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	79.08	Per cubic metre			
4	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Each			

Estimated Cost:- Rs. 2,70,698.00

Estimated Cost:- Rs. 3,79,698.00

Earnest Money:- Rs. 7,600.00

Time :- Two Month

Executive Engineer,
Ghumarwin Division,
HP, PWD

35

Schedule of Quantity

Schedule of Quantity

Estimated Cost:- Rs.	4,99,692.00
Earnest Money:- Rs.	10,000.00
Time :-	Two Month

Name of Work:- C/O link road from H/Basti Bum to Grah Galah Hatwar Hambot (SH-3 Providing and laying C.C Pavement at RD 0/00 to RD 0/028

Sr. No.	Description Item	Unit	Rates		Quantity	Unit	Rates		Amount
			In figure	In word			In figure	In words	
1	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		53.94		Per square metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		47.40		Per Cubic Metre				
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		35.55		Per Cubic Metre				
Total:-									

Executive Engineer
Chumarwa Division
H.P.P.V.D. Chumarwa