

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-NHD-GA-TENDER/2022-23

4951-53

Dated: 7-9-2022

To

✓ The Executive Engineer (IT Cell),
Nigam Vihar Shimla-2

Subject:-

Publication of Notice Inviting Tenders.

Dear Sir,

Enclosed please find herewith the tender Notice for work as given in the Notice inviting Tender for Uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of HP letter No. PBW(BA9(3)1/2020 dated Shimla-2 16th July 2021. The works mentioned in the tender notice are of urgent nature and in public interest being restoration of rain damages during the monsoon season on various National Highways which has been blocked/ hindered due to heavy rains.

Amal Kumar
Executive Engineer,
National Highway Division,
HP, PWD Hamirpur.

Copy to the Superintending Engineer National Highway Circle HPPWD Shahpur for information please.

Copy to Computer Cell O/O Executive Engineer (IT Cell), Nigam Vihar Shimla-2 for information and necessary action please.

Executive Engineer,
National Highway Division,
HP, PWD Hamirpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by **Executive Engineer, NH Division, HPPWD, Hamirpur (H.P)** from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on or before **21-09-2022 upto 10.30 A.M** and shall be opened on the same day at **11:00 A.M.** in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received upto **20-09-2022 upto 12.00 Noon** on cash payment (Non-Refundable) and tender document will be issued on the same day from **2.30 P.M. to 5:00 P.M.** If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

SN	Name of work	Estimated cost	Earnest money	Time allowed	Cost of form	Form No
1	A/R & M/O on NH- 503 Extn. between Km.19/0 to 44/700 (SH:- Providing and Fixing of two Nos. Sign Boards and repair of W- beam metal crash barrier including fixing of spacers, Posts and locking nut, bolts with welding at different location in Between km. 19/00 to 44/700)	475000.00	9500.00	one Month	350/-	6&8
2	A/R & M/O on NH- 503 Extn Km. 19/0 to 44/700 (SH- Hiring of labour/beldar in Km 19/0 to 44/700)	203000.00	4100.00	one Month	350/-	6&8
3	A/R & M/O on NH- 503 Extn Km. 19/0 to 44/700 (SH- White Washing on B/walls, poles, trees etc. in Km 19/0 to 44/700)	150000.00	3000.00	one Month	350/-	6&8
4	A/R & M/O on NH- 503A Km. 0/0 to 70/0 (SH:- Cleaning of jungle/ cutting of bushes,grass etc. on both sides of road in Km. 38/0 to 67/00)	399526.00	8000.00	one Month	350/-	6&8
5	A/R & M/O on NH- 503 A Km. 0/0 to 70/0 (SH- White Washing on B/walls, side drain ,parapets, trees etc. in Km 40/0 to 67/00)	150000.00	3000.00	one Month	350/-	6&8
6	A/R & M/O on NH-503 (Extn.) Km. 0/0 to 19/0 (SH: - Clearing and grubbing road both sides between Km. 1/500 to 19/0).	175813.00	3600.00	one Month	350/-	6&8
7	A/R & M/O on NH-503 (Extn.) Km. 0/0 to 19/0 (SH: - C/o wire crate at Km. 9/376 (RHS).	468609.00	9500.00	Two Months	350/-	6&8
8	A/R & M/O on NH- 20A (503) Km. 39/0 to 91/0 Raintal- Mubarikpur (SH:- Clearance of grass in Km. 39/0 to 91/00)	299889.00	6500.00	one Month	350/-	6&8
9	A/R & M/O on NH-70 (New NH-03) KM 58/400 to 196/495(SH: Construction of footpath for pedestrian with 40 mm thick interlocking paver blocks including F/F kerb stone 300x300x100 mm in km. 139/300 to 139/675 (RHS)	499590.00	10000.00	one Month	350/-	6&8

Draft notice inviting/ specification special conditions can be seen in this office on any working day between **11:00 AM to 4:00 PM** ambiguous/ Telegraphic conditional tenders by fax shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as

well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. All the

application must accompanied with the Earnest Money in the shape of call at deposit/ N.S.C. purchased from any post office in H.P/FDR from any nationalized bank duly pledged in favour of Executive Engineer. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: - The following document are required to be attached with the application:-

- 1 A copy of valid enlistment and renewal certificate.
- 2 A copy of GST
- 3 Any other information as desired by the Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false, at any stage the tender is liable to be rejected and action taken against contractor/ firm.
- 4 Copy of Pan Card.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

NO.PW-NHD-HMR-GA-TENDER/2022-23
COPY FORWARDED TO THE FOLOWING:


4926-50 DATED: 7-9-2022


- 1 The Engineer-in-Chief, HPPWD, Shimla-I
- 2 The Chief Engineer (NH), HPPWD, Shimla-I.
- 3 All the Superintending Engineer, NH /B&R in HP.
- 4 The D.C Hamirpur District Kangra at Dharamshala.
- 5 The D.C Hamirpur District Hamirpur.
- 6 All the Executive Engineer, NH/B&R in HP.
- 7 The Sub-Divisional Officer (Civil) Hamirpur Hamirpur District Hamirpur.
- 8 All the Assistant Engineer, NH/B&R in HP.
- 9 The B.D.O. Hamirpur District Hamirpur.
- 10 The Executive Officer, Municipal Committee Hamirpur
- 11 Secretary Zila Parishad Hamirpur
- 12 All the Contractors/ Suppliers working under HPPWD Hamirpur.
- 13 All the Head of Branches of this office.
- 14 Notice Board

Executive Engineer,
NH Division, HPPWD
Hamirpur.

Certificate

Certified that the tenders called vide this office letter No. NO.PW-NHD-HMR-GA-TENDER/2022-23-4926-50 DATED: - 07-09-2022 are of emergent/ urgent nature and in public interest being restoration of rain damages on various National Highways falls under the jurisdiction of this division during the monsoon season.


Executive Engineer,
NH Division, HPPWD
Hamirpur.



Job No - I

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 475000.00
 Earnest Money:- Rs. 9500.00
 Time: - One Month

Name of work :A/R & M/O NH-503 Extn at Km 19/00 to 44/700 (SH- Providing and fixing of two nos Sign boards and repair of W- beam metal crash barrier including fixing of spacers, posts and locking nuts, bolts with welding at different locations in between Km 19/0 to 44/700)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign as per IRC :67 made of high intensity grade sheeting vide clause 801.3. 2mm thick aluminium sheeting, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over back support frame of min 25x25x3mm Angle mounted on a mild steel circular pipe 65 NB, 3.2 mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges.	2.00			Each	
2	Repair of existing W beam crash barrier by providing spacers, posts where ever missing and locking them with metal beam rail with providing nuts and bolts and welding them including all the labour charges as per direction of Engineer in charge					
(A)	Spacers 150*75*5 mm, 330 mm long @ 3.50 Kg each	2625.00			Per Kg.	
(B)	Posts 150*75*5 mm, 1.80 mtr long @ 29.50 Kg each	2006.00			Per Kg.	
	G. Total					

Amir Chahal
 Executive Engineer,
 National Highway Division,
 HP.PWD, Jalandhar (HP)

Job No = 2

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 203000.00
 Earnest Money:- Rs. 4100.00
 Time:- One Month

Name of work :- A/R & M/O on NH-503 Extn. Km. 0/0 to 44/700 (SH: Hiring of labour/ beldar in Km. 19/0 to 44/700					
Sr No.	Description of item.	Qty.	Rate		Unit
			In Figure	In Words	
1	Hiring of Labour/Belder as and whenever required the Deptt. For carrying out miscellaneous road repair activities such as clearing of drains, culverts, bridges, repair of rain cuts, removal of vegetation from bridges and culverts etc. Cleaning/clearing of Drainage sports of culverts and bridges complete in all entire satisfaction of Engineer - in - Charge.	580.00			Per Day
G.Total					

Arjun Chavhan
 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

Job No-3

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 150000.00
 Earnest Money:- Rs. 3000.00
 Time: - One Month

Name of work :- A/R & M/O on NH-503 Extn. Km. 19/0 to 44/700 (SH:- White washing on B/wall, poles, trees etc. in km. 19/0 to 44/700)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	White washing of parapet walls of CD work and tree trunks, white washing two coats on parapets walls, CD works and tree trunks including preparation of surface by cleaning scrapping etc. as per technical specifications Clause 1915 in direction of Engineer-in-Charge.	10000.00			Per Square meter	
G. Total						

Arvind Chaur
 Executive Engineer,
 National Highway Division,
 HP PWD., Hamirpur (HP)

Job No - 4

Earnest Money:- Rs. 8000.00
Time: - One Month

Name of work :- A/R & M/O on NH-503A Km. 0/0 to 70/0 (SH:- Clearing of jungle/ cutting of bushes, grass etc. on both sides of road in Km. 38/0 to 67/00)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm (Three hundred millimeter), removal of stumps of scuh trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000m (One thousand meter) including removal and disposal of top organic soil not exceeding 150mm (one hundred fifty millimeter) in thickness as per Technical Specification clause 201. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge	72641.090			Per square meter	
	G.Total					

Amal Chaur
Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

Job No-5

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 150000.00
 Earnest Money:- Rs. 3000.00
 Time: - One Month

Name of work :- A/R & M/O on NH-503A Km. 0/0 to 70/0 (SH:- White washing on B/wall, side drain, parapets, trees etc. in km 40/0 to 67/00)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	White washing of parapet walls of CD work and tree trunks, white washing two coats on parapets walls, CD works and tree trunks including preparation of surface by cleaning scrapping etc. as per technical specifications Clause 1915 in direction of Engineer-in-Charge.	10000.00			Per Square meter	
	G. Total					

A. J. G. M.
 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirgarh (HP)

Job No = 6

Estimated Cost:- Rs. 175813.00
 Earnest Money:- Rs. 3600.00
 Time: - One Month

Name of work :- A/R & M/O on NH-503 (Extn.) Km. 0/0 to 19/00 (SH:- Clearing and grubbing road both sides between Km. 1/500 to 19/0)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm (Three hundred millimeter), removal of stumps of scuh trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000m (One thousand meter) including removal and disposal of top organic soil not exceeding 150mm (one hundred fifty millimeter) in thickness as per Technical Specification clause 201. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge	31966.000			Per square meter	
	G.Total					

Amrinder
 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

Job No = 7

Estimated Cost:- Rs. 468609.00

Earnest Money:- Rs. 9500.00

Time:- Two Months

Name of work :- A/R & M/O on NH-503 (Extn.) Km. 0/0 to 19/0 (SH:- C/o wire crate at Km 9/376 (RHS)

Description of item.

Sr No.	Qty.	Rate		Unit	Amount
		In Figure	In Words		
1	31.46			Per Cubic meter	
Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimeter) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges.					
2	151.880			Per Cubic meter	
Providing and laying of boulder apron laid in wire crates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each. including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge.					
G. Total					

Executives Engineer
 National Highway Division
 HPPWD Hampden

Job NO = 8

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 299889.00
 Earnest Money:- Rs. 6500.00
 Time:- One Month

Name of work :- A/R & M/o on NH-20A km 39/0 to 91/0 Ranital- Mubarikpur (SH:-Clearance of grass in Km. 39/0 to 91/00)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm (Three hundred millimeter), removal of stumps of scuh trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000m (One thousand meter) including removal and disposal of top organic soil not exceeding 150mm (one hundred fifty millimeter) in thickness as per Technical Specification clause 201. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge	54525.272			Per square meter	
G. Total						

Anand Chavhan
 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

Job No = 9

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on NH-70 (New NH-03) KM 58/400 to 196/495(SH: Construction of footpath for pedestrian with 40 mm thick interlocking paver blocks including F/F kerb stone 300x300x100 mm in km. 139/300 to 139/675 (RHS)					
Estimated Cost:- Rs.		499590.00		One Month	
Earnest Money:- Rs.		10000.00			
Time: -					
Sr No.	Description of item.	Qty.	Rate		Unit
			In Figure	In Words	
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involve for sub grade to be paid for seaparately) depending upon the classification of soil. Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	303.000			Per Square meter
2	Providing and laying, mechanically mixed & vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and technical specifications clause 802.803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregates 20mm (Twenty millimeter) nominal size) including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge.	44.460			Per Cubic meter
3	Providing and fixing Kerb stone at or near ground level factory made of M-25 grade cement concrete in position to the required line and level and curvature jointed with cement mortar 1:3 of kerb stone of size 300x300x100 mm as per the directions of engineer in charge complete in all respect.	9.074			Per Cubic meter
4	Providing and laying of interlocking concrete block pavements having thickness of 40 mm as per drawing and technically specifications 1504 as per the directions of engineer in charge complete in all respect.	211.715			Per Square meter
G. Total					

Andam
Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)