



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041
Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23-
To

- 11706-15

Dated:- 02-09-2022

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.**

Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.

Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in, Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041.

NOTICE INVITING TENDER.


Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **17-09-2022 up to 10.30 A.M.** and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **15-09-2022 upto 4.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **16-09-2022** during office hours till **4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	C/O Link Road to Village Baroh Km. 0/00 to 0/615. (SH:- P/L Interlocking Paver Block Pavement at RD. 0/00 to 0/070) (Under O.T.M.NP. Head).	Rs. 3,98,786.00 Only	Rs. 8,000.00 Only	One Month
2	C/O Link Road to Village Lasmai Km. 0/00 to 2/00. (SH:- P/L Interlocking Paver Block Pavement at RD. 0/935 to 1/00)	Rs. 4,08,623.00 Only	Rs. 8,200.00 Only	One Month
3	A/R & M/O Various Road Under HPPWD Sub Division Dhaneta. (SH:- P/F Inauguation/Foundation Stone Pelmet) (Pansai).	Rs. 81,625.00 Only	Rs. 1,700.00 Only	One Month
4.	Restoration of Rain Damages on D.A.V. School Kangoo to Harizan Basti Tan Km. 0/00 to 2/500. (SH:- Removal of Slips, Maintenance of Drain and Maintenance of Earthen Shoulders in Between Km. 0/00 to 1/500).	Rs. 4,49,840.00 Only	Rs. 9,000.00 Only	Two Months
5	C/O Link Road Dashwin to Rail (Patneri) in Km. 0/00 to 1/200. (SH:- P/L 900mm Dia RCC Hume Pipe Culvert at RD. 0/450, Both Side, R/Wall at RD. 0/320 to 0/331 and U-Shape Drain at RD. 0/00 to 0/043) (Under OTMNP Head).	Rs. 4,57,274.00 Only	Rs. 9,200.00 Only	Two Months
6	A/R & M/O HPPWD Rest House Building at Bhota. (SH:- P/F Curtain Cloth).	Rs. 87,780.00 Only	Rs. 1,800.00 Only	One Month
7	C/O Link Road From Bhira to PHC Kashmir Road Km. 0/00 to 3/00. (SH:- P/L Interlocking Paver Block Pavement at RD. 0/830 to 0/960) (Under SCSP Head).	Rs. 4,18,065.00 Only	Rs. 8,400.00 Only	One Month
8	Restoration of Rain Damages on Hareta Bah to loo Road Km. 0/00 to 3/760 (SH:- C/O R/Wall at RD. 1/800 to 1/820).	Rs. 4,08,972.00 Only	Rs. 8,200.00 Only	One Month

HIM SUCHANA ANAM JAN SAMPARK.


Executive Engineer
Barsar Division
HPPWD Barsar

On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-105/2022-23-1170675 dated 02/09/2022


Executive Engineer
Bansar Division
HPPWD Bansar.

Schedule of quantity

Job No :- 1

Estimated Cost Rs:-398786 .00

Earnest Money Rs:- 8000.00

Time Limit :- one Month

Name of work:-C/O link road to village Baroh Km 0/00 to 0/615
(SH:- P/L intelocking paver block Pavement at Rd 0/00 to 0/070)
(under OTMNP Head)

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	109.20	Cubic metre			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	39.00	Cubic metre			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.34	Cubic metre			Per Cubic Metre	

4	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make confirming to the Nitco, Modern, Gico, NTC, BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	390.00	Square metre			Per square Metre
						Total:



Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:-C/O link road to village Lasmai Km 0/00 to 2/00
(SH:- P/L interlocking paver block Pavement at Rd 0/935 to 1/00)
(under OTMNP Head)

Job No :- 2
Estimated Cost Rs:-408623 .00
Earnest Money Rs:- 8200.00
Time Limit :- one Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	109.20	Cubic metre			Per Cubic Metre	
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax, GST or any other taxes imposed by the Government.	19.50	Cubic metre			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	39.00	Cubic metre			Per Cubic Metre	

4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can presibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.44	Cubic metre			Per Cubic Metre
5	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make confirming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	390.00	Square metre			Per square Metre
						Total:-



Executive Engineer

Barsar Division

HPPWD Barsar

Schedule of quantity

Name of work:- A/R & M/O various road under HPPWD Sub Division Dhaneta
(SH:- P/F inaguration / foundation stone Pelmet (Pansai))

Job No :- 3
Estimated Cost Rs:-81625 .00
Earnest Money Rs:- 1700.00
Time Limit :- one Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Providing and fixing remote control curtain of (Moteraes roller blinds) size 8 feet 6 inch (eingth feet six inch) into 6 feet 6 inch (six feet six inch) with all accessries (inaguration/ foundation stone Pelmet) including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	170.28			Each	
					Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Name of work:- Restoration of rain damages on D.A.V. Kangoo to Harizan Basti Than Km 0/00 to 2/500
(SH:- Removal of slips, Maintenance of drain & maintenance of earthen shoulder in between Km 0/00 to 1/500)

Job No:- 4
Estimated Cost Rs:-449840.00
Earnest Money Rs:-9000.00
Time Limit :- Two Month

Sr. No	Description of item	Quantity		Figure	Rate inclusive all taxes i/c G.S.T	Unit	Amount
		518.93	cubic metre			Per Cubic Metre	
1	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slopes and disposal all material upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	518.93	cubic metre			Per Cubic Metre	
2	Clearing and grubbing road land clearing and grubbing road land including uprooting wild vegetation grass, bushes, shrubs, saplings and trees of girth upto 300mm (three hundred millimetre) removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned , upto a lead of 1000 metre (one thousand metre) including removal and disposal of top organic soil not exceeding 150mm (one hundred millimetre) in thickness as per Technical Specification Clause 201 including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	64980.00	Square metre			Per Cubic Metre	
3	Maintenance of earthen shoulder (filling with fresh selected soil making up less of material / irregularities on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000mtrs as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government .	10360.00	Square metre			Per square Metre	
4	Maintenance of Drain :- Maintenance of drain including erosion, repair clearing , cleaning reshaping regarding deeding of side drain as well as catch water drain as per technical specification clause No 1907 including carriage of material and equipments in all leads and lifts with all mode of transport and as per the direction of Engineer-in-Charge. including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	28000.00	Running metre			Per running Metre	
						Total:-	

(Signature)

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Job No:- 5

Name of work:- C/O link road Daswin to Rail (Patneri) Km 0/00 to 1/200

Estimated Cost Rs:-457272.00

(SH:- P/L 900 mm dia RCC Hume Pipe culvert 0/450 both side & C/O R/wall at Rd 0/320 to 0/331& U-Shape drain at Rd 0/00 to 0/043))


Earnest Money Rs:-9200.00

(under OTMNP Head)

Time Limit :- Two Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	95.98		Per Cubic Metre	
2	Providing and laying 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm (Fourty millimetre) nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax, GST or any other taxes imposed by the Government.	2.53		Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	37.34		Per Cubic Metre	

4	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	34.46	Cubic metre		Per Cubic Metre
5	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	16.44	Cubic metre		Per Cubic Metre
6	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	14.00	Numbers		Each
7	Providing and Laying reinforced cement concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government .	7.50	Running metre		Per running Metre
				Total:-	



 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Job No :- 6
 Estimated Cost Rs:-87780 .00
 Earnest Money Rs:- 1800.00
 Time Limit :- one Month

Name of work:- A/R & M/O H.P.P. W.D Rest House at Bhotia
 (SH:- P/F Curtain cloth)

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Providing and fixing curtain of superior quality as per directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	44.00	Numbers			Each	
						Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Name of work:-C/O link road from Bhira to P.H.C Kashmir Km 0/00 to 3/00

(SH:- P/L intelocking paver block Pavement at Rd 0/830 to 0/960)

(under SCSP Head)

Job No :- 7

Estimated Cost Rs:-418065 .00

Earnest Money Rs:- 8400.00

Time Limit :- one Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	109.20			Per Cubic Metre	
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	39.00			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	39.00			Per Cubic Metre	

4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.44	Cubic metre			Per Cubic Metre
5	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make confirming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	390.00	Square metre			Per square Metre
Total:-						

[Signature]

Executive Engineer

Barsar Division

HPPWD Barsar

[Signature]

Schedule of quantity

Name of work:- Restoration of rain damages on Hareta Bahloo road Km 0/00 to 3/760
(SH:- C/O R/Wall at Rd 1/800 to 1/820)

Job No:- 8


Estimated Cost Rs:-408972.00

Earnest Money Rs:-8200.00

Time Limit :- One Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T	Unit	Amount
		23.80	Cubic metre			
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.				Per Cubic Metre	
2	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	83.20	Cubic metre		Per Cubic Metre	
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	24.00	Cubic metre		Per Cubic Metre	

4	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D- plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	Numbers		Each	
					Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar