



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in, Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23-
To

-12941-50

Dated:- 15-09-2022


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041


Fax No. 01972-288041.

NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **24-09-2022 up to 10.30 A.M.** and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **22-09-2022 upto 4.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **23-09-2022** during office hours till **4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (Section Bhota) (SH:- Supply and Stacking 50mm to 25mm, 10mm to 12mm Course and Sand for Patch Work at Various Road at Various RDs).	Rs. 1,72,500.00 Only	Rs. 3,500.00 Only	One Month
2	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (Section Bhota) (SH:- Supply and Stacking of Fuel Wood for Patch Work).	Rs. 1,05,000.00 Only	Rs. 2,100.00 Only	One Month
3	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (SH:- P/F Dual Direction Delineators at Various Road at Various RDs).	Rs. 4,63,500.00 Only	Rs. 9,300.00 Only	One Month
4.	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (SH:- P/F of Mile Stone Under HPPWD Sub Division Barsar).	Rs. 4,12,535.00 Only	Rs. 8,300.00 Only	Two Months
5	Repair and Maintenance of Vety. Hospital Building at Bhota. (SH:- Balance Work of Demolishing C-C Door, Window and P/F Collapsible Door etc).	Rs. 1,68,392.00 Only	Rs. 3,400.00 Only	One Month
6	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (SH:- Providing and Supplying informatory Board)	Rs. 4,45,958.00 Only	Rs. 9,000.00 Only	One Month
7	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (SH:- Providing and Supplying informatory Board)	Rs. 4,42,743.00 Only	Rs. 8,900.00 Only	One Month
8	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (SH:- Providing and Supplying informatory Board)	Rs. 1,46,082.00 Only	Rs. 3,000.00 Only	One Month

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
Barsar Division
HPPWD Barsar.


On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-105/2022-23-

12941-50 dated 15/09/2022


Executive Engineer
Barsar Division
HPPWD Barsar.

Job No:- 1

Estimated cost Rs:- 172500.00

Earnest money Rs:- 3500 .00

Time Limit :- One Month

Schedule of quantity

Name of work:- A/R & M/O on various road under HPPWD Sub Division Barsar

(SH:- Supply & stacking 50mm to 25mm, 10mm to 12mm course & sand for patch work at various road at various Rds)

(Section Bhota)


Sr.No	Description of item	Quantity	Unit	Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figures	words		
1	Supplying and stacking at site hard crushed stone aggregate 10mm to 12mm (ten millimetre into twelve millimetre) nominal size broken/ crushed stone aggregate including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, G.S.T or other taxes imposed by the Government .	70.00	cubic metre			per cubic metre	
2	Supplying and stacking at site hard crushed stone aggregate 50mm to 25mm (fifty millimeter into twenty five millimeter)nominal size broken / crushed aggregate including carriage of material within all leads and lifts and other incidentalsThe rates are inclusive octroi , royalty , Malkana, toll tax, G.S.T or other taxes imposed by the Government .	60.00	cubic metre			per cubic metre	
3	Supplying and stacking river bed course sand at site work free from foreign material including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, G.S.T or other taxes imposed by the Government .	10.00	cubic metre			per cubic metre	
						Total:-	

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity
 Name of work: A/R & M/O various roads under HPPWD Sub-Division Barsar
 (SH:- Supplying & Stacking of fuel wood for patch works (Section Bhotra)

Job No-2
 Estimated cost Rs:- 105000.00
 Earnest money Rs:- 2100 .00
 Time Limit :- One Month

Sr.No	Discription of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Supplying and stacking dry bansu hard fuel wood in logs not less than 25cm (twenty five centimeter) in girth and stacking in proper stacks including loading unloading including sand paper smooth complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	150.00	Quintal		Per Quintal	
					Total:-	



Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity
Name of work:-A/R & M/O on various road under HPPWD Sub Division Barsar
(SH:- P/F Dual Direction Delinators at various Rd)

Job No 3
Estimated cost Rs:-463500.00
Earnest money Rs:- 9300.00
Time Limit :- Two Month


Sr.No	Discription of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Providing and fixing dual direction delineator made of dia 18G (eighteen gauge) MS rectaanugular pipe of sizw 25 x 63mm (twenty five into sixty three millimetre) and of length 600 mm (six hundred millimetre) pipe stove enameled and baket to 120 (one hundred twenty) power coated head made of ABC plastic rectangular moulded with flat face provided with high intensity prismatic reflectors of colour (white/Yellow/Red) of size 100 x 125 mm (one hundred into one hundred twenty five millimetre) with additional to reflective strips of 20mm (twenty millimetre) wide make green light as per the direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	450.00			Each	
					Total:-	


Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity
Name of work:-A/R & M/O on various road under HPPWD Sub Division Barsar
(SH:- P/F mile stone under HPPWD Sub Division Barsar)

Job No 4
Estimated cost Rs:-412535.00
Earnest money Rs:- 8300.00
Time Limit :- Two Month

Sr.No	Discription of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Numbers	Words	Figures	words		
1	Providing and fixing 5 th (Fifth) kilometre stone precast re-inforced cement concrete M-15 (M-Fifteen) grade design mix minimum cement content 240kg(Two hundred forty kilogramme), per cubic metre kilometre stone of standard design as per IRC 8, fixing in position including painting and printing etcetera as per drawing and technical specification MORD 2014 clause 1703 including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	65.00				Each	
2	Providing and fixing ordinary kilometre stone precast re-inforced cement concrete M-15 (M-Fifteen) grade design mix minimum cement content 240kg(Two hundred forty kilogramme) per cubic metre kilometre stone of standard design as per IRC 8, fixing in position including painting and printing etcetera as per drawing and technical specification MORD 2014 clause 1703 including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	20.00				Each	
3	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701 Hindi (Matras commas and the like not to be measured and paid for. Half letters shall be counted as half only) including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	400.00				Per Cm height per letter	
4	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered/ concrete surfaces as per drawing and Technicak Specification Clause 1701 including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	70.20				Per square Metre	
						Total:-	



Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Job No 5
Estimated cost Rs:-168392.00
Earnest money Rs:- 3400.00
Time Limit :- One Month

Name of work:- Repair & maintenance of Veterinary Hospital building at Bhota
(SH:- Balance work of Demolishing Cement Concrete, Door, window & P/F Collapsible Door etc.)

Sr.No	Discription of item (Deposit works)	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50m (fifty metres) lead Nominal concrete 1:3:6 (one cement :three Sand :six graded crushed stone aggregate) or richer mix i/c equivalent design mix as per direction of Engineer - in - charge including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana , toll tax, GST or other taxes imposed by the Government.	12.00		Cubic metre	Per Cubic Metre	
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50m (fifty metres) lead of area 3 sqm (three square metres) and below as per direction of Engineer - in - charge including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana , toll tax, GST or other taxes imposed by the Government.	26.00		Numbers	Each	
3	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm (twenty into ten into two millimetre) and braced with flat iron diagonals 20x5 mm(twenty into five millimetre) size, with top and bottom rail of T-iron 40x40x6 mm, (forty into forty into six millimetre) with 40 mm(forty millimetre) dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	12.00		Square metre	Per square metre	
4	Providing and laying integral cement based treatment for hydrophilic in nature for waterproofing treatment to the RCC structures like retaining walls of the basement, water tanks, roof slabs, podiums, reservoir, sewage & water treatment plant, tunnels / subway and bridge deck etc., prepared by mixing in the ratio of 5 : 2 (5 parts integral crystalline slurry : 2 parts water) for vertical surfaces and 3 : 1 (3 parts integral crystalline slurry : 1 part water) for horizontal surfaces and applying the same from negative (internal) side with the help of synthetic fiber brush. The material shall meet the requirements as specified in ACI- 212-3R-2010 i.e by reducing permeability of concrete by more than 90% compared with control concrete as per DIN 1048 (one thousand fourty eight) and resistant to 16 (sixteen) bar hydrostatic pressure on negative side. The crystalline slurry shall be capable of self-healing of cracks up to a width of 0.50mm (zero point fifty millimetre) . The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage for vertical surface two coats @ 0.70 kg per sqm (zero point seventy kilogramme square metre) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	120.00		square metre	Per square Metre	
					Total:-	


Executive Engineer
Barsar Division
HPPWD Barsar

Name of work:-A/R & M/O on various road under HPPWD Sub Division Barsar
(SH:- Providing and supplying informatory board)

Schedule of quantity


Job No 6

Estimated cost Rs:-445958.00

Earnest money Rs:- 9000.00

Time Limit :- One Month

Sr.No	Discription of item	Quantity	Rate inclusive all taxes /c G.S.T		Unit	Amount
			Figures	words		
1	Providing informatory board with as per specification and drawing MS sheet of 2mm (two millimetre) thick duly welded with MS flat iron 32mmx 5mm (thirty two millimetre into five millimetre) size on edges MS sheet tube post of size 48.3 (fourty eight point three) outer dia complete welded with MS sheet as per drawing all section of framed post and MS tube will be primer painted and as per direction of Engineer in charge 900x900 mm (nine hundred into nine hundred millimetre) size including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	30.00			Each	
2	Providing informatory board with as per specification and drawing MS sheet of 2mm (two millimetre) thick duly welded with MS flat iron 32mm x 5mm (thirty two millimetre into five millimetre) size on edges MS sheet tube post of size 48.3 (fourty eight point three) outer dia complete welded with MS sheet as per drawing all section of framed post and MS tube will be primer painted and as per direction of Engineer in charge 600x450 mm (six hundred into four hundred fifty millimetre) size including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	86.00			Each	
					Total:-	


Executive Engineer
Barsar Division
HPPWD Barsar

Name of work:-A/R & M/O on various road under HPPWD Sub Division Barsar
(SH:- Providing and supplying informatory board)

Schedule of quantity

Job No 7

Estimated cost Rs:-442743.00

Earnest money Rs:- 8900.00

Time Limit :- One Month

Sr.No	Discription of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Providing informatory board with as per specification and drawing MS sheet of 2mm (two millimetre) thick duly welded with MS flat iron 32mmx 5mm (thirty two millimetre into five millimetre) size on edges MS sheet tube post of size 48.3 (fourty eight point three) outer dia complete welded with MS sheet as per drawing all section of framed post and MS tube will be primer painted and as per direction of Engineer in charge 900x900 mm (nine hundred into nine hundred millimetre) size including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	36.00			Each	
2	Providing informatory board with as per specification and drawing MS sheet of 2mm (two millimetre) thick duly welded with MS flat iron 32mm x 5mm (thirty two millimetre into five millimetre) size on edges MS sheet tube post of size 48.3 (fourty eight point three) outer dia complete welded with MS sheet as per drawing all section of framed post and MS tube will be primer painted and as per direction of Engineer in charge 600x450 mm (six hundred into four hundred fifty millimetre) size including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	76.00			Each	
					Total:-	

Executive Engineer
Barsar Division
HPPWD Barsar

Name of work:-A/R & M/O on various road under HPPWD Sub Division Barsar
(SH:- Providing and supplying informatory board)

Schedule of quantity


Job No 8

Estimated cost Rs:-146082.00

Earnest money Rs:- 3000.00

Time Limit :- One Month

Sr.No	Discription of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Numbers	Figures	words			
1	Providing informatory board with as per specification and drawing MS sheet of 2mm (two millimetre) thick duly welded with MS flat iron 32mm x 5mm (thirty two millimetre into five millimetre) size on edges MS sheet tube post of size 48.3 (fourty eight point three) outer dia complete welded with MS sheet as per drawing all section of framed post and MS tube will be primer painted and as per direction of Engineer in charge 600x450 mm (six hundred into four hundred fifty millimetre) size including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	43.00				Each	
					Total:-		


Executive Engineer
Barsar Division
HPPWD Barsar