

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed **Percentage rates** tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **12.09.2022** Up to 11.30 A.M. and will be opened on the same day at 3.30 P.M. in the presence of interested contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto 1.00PM & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on 9.09.2022.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No.II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr.No	Name of work	Estt cost	E/Money	Cost of tender form	Time limit
1	RRD on Kun to kot road km 0/0 to 2/0 (SH:- C/O PCC B/wall at RD 0/430 to 0/438)	Rs.142748/-	Rs.2900/-	Rs.350	One month
2	RRD on Khalanoo to Mahan road km 0/0 to 2/750 (SH:- C/O PCC R/wall at RD 2/330 to 2/345)	Rs.362932/-	Rs.7300/-	Rs.350	One month
3	RRD on Roda Nallah Karkoh Arthi road km 0/0 to 12/300 (SH:- C/O PCC R/wall at RD 9/880 to 9/890)	Rs.498654/-	Rs.10000/-	Rs.350	One month
4	RRD Sandhapatan Bharol Bangora Hard Ropri Kalg Traimbli Basahi Drubal Chauranj Banwar Kun ka Tar Mandhokar Bhargaon Kotli road km 70/600 to 85/0 (SH:- C/O toe wall & PCC R/wall at RD 83/259 to 83/268)	Rs.464488/-	Rs.10000/-	Rs.350	One month
5	-do- (SH:- As above at RD 75/592 to 75/604)	Rs.492958/-	Rs.9900/-	Rs.350	One month
6	-do- (SH:- As above at RD 75/553 to 75/561)	Rs.486686/-	Rs.9800/-	Rs.350	One month
7	RRD on Chail Gohar Pandoh road km 24/0 to 29/600 (SH:- C/O R/wall at RD 27/825 to 27/837)	Rs.498469/-	Rs.10000/-	Rs.350	One month
8	-do- (SH:- As above at RD 27/535 to 27/545)	Rs.371413/-	Rs.7500/-	Rs.350	One month
9	-do- (SH:- As above at RD 25/837 to 25/849)	Rs.497598/-	Rs.10000/-	Rs.350	One month
10	RRD on Bari Dhanyari road km 0/0 to 5/300 (SH:- C/O R/wall at RD 0/500 to 0/514)	Rs.487169/-	Rs.9800/-	Rs.350	One month
11	-do- (SH:- As above at RD 1/157 to 1/172)	Rs.499937/-	Rs.10000/-	Rs.350	One month
12	RRD on Talyahar Pairi road km 0/0 to 5/100 (SH:- C/O B/wall at RD 2/120 to 2/135)	Rs.268187/-	Rs.5400/-	Rs.350/-	One month
13	-do- (SH:- C/O R/wall at RD 4/130 to 4/140)	Rs.285294/-	Rs.5800/-	Rs.350/-	One month
14	RRD on Ratti Pul to Alahtu via Saini Mohri road km 0/0 to 6/500 (SH:- C/O PCC R/wall at RD 1/410 to 1/421.50)	Rs.216413/-	Rs.4400/-	Rs.350/-	One month
15	A/R & M/O on Ganpati Kun Ka Tar road km 0/0 to 21/500 (SH:- C/O r/wall for protection of road at RD 1/070 to 1/081)	Rs.288096/-	Rs.5800/-	Rs.350/-	One month
16	RRD on Sain to Sadoh road km 0/0 to 14/400 (SH:- C/O R/wall at RD 7/620 to 7/630)	Rs.492578/-	Rs.9900/-	Rs.350/-	One month
17	-do- (SH:-As above at RD 0/280 to 0/294)	Rs.479156/-	Rs.9600/-	Rs.350/-	One month
18	-do- (SH:- C/O B/wall at RD 0/280 to 0/305)	Rs.246596/-	Rs.5000/-	Rs.350/-	One month
19	-do- (SH:- C/O R/wall at RD 12/800 to 12/808)	Rs.337569/-	Rs.6800/-	Rs.350/-	One month

20	RRD on Khad Kalyana to Bhaled road km 0/0 to 6/0 (SH:- C/O R/wall at RD 1/050 to 1/068)	Rs.498858/-	Rs.10000/-	Rs.350/-	One month
21	-do- (SH:- As above at RD 1/980 to 1/990)	Rs.493595/-	Rs.9900/-	Rs.350/-	One month
22	-do- (SH:- As above at RD 1/970 to 1/980)	Rs.493595/-	Rs.9900/-	Rs.350/-	One month
23	RRD on Circular road Twambra Nallah to Panjethi road km 0/0 to 2/0 (SH:- C/O R/wall at RD 1/063 to 1/072)	Rs.235997/-	Rs.4800/-	Rs.350/-	One month
24	RRD on Majhwar Moviseri via Sari Rakhoon road km 0/0 to 6/800 (SH:- C/O R/wall at RD 3/445 to 3/460)	Rs.266171/-	Rs.5400/-	Rs.350/-	One month

GENERAL CONDITIONS:-

- 1 The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- 2 The contractors whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to compete in tendering for four months.
- 3 The contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
- 4 The rates beyond the limit of -30% and over + 5%, will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30 % for unbalanced bid in case the rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively.

No.PW-MDII-CB NIT (off line) /2021-

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt.Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt.Mandi HP
4. The Chief Engineer,(MZ)HPPWD: Mandi.
5. The Superintending Engineer, Ist Circle, HPPWD: Mandi.
6. The Distt.Panchyat officer Mandi Distt.Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt.Mandi HP
8. All A.E,S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies


Executive Engineer
Mandi Division No.II
HP.PWD Mandi
Dated:-

3-9
2022

Executive Engineer
Mandi Division No.II
HP.PWD Mandi

CERTIFICATE

CERTIFIED THAT THE TENDER AS CALLED VIDE THIS OFFICE
LETTER NO. PW/MDII/CB/NIT/OFF LINE/21-¹¹⁴⁷²⁻⁸³ DATED ^{31/9/2022} THEREIN
THE URGENCY OF WORK I.E. C/O R/WALLS B/WALLS, WHICH HAS BEEN
DAMAGED BADLY DUE TO HEAVY RAIN WHICH IS ESSENTIAL REQUIRED TO
RESTORE THE DAMAGES PORTION TO MAINTAIN THE ROAD SURFACE FOR
PLYING OF SMOOTH VEHICULAR TRAFFIC & MAINTENANCE OF RESIDENTIAL &
NON RESIDENTIAL BUILDINGS OF OTHER DEPTT.

 Executive Engineer
Mandi Division No. II
HP. PWD Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Kun to Kot road Km. 0/00 to 2/00.
(SH:- C/O PCC B/wall at RD. 0/430 to 0/438).

Estimated Cost Rs. 1,42,748/-
Earnest Money Rs. 2900/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	13.81	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	2,636.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	7.65	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	3,323.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	26.55	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	1,33,398.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	3,391.00
					Total	1,42,748.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Khalanoo to Mahan road Km. 0/00 to 2/750.
(SH:- C/O PCC Retaining walls at RD. 2/330 to 2/345).

Estimated Cost Rs. 3,62,932/-
 Earnest Money Rs. 7300/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	35.55	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	15,441.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	60.38	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	3,13,082.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	24.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	8,412.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	17.15	1515.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	25,997.00
					Total	3,62,932.00

Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Roda Nallah Karkoh Arthi road Km. 0/00 to 12/300.
(SH:- C/O PCC Retaining walls at RD. 9/880 to 9/890).

Estimated Cost Rs. 4,98,654/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	29.95	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	13,009.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	87.00	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	4,51,112.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	9.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	3,155.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	20.70	1515.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	31,378.00
					Total	4,98,654.00


Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

% age rate of SCHEDULE OF QUANTITY

Name of work: **RRD on Santhapatan-Bharol-Bangora-Hard Ropri Kalg, Traimbahi Basahi Drubal, Chauranj, Banwar, Kun-Ka-Tar**
Mandhokar Bhargaoon Kotli road Km. 70/600 to 85/00. (SH:- C/O PCC R/wall at Rd 83/259 to 83/268)

Estimated Cost Rs. 4,64,488/-
Earnest Money Rs. 10,000/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earthwork excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	31.59	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	13,721.00
2	Providing and laying concrete for plain concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	79.20	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	4,10,667.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	28.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	9,814.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	19.98	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	30,286.00
					Total	4,64,488.00

 Exclusive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age rate SCHEDULE OF QUANTITY

Name of work: RRD on Sandhapatan Bharol Bangora Hard Ropri Kalg, Trainbati Basahi Drubal, Chauranj, Banwar, Kun-Ka-Tar
Mandhokar Bhargaon Kotli road Km. 70/600 to 85/00. (SH: C/O PCC R/wall at Rd 75/592 to 75/604)

Estimated Cost Rs. 4,92,958/-
Earnest Money Rs : 9900/-
Time : One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications. Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	39.20	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	17,027.00
2	Providing and laying concrete for plain concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm. Forty millimetre nominal size) in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	84.00	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	4,35,557.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	28.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	9,814.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	20.16	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	30,560.00
					Total	4,92,958.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

% age rate of SCHEDULE OF QUANTITY

Estimate of work on Santhapattan Bharol Bangora Hard Ropri Kalg, Traimbali Basahi Drubal, Chauranj, Banwar, Kun-Ka-Tar
Mandhokar Bhargaoon Kotli road Km. 70/600 to 85/00. (SH:- C/O PCC R/wall at Rd 75/553 to 75/561)

Estimated Cost Rs. 4,86,686/-
Earnest Money Rs : 9800/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2 Earth work in excavation in all kinds, of soil for structure as per drawing and technical specifications: Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3 29.96	4 434.35	5 Rupees Four Hundred Thirty Four and Paise Thirty Five Only	6 Per Cubic Metre	7 13,013.00
2	Providing and laying concrete for plain concrete 1:5:10 (one cement : five sand : ten graded stone/aggregate 40mm) (Forty millimetre nominal size) in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	83.80	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	4,34,520.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	24.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	8,412.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	20.28	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	30,741.00
					Total	4,86,686.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Name of work :- R.R.D. on Chail Gohar Pandoh road Km. 24/00 to 29/600.
(SH:- C/O R/wall at RD. 27/825 to 27/837).

Estimated Cost Rs. 4,98,469/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	18.60	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	3,551.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	21.60	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	9,382.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	91.67	5024.40	Rupees Five Thousand Four and Paise Forty Only	Per Cubic Metre	4,60,587.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	14.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	4,747.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.06	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	20,202.00
					Total	4,98,469.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Chail Gohar Pandoh road Km. 24/00 to 29/600.

(SH:- C/O R/wall at RD. 27/535 to 27/545).

Estimated Cost Rs. 3,71,413/-
Earnest Money Rs. 7500/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	21.10	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	4,028.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	19.75	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	8,578.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	66.70	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	3,35,127.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	15.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	5,086.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	11.10	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	18,594.00
					Total	3,71,413.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Chail Gohar Pandoh road Km. 24/00 to 29/600.
(SH:- C/O R/wall at RD. 25/837 to 25/849).

Estimated Cost Rs. 4,97,598/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	21.00	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	4,009.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	22.50	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	9,773.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	90.72	5024.40	Rupees Five Thousand Four and Paise Forty Only	Per Cubic Metre	4,55,814.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	15.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	5,086.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	13.68	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	22,916.00
					Total	4,97,598.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Bari Dhanyari road Km. 0/00 to 5/300.
(SH:- C/O R/wall at RD. 0/500 to 0/514).

Estimated Cost Rs. 4,87,169/-
Earnest Money Rs. 9800/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	45.78	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	19,885.00
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	30.07	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	1,52,819.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	56.14	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	2,82,070.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	25.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	8,476.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.66	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	16,182.00
6	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including hauling/carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals as per direction of Engineer-in-charge.	19.88	389.20	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	7,737.00
					Total	4,87,169.00


Responsible Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Bari Dhanyari road Km. 0/00 to 5/300.
(SH:- C/O R/wall at RD. 1/157 to 1/172).

Estimated Cost Rs. 4,99,937/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	23.85	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	4,553.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.40	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	6,689.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	45.42	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	2,30,829.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	45.90	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	2,30,620.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	27.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	9,154.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.80	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	18,092.00
					Total	4,99,937.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Talyahar Pairi road Km. 0/00 to 5/100.
(SH:- C/O B/wall at RD. 2/120 to 2/135).

Estimated Cost Rs. 2,68,187/-
Earnest Money Rs. 5400/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words		Unit	Amount
				3	4		
1	2	3	4	5	6	7	
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	33.75	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	6,443.00	
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	14.40	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	6,255.00	
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	49.50	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	2,48,708.00	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	20.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	6,781.00	
					Total		2,68,187.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Talyahar Pairi road Km. 0/00 to 5/100.
(SH:- C/O R/wall at RD. 4/130 to 4/140).

Estimated Cost Rs. 2,85,294/-
Earnest Money Rs. 5800/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	12.30	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	2,348.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	12.60	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	5,473.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	50.80	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	2,55,240.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.20	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	12,061.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	30.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	10,172.00
					Total	2,85,294.00


Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Page Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Ratti Pul to Alathu via Saini Mohri road Km. 0/00 to 6/500.
(SH:- C/O PCC R/wall at RD. 1/410 to 1/421.50).

Estimated Cost Rs. 2,16,413/-
Earnest Money Rs. 4400/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	6.56	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	1,252.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	9.55	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	4,148.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	37.59	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	1,88,867.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.97	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	15,026.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	21.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	7,120.00
					Total	2,16,413.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Name of work :- A/R & M/O on Ganapati Kun-Ka-Tar road Km. 0/00 to 21/500.
(SH:- C/O R/wall for protection of road at RD. 1/070 to 1/081).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 2,88,096/-
 Earnest Money Rs. 5800/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	3 15.07	4 190.90	5 Rupees One Hundred Ninety and Paise Ninety Only	6 Per Cubic Metre	7 2,877.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	20.35	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	8,839.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	16.94	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	86,091.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	33.66	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	1,69,121.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	11.22	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	18,795.00
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	7.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	2,373.00
					Total	2,88,096.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Sain to Sandoh road Km. 0/00 to 14/400.
(SH:- C/O R/wall at RD. 7/620 to 7/630).

Estimated Cost Rs. 4,92,578/-
 Earnest Money Rs. 9900/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	26.20	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	5,002.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.30	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	6,646.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	40.80	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	2,07,350.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	50.80	5024.40	Rupees Five Thousand Four and Paise Forty Only	Per Cubic Metre	2,55,240.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	20.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	6,781.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	6.90	1675.15	Rupees Four Hundred One and Paise Thirty Only	Per Cubic Metre	11,559.00
					Total	4,92,578.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- RRD on Sain to Sandoh road Km. 0/00 to 14/400.
(SH:- C/O R/wall at RD. 0/280 to 0/294)

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,79,156/-
Earnest Money Rs. 9600/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	22.26	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	4,249.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.40	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	6,689.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	44.52	5082.1	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	226,255.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	42.84	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	215,245.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (N) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	29.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Per Cubic Metre	9,832.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.08	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	16,886.00
Total						479,156.00


Executive Engineer,
Mand Division No-II,
HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Sain to Sandoh road Km. 0/00 to 14/400
(SH:- C/O B/wall at RD 0/280 to 0/305)

Estimated Cost Rs. 2,46,596/-
Earnest Money Rs.5000/-
Time:- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	20.25	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	3,866.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	13.05	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	5,668.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	45.90	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	230,620.00
4	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (hundred millimetre) dia AC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	19.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	6,442.00
					Total	246,596.00

 Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Sain to Sandoh road Km. 0/00 to 14/400.
(SH:- C/O R/wall at RD. 12/800 to 12/808)

Estimated Cost Rs. 3,37,569/-
Earnest Money Rs. 6800/-
Time :- One month.

Sr. No.	Description of items	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	318.00	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	3,436.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	11.36	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	4,934.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	30.24	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	153,683.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	32.08	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	161,183.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (N) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	15.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Per Cubic Metre	5,086.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	5.52	1675.15	Rupees Four Hundred Eighty One and Paise Thirtv Only	Per Cubic Metre	9,247.00
					Total	337,569.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Khad Kalyana to Bhaled road Km. 0/00 to 6/00
(SH:- C/O R/wall at RD. 1/050 to 1/068)

Estimated Cost Rs. 4,98,858 /-
 Earnest Money Rs. 10,000 /-
 Time :- One month.

Description of items.						
1	2	Quantity	Rates	Words	Unit	Amount
			Figure			
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	22.14	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	4,227.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	22.68	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	9,851.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	89.60	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	450,186.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	38.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	12,884.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.96	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	21,710.00
Total						498,858.00

Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Khad Kalyana to Bhaled road Km. 0/00 to 6/00
(SH:- C/O R/wall at RD. 1/980 to 1/990)

Estimated Cost Rs. 4,93,595/-
Earnest Money Rs. 99,00/-
Time :- One month.

Sl. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	26.20	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	5,002.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.30	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	6,646.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 25mm (twenty five millimeter) nominal size including carriage of materials with in all leads, lifts and other incidentals.	40.80	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	207,350.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	50.80	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	255,240.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	23.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	7,798.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	6.90	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	11,559.00
					Total	493,595.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Khad Kalyana to Bhaled road Km. 0/00 to 6/00
(SH:- C/O R/wall at RD. 1/970 to 1/980)

Estimated Cost Rs. 4,93,595/-
Earnest Money Rs. 99,00/-
Time :- One month.

	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	26.20	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	5,002.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.30	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	6,646.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 25mm (twenty five millimeter) nominal size including carriage of materials with in all leads, lifts and other incidentals.	40.80	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	207,350.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals	50.80	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	255,240.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	23.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	7,798.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	6.90	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	11,559.00
					Total	493,595.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Estimated Cost Rs. 2,35,997/-
Earnest Money Rs. 4800/-
Time :- One month.

Name of work :- RRD on Circular road Twambra Nallah to Panjethi road Km. 0/00 to 2/00.
(SH:- C/O Retaining wall at RD. 1/063 to 1/072).

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	6.21	190.90	Rupees One Hundred Ninety and Paise Ninety Only	Per Cubic Metre	1,185.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	12.24	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	5,316.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	39.60	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	1,98,966.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	17.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	5,764.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.26	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	17,187.00
6	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including hauling/carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	62.9	120.50	Rupees One Hundred Twenty and Paise Fifty Only	Per Cubic Metre	7,579.00
					Total	2,35,997.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Majhwar Moviseri via Sari Rakhoon road Km. 0/00 to 6/800.
(SH:- C/O R/wall at RD. 3/445 to 3/460).

Estimated Cost Rs. 2,66,171/-
Earnest Money Rs. 5400/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words	Unit	Amount
1	Excavation in Hilly Area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with a lift upto any lead as per Technical Specification clause 1603.2 including carriage of materials with in all leads, lifts and other incidentals.	24.90	303.30	Rupees Three Hundred Three and Paise Thirty Only	Per Cubic Metre	7,552.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	45.90	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	2,30,620.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	27.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	9,154.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	11.25	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	18,845.00
					Total	2,66,171.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.