

OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811

E-MAIL:- ee-sol-hp@nic.com

No.PW-SD/CB-Tender/-22-23-8250 - 60

Dated: 31/08/2022

To

The Executive Engineer (IT Cell), Nigam Vihar, Nirman Bhawan, HPPWD, Shimla-2, Email ID:-cc-pwd-hp@nic.in

Subject: -

Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer, B&R Division, HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

- 1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
- 2. The Superintending Engineer, 3rd-HP.PWD, Solan.
- 3. The Drawing Branch & Accounts Branch of this office.
- 4. Notice Board.

Executive Engineer, B&R Division,

HP.PWD, Solan.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited on Form No.6 &8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	08.09.2022	Upto 4.00 P.M.
2	The last date sale of tender forms.	09.09.2022	Upto 4.00 P.M.
3	The date for receipt of tender forms.	09.09.2022	Upto 10.30 A.M.
4	The date of opening of tender	12.09.2022	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 12.09.2022 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive

Engineer reserves the right to reject the tender without assigning any reason. Sr. Name of work Estimated Earnest Time Cost of No Cost. (Rs.) Money Form (Rs) Construction of Kathlighat to Katoh road km 4,97,933/-10,000/-One Rs.350/-0/0 to 2/0 under MNP (SH: F/C to jeepable Month road CD work & Soling in km 0/0 to 2/0) (SW: Providing and laying local earth for backfilling behind retaining walls km 0/0 to 0/200) 2,90,122/-Construction of Kaithlighat Basha road km 0/0 5,850/-One Rs.350/to 6/660 under MNP (SW: C/o PCC retaining Month wall at RD 2/100 to 2/115) Annual repair and maintenance of Kiari 4,92,276/-9,900/-Fifteen Rs.350/-Banglow Malga road km 0/0 to 7/0 (SH: Days Clearance of side drain, white washing of parapets, Drains and dressing of berms from km 0/0 to 7/0)

TERMS & CONDITIONS:-

- The tender form will not be issued to those contractors whose performance has been found unsatisfactory
- The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms. Application without earnest money will not be entertained.
- 3. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

SCHEDULE OF QUANTITY

				Total:-	
		Per Cubic Meter	1841.470 m3	Excavating, supplying and filling of local earth (including royalty) by mechanical 1841.470 m3 Per transport upto all lead and lift including ramming and watering of the earth in layers not exceeding 20 cm in trenches. & behind the R/wall etc.)	
oling in km 0/0 to 2/0	00	to jeepable i	NP (SH:- F/C 0/0 to 0/200)	Name of Work :-Constrution of Kathlighat to Katoh road km 0/0 to 2/0 under MNP (SH:- F/C to jeepable road CD work & (SW:- Providing and laying local earth for backfilling behind retaining walls km 0/0 to 0/200)	
One Montl	Time limit : -				
10000.0	Earnest Money: -				
497933.0	Estimated Cost: -			Job No. :-	1
Rs.	Figures Words				Z (
AMOUNT	RATEIn	Unit	Qty.	Description of work	2

Total in Words

T/S No. 163 for the 2022-23.
Sr. No. 197 for the year 2022-23.

Beck Davision, HP.PWD. Solan.

SCHEDULE OF OUANTITY

N N	Maria di wal k	Oty.	Unit	RAT	RATE In	AMOUNT
1	Tob No :			Figures Words	ords	Rs.
				Es	Estimated Cost: -	492276.00
				Ea	Earnest Money: -	000006
	Name of Work Annual panaland maintain			Ξ	Fime limit: -	Fifteen days.
	parapets, Drains and dressing of berms from km 0/0 to 7/0)	n 0/0 to 7/0	(SH:- Cl	earance of side	drain, white w	ashing of
	ance of unlined drain to ortion or dispose surplus tor, including all leads,	5960.000 m	Per running meter.	-		-
7	g of the same to suitable lirection of Engineer-in-	7707.500 m2 Per Squ	Per Square		8	
m	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 (One nine one five) and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	1028.000 m2 Per Squa	Per Square Meter			
ਜ	Maintenance of Earhen shoulder by Stripping excess soil from the shoulder surface and dressing it in entire length to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903, and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	7101.000 m2 Per Squ Met	Per Square Meter			
	Total:-					

T/S No. 170 for the 2022-23, Sr. No. 196 for the year 2022-23. Hyseuthyc Engineer B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

One Month	Time Limit: -				
5850.00	Earnest Money: -				1001 000
290122.00	Estimated Cost: -				Joh No.
Rs.	Figures Words		77.73	1	No. or manufacture or or
AMOUNT	RATE In	Unit	Qty.	ork	NI Description of w
			COMMUNICATION CO.		

Name of work: - Construction of Kaithlighat Basha Road Km. 0/0 to 6/660 under MNP (SW:- C/O PCC Retaining wall at RD, 2/100 to 2/115)

12	
Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five milimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation spaints soil, and possesses and sparage to thill side rock. Stacking is prohibeted). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and horror, and backfilling in trenches with excavated suitable, material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.
62.250 m3	26.850 m3
Per Cubic Meter	Meter.

SCHEDULE OF QUANTITY

4 Bac bre con (on lab		Zo.	SI Des
Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight), including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 (six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.		Description of work
9.750 m3	28.000 No.		Qty. Unit RAT
Per cubic meter	Each.	28,000 No. Each.	Unit
		Figures Word	RATE In
		Figures Words	n
		Rs.	AMOUNT

Total in Words

T/S No. 176 for the 2022-23 Sr. No. 205 for the year 2022-23.

EKSEKNING ENGINEET.
Solandaktijasishi, HP: NWD: Solan.
SOLAN

Exigency Certificate"

It is certified that the tenders which were invited vide this Office NIQ NO.PW.SD.CB.Tender/2022-23-8250-60 dated: 31 August, 2022 are of emergent nature of work & in public interest.

Dated:-31th August, 2022 Place:-Solan.

> Executive Engineer, Solan B & R Division, H.P.P.W.D, Solan.