

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2022-23

9346

Dated:- 07-9-2022

To,


The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 19.09.2022 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above


Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

**Himachal Pradesh
Public Works Department
"Notice Inviting Tender"**

Sealed item rate tender are hereby invited in form No. 6&7 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968.The important dates of tender are as under:-

The last date and time of receipt of application for tender form 19.09.2022 up to 4.00 P.M.

The last date for sale of tender is up to 20.09.2022 at 4.00PM.

The tender shall be received up to 11:00 AM on 21.09.2022 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 21.09.2022. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimat ed cost.	Earnest Money.	Cost of form.	Time allowed.
1.	Restoration of Rain Damages on Bah to Gahar Road Km. 0/0 to 8/720 (SH:- Construction of R/wall in PCC 1:4:8 at RD 1/560 to 1/570)	351611	7100	350	One Month
2.	Restoration of Rain Damages on Baldwara to Kashmali Road Km. 0/0 to 14/0 (SH:- Construction of PCC R/wall in PCC 1:5:10 at RD 0/025 to 0/040)	349309	7000	350	One Month
3.	Construction of Link Road Triyada to Silari (SH:- Hiring of Excavator cum loader for removal of slips dressing of berms etc.) Depositwork	74250	1500	350	One Month

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
8. The tender shall be awarded to the lowest bidder without any negotiation if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The earnest money shall be deposited duly pledged in favour of Executive Engineer B& R Division HPPWD Sarkaghat & Cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.

10. All the required documents should be submitted with the application others wise single application may be rejected.
11. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

Dated: 07-9-2022

No. PW-SKT-CB-Tender/2022-23

9339-45

1. The Engineer - in- Chief HPPWD Nirman Bhawan Shimla for information please.
2. The Chief Engineer Hamirpur Zone HP.PWD . Hamirpur for information please.
3. The Superintending Engineer Dharampur Circle, HP.PWD. Dharampur for information please.
4. Block Development officer Sarkaghat for information please.
5. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
6. Copy to Drawing Branch of this office for information.
7. Notice Board.


Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

Schedule of Quantity

Name of work:- Resoration of rain Damages Bah to Gahar road km 0/0 to 8/720 (SH: -Construction of R/wall in PCC 1:4:8 at RD 1/560 to 1/570)

Estimated Cost:- Rs.3,51,611/-
Earnest money:- Rs. 7,100/-
Time allowed:- One month.


Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m. (One point five metre) .All kinds of soil including all leads and lifts and as per the direction of Engineer- in-Charge.	20.50			Per cubic metre	
2	Centering and shuttering including strutting, propping etcetra and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc including all leads and lifts and as per the direction of Engineer- in-Charge.	86.57			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement : four coarse sand) : eight graded stone aggregate 40 mm (Forty millimetre)nominal size including all leads and lifts and as per the direction of Engineer- in-Charge.	59.34			Per Square metre	
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC(poly vinayal chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	19.00			Each	
5	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	18.00			Per cubic metre	
					Total	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of works:- R/R Damages on Baldwara to Kashmiri Road km 0/0 to 14/00 (Sh:-Construction of PCC R/wall in 1:5:10 at RD 0/025to 0/040).

RU/UD2510/01040).						Construction of PCC R/Wall in 1:5:10 at		Estimated cost :-		Rs. 3,49,309. 00	
								Earnest Money:-		Rs. 7,000.00	
								Time Limit:-		One month	
Description of item/Sub Head						Quantity	Rates		Unit	Amount	
							In Figure	In words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm(ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.					27.98			Per cubic metre		
2	Centering and shuttering including strutting,propping etcetra And removal of form work for foundations, footings,bases for columns as per drawing and HP,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.					119.90			Per square metre		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:5:10 (one cement :five fine sand :ten crushed graded crushed stone aggregate) 40 mm (forty millimetre) nominal size as per drawing and HP,PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.					62.22			Per cubic metre		
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.					36.00			Each		
5	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.					17.63			Per cubic metre		
									Total:-		


Executive Engineer
B & R Division HPPWD
Sarkaghat

SCHEDULE OF QUANTITY

Name of Work:-C/O Link road Triyada to Silari (SH:-Hiring of excavator cum loader for removal of slips,dressing of berms etc). (Depo site work)		Estimated cost :-		Rs. 74250/-	
		Earnest Money:-		Rs. 1500 /-	
		Time Limit:-			
Sr.No	Description of item/Sub Head	Rates		Unit	Amount
		In Figure	In words		
1	Hiring of Excavator cum loader for cutting work filling and deposal etcetra with a minimum capacity of 30 (thirty) cubic metre per hour.Including pay of operators, P.O.L charges,maintenance or any minor or major accidents,and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as perthe PWD specification and the direction of Engineer- in- Charge .	55.00		P/Hour	

Executive Engineer
B & R Division HPPWD
Sarkaghat