

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23-

12430-32 Dated:- 26/9/22

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 06.10.2022 up to 11:00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 04.10.2022 upto 01:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Dharmehar Tarswan Dragar Garhgaon road Km 0/0 to 5/250. (SH:- Construction of P.C.C. Breast wall at R.D. 2/740 to 2/752)	3,00,553/-	6,000/-	350/-	One month
2	Restoration of rain damages on Padhar Balh road Km 0/00 to 18/500. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 0/00 to 08/500)	2,50,000/-	5,000/-	350/-	Two months
3	Restoration of rain damages on Padhar Nahuli road Km 0/00 to 14/500. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 0/00 to 14/500)	4,50,000/-	9,000/-	350/-	Three months
4	Restoration of rain damages on Baragaon Bah Padwahan road Km 11/0 to 26/945. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 22/0 to 26/945)	3,80,000/-	7,600/-	350/-	Three months
5	Restoration of rain damages on Kufri Kheel Damela road Km 0/00 to 8/100. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 0/00 to 8/100)	3,50,000/-	7,000/-	350/-	Three months
6	Restoration of rain damages on Drang Basahi road Km 0/00 to 22/00. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 0/00 to 22/00)	4,00,000/-	8,000/-	350/-	Three months
7	Restoration of rain damages on Baragaon Bah Padwahan road Km 11/0 to 26/945. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 11/0 to 16/00)	4,00,000/-	8,000/-	350/-	Three months

8	Restoration of rain damages on Baragaon Bah Padwahan road Km 11/0 to 26/945. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 16/0 to 22/00)	4,60,000/-	9,200/-	350/-	Three months
9	Restoration of rain damages. on Jhanad Lagdhar road Km 0/00 to 5/270. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 0/00 to 5/270)	2,50,000/-	5,000/-	350/-	Two months
10	Restoration of rain damages on Kufri Kheel Lohra road Km 0/00 to 7/00. (SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc. in Km 0/00 to 7/00)	2,40,000/-	4,800/-	350/-	Two months

1. **Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)

Schedule of Quantity

Estimated Cost:- Rs. 300553.00
 Earnest Money:- Rs. 6000.00
 Time:- One month

Name of work:- Construction of Dharmehar Tarswan Dragar Garhgaon road Km. 0/0 to 5/250.
 Sub Head:- Construction of P.C.C. Breast wall at R.D. 2/740 to 2/752.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	23.40 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	44.31 Cum.			Per cubic metre	
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	10.00 Nos.			Each	
	Total:-					

Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar.

SCHEDULE OF QUANTITY

Estimated Cost :- 250000.00
 Earnest Money :- 5000.00
 Time :- Two Months

Name of Work :- Restoration of rain damages on Padhar Balh road KM 0/00 to 18/500

(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 0/00 to 18/500)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	250.00			Per Hour	
Total :-						

Executive Engineer

Mandi Division no. 1
 HPPWD. at Padhar

SCHEDULE OF QUANTITY

Estimated Cost :- 450000.00
 Earnest Money :- 9000.00
 Time :- Three Months

Name of Work :- Restoration of rain damages on Padhar Nahuli road KM 0/00 to 14/500
(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 0/00 to 14/500)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	450.00			Per Hour	
Total :-						


 Executive Engineer
 Mandi Division no. 1
 HPPWD. at Padhar


SCHEDULE OF QUANTITY

Estimated Cost :- 380000.00
 Earnest Money :- 7600.00
 Time :- Three Month

Name of Work :- Restoration of rain damages on Baragaon Bah Padwahan road km 11/0 to 26/945.

(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 22/0 to 26/945)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	380.00			Per Hour	
Total :-						


 Executive Engineer
 Mandi Division no. 1
 HPPWD. at Padhar

SCHEDULE OF QUANTITY

Estimated Cost :- 350000.00
Earnest Money :- 7000.00
Time :- Three Month

Name of Work :- Restoration of rain damages on Kufri Kheel Damela road KM 0/00 to 8/100
(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 0/00 to 8/100)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	350.00			Per Hour	
Total :-						

Executive Engineer
Mandi Division no. 1
BPPWD. at Padhar

SCHEDULE OF QUANTITY

Estimated Cost :- 400000.00
 Earnest Money :- 8000.00
 Time :- Three Month

Name of Work :- Restoration of rain damages on Drang Basahi road KM 0/00 to 22/00
(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 0/00 to 22/00)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	400.00			Per Hour	
Total :-						

Executive Engineer
 Mandi Division no. 1
 HPPWD. at Padhar

SCHEDULE OF QUANTITY

Estimated Cost :- 400000.00

Earnest Money :- 8000.00

Time :- Three Month

Name of Work :- Restoration of rain damages on Baragaon Bah Padwahan road km 11/0 to 26/945.

(SH):- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 11/0 to 16/0)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	400.00			Per Hour	
	Total :-					


Executive Engineer
Mandi Division no. 1
HPPWD, at Padhar

SCHEDULE OF QUANTITY

Estimated Cost :- 460000.00
 Earnest Money :- 9200.00
 Time :- Three Month

Name of Work :- Restoration of rain damages on Baragaon Bah Padwahan road km 11/0 to 26/945.

(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 16/0 to 22/0)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	460.00			Per Hour	
	Total :-					


 Executive Engineer
 Mandi Division no. 1
 HPPWD. at Padhar

SCHEDULE OF QUANTITY

Estimated Cost :- 250000.00
Earnest Money :- 5000.00
Time:- Two Months

Name of Work :- Restoration of rain damages on Jhanad Lagdhar road KM 0/00 to 5/270
(SH:- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 0/00 to 5/270)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	250.00			Per Hour	
Total :-						

Executive Engineer
Mandi Division no. 1
HPPWD. at Padhar


SCHEDULE OF QUANTITY

Estimated Cost :- 240000.00
 Earnest Money :- 4800.00
 Time :- Two Month

Name of Work :- Restoration of rain damages on Kufri Kheel Lohra road KM 0/00 to 7/00

(SH):- Hiring of Hydraulic excavator cum loader for cutting in earth work, removal of slips, dressing of berms, clearing of drains and catch pit etc in km 0/00 to 7/00)

S.N.	Description of Items	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic excavator cum loader for cutting in earth work/ removal of slips/clearance of drain and catch pit/ dressing of berms in all kind of soil and trimming of side slopes and disposing of excavated earth upto any lead from various sites of work within all leads and lifts to the entire satisfaction of the engineer in charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility the contractor. The repair and spares including watch and ward of machines shall also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	240.00			Per Hour	
	Total :-					


 Executive Engineer
 Mandi Division no. 1
 HPPWD. at Padhar