

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.PW-GHR-CB-NIT/E-Tendering / 2022-23-

8502-11

Dated:-

6/9/22

To

✓ The Executive Engineer, (IT Cell)
Nirman Bhawan,
Nigam Vihar, Shimla.

Subject: -


Publishing of Tender Notice.

Sir,

Enclosed please find herewith the tender notice for uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of H.P. letter No.(PBW) BA(3)/2020 dated 16th July, 2021 as the work mentioned in the Tender Notice are urgent in nature and in public interest.

DA:- As above.

Yours faithfully,


Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

Copy along with copies of Notice forwarded for information:-

1. The Engineer-in-Chief HP.PWD.Shimla.
2. The Chief Engineers (MZ) HP.PWD Mandi.
3. The Superintending Engineer, 1st.Circle, HP.PWD Mandi.
4. The computer cell O/O Executive Engineer (IT Cell) Nirman Bhawan Nigam Vihar Shimla-2 for uploading the NIT on departmental site.
5. The Assistant Engineers working under the division.
6. Notice Board.
7. H.D.M./A.B.in this office.

✓
Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

**Himachal Pradesh
Public works Department**

Notice inviting Tender

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **15-09-2022** up to 11.00 A.M. and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T./ tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **14-09-2022**. The applications for issue of tender forms will be received up to 2.00 P.M. on **13-09-2022**

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D.Rs in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tenders shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr.No	Name of road/work	Estimated Cost	Earnest Money	Cost of Tender Form	Time Limit	Class of contractor
1	A/R & M/O on Kot Devidarh road km 0/000 to 24/000 (SH: Providing and Laying G-III for correction layer and repair of pot holes in km 9/500 to 19/000)	4,98,068/-	10,000/-	350/-	Two Months	D & C
2	A/R & M/O on Kot Devidarh road km 0/000 to 22/500 (SH: Providing and Laying G-III for correction layer and repair of pot holes in km 0/0 to 9/500 Job No. III)	4,99,253/-	10,000/-	350/-	Two Months	D & C
3	Construction of Padhru to Kainchdi road (Portion Masyana to Kainchadi km 0/0 to 1/500 (SH: 5/7 mtr. wide Formation cutting in km 0/660 to 0/810) under OTMNP	4,84,138/-	10,000/-	350/-	Three Months	D & C
4	Construction of Padhru to Kainchdi road (Portion Masyana to Kainchadi km 0/0 to 1/500 (SH: 5/7 mtr. wide Formation cutting in km 0/810 to 1/030) under OTMNP	4,80,580/-	10,000/-	350/-	Three Months	D & C
5	RRD on link road to Sainj km 0/00 to 2/00 (SH: C/o PCC R/wall at RD. 1/165 to 1/188) Under OTMNP	1,36,585/-	3000/-	350/-	Three Months	D & C

6	A/R & M/O on Gohar Kandha road km 0/0 to 16/00 (Portion in km 0/00 to 2/600) SH: construction of Breast wall at RD 1/655 to 1/665)	1,74,308/-	3500/-	350/-	Two Months	D & C
7	Construction of Sainj Pangliur road km 0/000 to 6/000 (SH: Formation cutting 5/7 mtr wide in km 1/955 to 2/250) Under SCSP	3,87,921/-	8000/-	350/-	Two Months	D & C
8	Construction of Behri Bridge to Behri village road km 0/00 to 0/500 (SH: Formation cutting at RD 0/00 to 0/495) OTMNP	4,28,986/-	9000/-	350/-	Three Months	D & C
9	A/R & M/O Chail Gohar Pandoh road km 0/0 to 24/0 (SH: Providing and Laying G-III and Repair of Pot Holes in km 13/500 to 16/00)	4,99,715/-	10000/-	350/-	Two Months	D & C
10	A/R & M/O Chail Gohar Pandoh road km 0/0 to 24/0 (SH: Providing and Laying G-III and Repair of Pot Holes in km 12/00 to 13/500)	4,99,910/-	10,000/-	350/-	Two Months	D & C
11	A/R & M/O Bassa kuther and Chail Gohar Pandoh road (SH: Providing and Laying G-III for correction layer and repair of pot Holes in Bassa kuther road 0/00 to 1/00 and Chail Gohar Pandoh road km 11/00 to 12/00)	4,99,225/-	10000/-	350/-	Two Months	D & C
12	Construction of Tunna Bhurla via Dari, Ger, Kunasot rod km 0/00 to 6/050 9SH: Formation cutting 5/7 mtr. wide Jeepable to Motorable standard road at km 0/765 to 0/835, 1/090 to 1/175, 1/645 to 1/750, 1/825 to 1/900 and 2/960 to 2/985) SCSP	4,34,562/-	9000/-	350/-	Three Months	D & C
13	RRD on Kot Devidarh road km 0/00 to 22/500 (SH: C/O Retaining wall at RD 12/725 to 12/741)	4,17,394/-	8500/-	350/-	Three Months	D & C
14	Improvement of Black spot on Shimla Mandi Tattapani road km 0/00 to 185/0 (Portion Rohangaloo to Baggi) (SH: Improvement of Narrow sharp curves in km 156/145 to 156/180)	1,17,997/-	2400/-	350/-	Two Months	D & C
15	RRD Chail Gohar Pandoh road km 0/00 to 24/00 (SH: C/O PCC R/wall at RD 22/320 to 22/330)	1,93,808/-	4000/-	350/-	One Month	D & C
16	RRD on Shimla Mandi via Tatapani road km 115/00 to 181/400 (SH: C/O Stone Masonry R/wall at RD 119/705 to 119/720)	2,22,516/-	4500/-	350/-	Two Months	D & C

17	RRD Shimla Mandi via Tatapani road km 115/00 to 138/00 (SH: C/O R/wall at RD 116/700 to 116/712)	3,88,073/-	8000/-	350	Three Months	D & C
18	RRD Shimla Mandi via Tatapani road km 115/00 to 138/00 (SH: C/O R/wall at RD 118/870 to 118/870)	1,77,760/-	3600/-	350/-	Two Months	D & C
19	A/R & M/O Maloh to Kateru road km 6/00 to 14/250 (SH: Retaining wall at RD 11/660 to 11/675)	3,38,054/-	7000/-	350/-	Three Months	D & C
20	C/o Link road from Maloh Kateru road near Chalaila village km 0/00 to 0/200 (SH: Providing and Laying stone soling, CC Pavement 1:2:4 at RD 0/00 to 0/48 and C/O R/wall at RD 0/32 to 0/45) under MMGSY	3,19,087/-	7000/-	350/-	Three Months	D & C
21	Construction of Mahadev to BBMB colony road km 0/00 to 1/000 (SH: C/O retaining wall at RD 0/839 to 0/850 and 0/874 to 0/880) Under OTMNP	3,68,603/-	7400/-	350/-	Two Months	D & C
22	Construction of Jathera katal Tamroh Chountra upper Pali road km 0/0 to 2/0 (SH: Providing and laying kharanja stone soling and cement pavement at RD 1/943.90 to 2/0) Under OTMNP	1,55,704/-	3500/-	350/-	Three Months	D&C

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors shall show their registration / renewal of enlistment before issue of tender form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. Tenders Forms will be issued to those contractors who have sufficient experience in execution of similar types of works.
5. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
6. Contractors will have to submit appropriate **Earnest Money** in the shape of **F.D.R. GST No , ITR for the year 2021-22 and Pan No.** with the applications for getting issued the tender forms, failing which, the forms would not be issued.
7. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% and below 30% of estimated cost will be summarily rejected.
8. The contractor can apply only for one work at a time.

Executive Engineer,
Gohar Division,
HP.PWD,Gohar.

SCHEDULE OF QUANTITY

Estimate Cost: Rs.498068- only
Earnest Money: Rs 10,000/- only
Time : Two months

Name of Work:- A/R & M/O on Kot Devidarh road KM 0/000 to 24/000 (SH:- Providing and Laying G-III for correction layer and repair of pot holes in KM 9/500 to 19/000)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, Laying, spreading and compacting stone aggregates of specific sizes 53 to 22.4 mm (fifty three to twenty two point four millimetre) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical specification Clause 405 (By Manual means) including all leads, lifts of material and other incidentals	1.62			Per Cubic metre	
2	Repairing to pot holes and removal of loose material trimming of sides, cleaning of surface by providing tack coat 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification clause 1904.2, 508 and 508.1as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1,299.09			Per Square metre	
Total:-						

(Signature)
Executive Engineer
Gohar Division (B&R)
HPPWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.499253 only
 Earnest Money: Rs 10,000/- only
 Time : Two months

Name of Work:- A/R & M/O on Kot Devidarh road KM 0/000 to 24/000 (SH:- Providing and Laying G-III for correction layer and repair of pot holes in KM 0/000 to 9/500)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing, Laying, spreading and compacting stone aggregates of specific sizes 53 to 22.4 mm (fifty three to twenty two point four millimetre) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical specification Clause 405 (By Manual means) including all leads, lifts of material and other incidentals	1.63			Per Cubic metre	-
2	Repairing to pot holes and removal of loose material trimming of sides, cleaning of surface by providing tack coat 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification clause 1904.2, 508 and 508.1as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1,302.14			Per Square metre	-
Total:-						-

(Signature)
 Executive Engineer
 Gohar Division (A&R)
 HPPWD Colaba

SCHEDULE OF QUANTITY

Estimate Cost :Rs.4,84,138/-only

Earnest Money: Rs. 10,000/- only

Time : Three Month

Name of work :- Construction of Padharu to Kainchdi road (Portion Masyana to Kainchadi km 0/00 to 1/500 (SH:- 5/7 mtr wide
Formation cutting in KM.0/660 to 0/810) Under OTMNP

S.N	Sub Head and item of work	Quantity	Rate in		Unit	Amount
			Figure	words		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settingout to the required line grades, side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in-charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways, embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or machanical means alongwith its leveling fine dressing and all labour, machinaries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 165.46 cubic metre @ Rs. 300.00 per cubic metre amount 49638/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of excution shall be the absolute responsibility of the contrator, which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge.	2635.05			Per cubic metre	
					Total	


 Executive Engineer
 Gohar Division (B&R)
 PWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost :Rs.4,80,580/-only

Earnest Money: Rs. 10,000/- only

Time : Three Month

Name of work :- Construction of Padharu to Kainchdi road (Portion Masyana to Kainchadi km 0/00 to 1/500 (SH:- 5/7 mtr wide Formation cutting in KM.0/810 to 1/030) Under OTMNP

S.N	Sub Head and item of work	Quantity	Rate in		Unit	Amount
			Figure	words		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settingout to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of trasportation including head load animal load or machanical means alongwith its leveling fine dressing and all labour, machinaries , materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 82.83cubic metre @ Rs. 300.00 per cubic metre amount 24849/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of excution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	2995.20			Per cubic metre	
					Total	

Executive Engineer
Gohar Division (B&R)
H.P.W.D Gohar

SCHEDULE OF QUANTITY

Name of work:- R.R damages on link road to Sainj Km. 0/00 to 2/00 (SH:- C/o PCC R/wall at RD. 1/165 to 1/188) under OTMNP				Estimated Cost:-1,36,585/-only. Earnest Money :- 3000/-only				
Description of item				Quantity	Time :- Three Months		Unit	Amount
					In figure	Rate In word		
S.No								
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.			13.80			Per Cubic Metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) curing complete with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge			31.05			Per cubic metre	
3	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge			4.78			Per Cubic Metre	
4	Providing weep hole in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge			20.00			Each	
							Total	


 Executive Engineer,
 Gohar Division (B&R)
 HP, PWD, Gohardiy

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O On Gohar Kandha road km. 0/0 to 16/00 (Portion in Km. 0/00 to 2/600) (SH:-
Construction of Breast wall at RD. 1/655 to 1/665)

Estimated Cost:- 1,74,308/-only.
Earnest Money :- 3500/-only.
Time :- Two Months

S. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	28.49			Per Cubic Metre	
2	Stone masonry in cement mortar for open foundation complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Random rubble masonry in cement mortar 1:5. (one cement : five sand) curing complete with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	20.80			Per cubic metre	
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	20.21			Per cubic metre	
Total					Total	


Executive Engineer,
Gohar Division (B&R)
HP, PWD, Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs.3,87,921/- only
Earnest Money: Rs 8000/- only
Time :- Two months

Name of Work:- Construction of Sainj Pangliur road KM 0/000 to 6/000 (SH:- Formation Cutting 5/7 meter wide in KM 1/955 to 2/250) *Under SESP*

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settingout to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or machanical means alongwith its leveling fine dressing and all labour, machinaries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 192.18 cubic mete @ Rs. 300/- per cubic metre amount 57655/-only shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of excution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge.	1921.83		Cum	per Cubic metre	
					Total	

[Signature]
Executive Engineer
B & R Division
H.P.P.W.D Gohar

218

8

SCHEDULE OF QUANTITY

Name of work:- Construction of Behari Bridge to Behari village road Km. 0/00 to 0/500 (Sft:- C/O Formation Cutting at RD 0/00 to 0/495) OTMNP		Estimated Cost :- 4,28,986/-only	
		Earnest Money :- 9,000/-only.	
		Time :- Three months	
S.No.	Description of item	Rate in	
		In figure	Words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settling out to the required line grades, side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in-charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways, embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or machanical means alongwith its leveling fine dressing and all labour, machinaries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 28.33 cubic metre @ Rs. 300.00 per cubic metre amount 8499/- only shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lifts and materials and as per direction of Engineer in charge .	2574.79	Per Cubic Metre
		Total	

Executive Engineer,
Gohar Division (B&R)
HP, PWD, Gohar

257

99

SCHEDULE OF QUANTITY

Estimated Cost:- 4,99,715/-only.

Earnest Money :- 10,000/-only.

Time :- Two Months

Name of work:- A/R & M/O Chail Gohar Pandoh road km 0/0 to 24/00 (SH:- Providing and

laying G-III and Repair of Pot Holes in km 13/500 to 16/00)

S.N o.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to 'water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405. By Manual Means. complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.03			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat Type-B specification clause 1904.2, 503 and 508.1 complete within all leads, lifts, carriage of material and other incidentals charges complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge. (Bitumen to be supplied by Department)	1266.94			Per square metre	
					Total	

(Signature)
 Executive Engineer
 Gohar Division (B&R)
 HPPWD Gohar

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chail Gohar Pandoh road km 0/0 to 24/00 (SH:- Providing and laying G-III and Repair of Pot Holes in km **12/000 to 13/500**)

Estimated Cost:- 4,99,910/-only.

Earnest Money :- 10,000/-only.

Time :- Two Months

S.N o.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405. By Manual Means, complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.46			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat Type-B specification clause 1904.2, 503 and 508.1 complete within all leads, lifts, carriage of material and other incidentals charges complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge. (Bitumen to be supplied by Department)	1257.81			Per square metre	
					Total	


 Executive Engineer
 Gohar Division (B&R)
 HPPWD Gohar

255

11

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Bassa Kuther and Chail Gohar Pandoh road (SH:- Providing and laying G-III for correction layer and Repair of Pot Holes in Bassa Kuther road 0/00 to 1/00 and Chail Gohar Pandoh road km 11/00 to 12/00)				Estimated Cost:- 4,99,225/-only. Earnest Money :- 10,000/-only. Time :- Two Months		
S N	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405. By Manual Means. complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.41			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat. 20mm (twenty millimetre) thick premix carpet and seal coat Type-B specification clause 1904.2. 503 and 508.1 complete within all leads, lifts, carriage of material and other incidentals charges complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge. (Bitumen to be supplied by Department)	1263.09			Per square metre	
					Total	


 Engineer
 Gohar Division (B&R)
 HPPWD Gohar

SCHEDULE OF QUANTITY

Name of work:- Construction of Tuna Bhurala via Dari, Ger, Kunsot road Km. 0/00 to 6/050 (SH:- Formation cutting 5/7 mtr. Wide Jeepable to Motorable standard road at Km. 0/765 to 0/835, 1/090 to 1/175, 1/645 to 1/750, 1/825 to 1/900 and 2/960 to 2/985)		Estimated Cost :- 4,34,562/-only.	
SCSP		Earnest Money :- 9,000/-only.	
		Time :- Three months	
S.No.	Description of item	Qty.	
		In figure	Words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settingout to the required line grades, side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways, embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or machanical means alongwith its leveling fine dressing and all labour, machinaries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 361.80 cubic metre @ Rs. 300.00 per cubic metre amount 1,8,540/- only shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	1973.49	Per Cubic Metre
		Total	



 Executive Engineer
 B & R Division
 H.P.W.D Gohar

SCHEDULE OF QUANTITY

Estimated Cost:- 4,17,394/-only.
Earnest Money :- 8500/-only.
Time :- Three Months.

Name of work:- R/R damages on Kot devidarh road Km. 0/00 to 22/500 (SH:- C/O Retaining wall at RD. 12/725 to 12/741)

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	45.04			Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 as per entire satisfaction and direction of Engineer-in-Charge. cement concrete 1:5:10 (One cement : five sand: ten aggregate)	48.00			Per Cubic Metre	
3	Stone masonry in cement mortar in foundation complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6. (one cement : six sand) curing complete with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	18.61			Per Cubic Metre	
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	39.21			Per cubic metre	
5	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	12.40			Per Cubic Metre	
					Total	


Executive Engineer,
Gohar Division(B&R)
HP, PWD, Gohar

SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Shimla Mandi Tattapani road Km 0/0 to 185/0 (Portion Rohangaloo to baggi) (SH:- Improvement of Narrow sharp curves in Km road in Km 156/145 to 156/180)

Estimate Cost: Rs. 117997/- only
Earnest Money: Rs 2400/- only
Time : Two month

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settingout to the required line grades, side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways, embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of trasportation including head load animal load or machanical means alongwith its leveling fine dressing and all labour, machinaries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 97 cubic mete @ Rs. 300/- per cubic metre amount 29148/-only shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of excution shall be the absolute responsibility of the contrator, which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge.	494.02			per Cubic metre	-
					Total	-

Executive Engineer
B&R Division Gohar
H&PWD Gohar

(15)

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Chail Gohar Pandoh road Km. 0/00 to 24/00 (SH:- C/O PCCR/wall at RD 22/320 to 22/330)					Estimated Cost:- 1,93,808/-only.	
					Earnest Money :- 4,000/-only	
					Time :- One Month.	
S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	10.30			Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 cement concrete 1:4:8 (One cement : four sand: eight aggregate 40 mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	13.20			Per Cubic Metre	
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 cement concrete 1:5:10 (One cement : five sand: ten aggregate 40 mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	31.50			Per Cubic Metre	
4	Providing weep hole in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	15.00			Per Each	
5	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	6.20			Per Cubic Metre	
					Total	


 Executive Engineer,
 Gohar Division (B&R)
 H.P.W.D., Gohar

224

Job No. 16

DRAFT SCHEDULE OF QUANTITY

of work: R/R Damages on Shimla Mandi via Tutapani road km. 115/00 to 181/400 (SH:- C/O stone masonry
all at RD 119/705 to 119/720)

Estimated Cost:- 2,22,516/- only.

Earnest Money :- 4500/- only.

Time :- Two Months.

No	Description of Item	Quantity
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of strumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	27.30
2	Stone masonry in cement mortar for open foundation complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Random rubble masonry in cement mortar 1:6. (one cement : five sand) curing complete with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	21.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	34.71
4	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	11.03

Executive Engineer
B & R Division
H.P.P.W.D Gohar

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Shimla Mandi via Tatapani road km. 115/00 to 138/00 (SH:- C/O R/wall at RD 116/709 to 116/712)

Estimated Cost:- 3,88,073/-only.

Earnest Money :- 8000/-only.

Time :- Three Months.

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	36.08			Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 as per entire satisfaction and direction of Engineer-in-Charge. cement concrete 1:4:8(One cement : four sand: eight aggregate)	32.64			Per Cubic Metre	
3	Stone masonry in cement mortar for open foundation complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6. (one cement : five sand) curing complete with in all leads and lifts and other incidentials complete and as per the entire satisfaction and direction of Engineer-in-Charge.	22.44			Per cubic metre	
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5, with in all leads and lifts and other incidentials complete and as per the entire satisfaction and direction of Engineer-in-Charge	35.64			Per cubic metre	
5	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentials complete and as per the entire satisfaction and direction of Engineer-in-Charge	18.96			Per cubic metre	
6	Providing weep hole in brick masonry/stone masonry/plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentials.	12.00			Per each	
Total						


 Executive Engineer,
 Gohar Division (B&R),
 HP, PWD Gohar.

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Shimla Mandi via Tatapani road km. 115/00 to 138/00 (SH:- C/O R/wall at RD 118/870 to 118/878)					Estimated Cost:- 1,77,760/-only.	
					Earnest Money :-3600/-only.	
					Time :- Two Months.	
S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposed up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	25.80			Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 as per entire satisfaction and direction of Engineer-in-Charge.cement concrete 1:6:12(One cement : six sand: twelve aggregate)	3.92			Per Cubic Metre	
3	Stone masonry in cement mortar for open foundation complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6, (one cement : five sand) curing complete with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	16.56			Per cubic metre	
4	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 as per entire satisfaction and direction of Engineer-in-Charge. cement concrete 1:4:8(One cement : four sand: eight aggregate)	1.60			Per Cubic Metre	
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	22.18			Per cubic metre	
6	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	5.36			Per cubic metre	
					Total	


Executive Engineer,
Gohar Division (B&R),
HP,PWD Gohar.

SCHEDULE OF QUANTITY

Estimate Cost: Rs 3,38,054/- only
Earnest Money: Rs 7000- only
Time : Three month

Name of Work :- A/R & M/O Maloh to Kateru road km 6/00 to 14/250 (SH:- C/O Retaining Wall at Rd 11/660 to 11/675)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead, lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads, lifts and carriage of materials and other incidentals, as per direction of Engineer in charge.	49.50			per Cubic metre	
2	Providing and laying cement concrete 1:6:12 (One cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 M10 within all leads, lifts and carriage of materials and other incidentals as per direction of Engineer in charge.	2.92			per Cubic metre	
3	Providing and laying cement concrete 1:5:10 (one cement : five sand ten, graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads, lifts and carriage of materials and other incidentals as per direction of Engineer in charge.	15.52			per Cubic metre	
4	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:6 (one cement : six sand) and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	5.00			Each	
5	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 within all leads, lifts and carriage of materials and other incidentals.	23.69			per Cubic metre	
6	Construction of dry rubble masonry for retaining walls, breast walls, revertment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 within all leads, lifts and carriage of materials and other incidentals as per direction of Engineer in charge.	42.90			per Cubic metre	
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	11.70			per Cubic metre	
					Total	


Executive Engineer
B & R Division
H.P.P.W.D Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 3,19,087/- only
 Earnest Money: Rs 7000- only
 Time : Three month

Name of Work :- C/o link road from Maloh Kateru road near Chalalla village km 0/00 to 0/200 (SH:- Providing and laying stone soling, CC Pavement 1:2:4 at RD 0/00 to 0/48 and C/O R/Wall at RD 0/32 to 0/45) Under MMGSY (2022-23)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation by mechanical means (Hydraulic excavation)/ manual means over areas (not exceeding 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift 1.5 m as directed by Engineer-in-charge.All kinds of soil. Engineer -in -Charge complete in all respect.	27.30			per Cubic metre	
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 M10 within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer in charge.	2.93			per Cubic metre	
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification, clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar : 1:6 (one cement : six sand) and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	11.43			per Cubic metre	
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer in charge.	24.66			per Cubic metre	
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	3.51			per Cubic metre	
6	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) with in all leads ,lifts and carriage of materials and other incidentals .as per direction of Engineer in charge.	24.20			per Cubic metre	
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803,1202 & 1203 P.C.C. grade M 20 (twenty millimetre) Nominal mix 1:2:4 (one cement : two sand : four graded crashed stone aggregate) within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge.	24.20			per Cubic metre	
					Total	


Engineer
B & R Division
H.P.P.W.D Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs 3,68,603/- only
 Earnest Money: Rs 7,400- only
 Time :- Two Months

Name of Work :- Construction of Mahadev to BBMB colony road KM 0/000 to 1/000 (SH:- C/O Retaining wall at RD 0/839 to 0/850 and 0/874 to 0/880) Under OTMNP

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	28.73			per Cubic metre	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other Incidentals . as per direction of Engineer -in -Charge complete in all respect.	90.90			per Cubic metre	
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	28.00			Each	
					Total	


 Executive Engineer
 Gohar Division (B&R)
 H.P.W.D Gohar.

22

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 155704/- only
Earnest Money: Rs 3500/- only
Time :Three month

C/o Jatehra Katal Tamroh Chountra Upper pali road KM 0/0 to 2/0
and laying Kharanja stone soling and cement pavement at RD. 1/943.90 to 2/0) Under OTMNP

Sub Head and item of work	Qyt.	Rate in		Unit	Amount
		Figure	Word		
2	3	4	5	6	7
of sub grade by dressing to camber (Earth work for the cutting involved to be paid for separately depending upon the classification of soil as per HP.PWD specifications including all leads , lifts of material and	21.38	sqm		Per Cubic metre	8
properly handpacked filling interstices with Kharanja stone and with power road roller to the requested gradient and comber including aterring and rolling of binding materials moorum or earth etc. complete WD specification. 100 mm spread thickness (finished work including labour) with in all leads ,lifts and carriage of materials and other	25.66	cum		Per Cubic metre	
and laying concrete for plain reinforced concrete in open foundation per drawing and technical specification clauses 802,803,1202 and grade M-20 1:2: 4 (one cement : two sand : four crushed stone agreegate size . with in all leads ,lifts and carriage of materials and other	21.38	cum		Per Cubic metre	
				Total	


Executive Engineer
Gohar Division
HPPWD Gohar