



Telephone No: 01782-233214

E-mail: cenh-ram-hp@nic.in

No. PW/EE/NH/RMP-CB-Tender /2022-23-
To


Dated:- 31/8/2022

The Executive Engineer, (IT)
Nigam Vihar Shimla-2.

Subject: - Publication of Tender notice


Enclosed please find herewith NIT for uploading on department website as the works mentioned in the NIT are urgent nature and in public interest.

DA:- Copy of NIT and schedule of quantity


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr.

Copy forwarded to the Superintending Engineer NH Circle HPPWD Shimla for information, please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action, please.


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage rate tender(s) on PWD form No.6 &8 are hereby invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD in appropriate class to reach in this office on **09-09-2022** up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **08-09-2022** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without **earnest money** or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	A/R & M/O NH-05 Km 236/00 to 368/00 (SH:- C/o V shape drain in PCC at RD 316/880 to 317/060).	495310/-	10000/-	One month	6&8	350/-
2	A/R & M/O NH-505A Km 0/00 to 17/00 (SH:- C/o R/wall in wire crate at RD 0/403 to 0/409).	471303/-	9500/-	One month	6&8	350/-
3	A/R & M/O NH-505A Km 0/00 to 17/00 (SH:- C/o B/wall in wire crate at RD 0/420 to 0/436.50).	461743/-	9500/-	One month	6&8	350/-
4	A/R & M/O NH-505A Km 0/00 to 17/00 (SH:- C/o R/wall in wire crate at RD 0/438 to 0/454.50).	460419/-	9500/-	One month	6&8	350/-
5	A/R & M/O NH-505A Km 0/00 to 17/00 (SH:- C/o B/wall in wire crate at RD 0/456 to 0/476).	464400/-	9500/-	One month	6&8	350/-
6	A/R & M/O NH-505A Km 0/00 to 17/00 (SH:- C/o R/wall in wire crate at RD 0/478 to 0/495).	452520/-	9100/-	One month	6&8	350/-
7	A/R & M/O NH-05 Km 236/00 to 368/00 (SH:- P/L of kilometer stone including painting etc between Km 307/00 to 368/00).	241235/-	4900/-	One month	6&8	350/-
8	A/R & M/O NH-05 Km 236/00 to 368/00 (SH:- Breaking of existing hard boulder with breaker at RD 325/220 to 325/230.50 (Bhabanagar Market)).	474225/-	9500/-	One month	6&8	350/-
9	A/R & M/O NH-05 Km 236/00 to 368/00 (SH:- Breaking of existing hard boulder with breaker at RD 325/080 to 325/094(Bhabanagar Market)).	487789/-	10000/-	One month	6&8	350/-
10	A/R & M/O NH-05 Km 236/00 to 368/00 (SH:- Providing and laying G-III and 20 mm thick premix carpet in pot holes along with seal coat at various reaches between Km /RD 312/00 to 329/00).	398197/-	8000/-	One month	6&8	350/-
11	A/R & M/O NH-05 Km 236/00 to 368/00 (SH:- Providing and laying G-III and 20 mm thick premix carpet in pot holes along with seal coat at various reaches between Km /RD 307/00 to 312/00).	462996/-	9500/-	One month	6&8	350/-

SPECIAL CONDITIONS

- The material shall be arranged by the contractor himself.
- The detail of documents to be attached with the application is given below.
 - Latest copy of renewal enlistment.
 - Copy of Pan Card.
 - Copy of GST No.
- The offer of the tender shall be kept open for 90 days
- Tender received after the specified time/date shall not be opened.
- Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
- If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.

7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.

8. The contractor/ firms are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.

9. The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).

10. The labour cess @ 1% will be deducted from the gross amount of the bill

11. A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.

12. The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.

13. Cement should be purchased from H.P. State Civil Supply Corporation

14. GST will be deducted from each bill as per latest instruction of the Government.

Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr.

Dated:- 31/08/22

No.PW/EE/NH/RMP/CB-Tender Notice/2022-23-
Copy forwarded for information to the:-


4441-51

1. Engineer-in-Chief, HP.PWD, Shimla
2. Chief Engineer (NH) HP.PWD, Shimla-1
3. Superintending Engineer, NH-Circle, HP.PWD, Shimla. It is requested to kindly issue the certificate the tender of above emergent nature in public interest.
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.

Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr

Certificate

Certified that the tenders of the works invited vide this office NIT No. PW/EE/NH/RMP/CB-tender/2022-23- 4441-51 dated 31-08-2022 is of urgent nature and in public interest.


Executive Engineer
NH Division HPPWD,
Rampur Bushahr.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-05 Km 236/000 to 368/000 (SH:- C/O V-shape drain in PCC at RD 316/880 to 317/060).

Estimated cost:- 495310.00
Earnest money:- 10000.00
Time:- One month

Sr. No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications in all kinds of soils i.e. pick work, jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charge with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost	88.20	271.00	(Rupees Two hundred seventy one and paise) <i>220/27</i>	Per Cubic metre	23902.00
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	81.00	5819.85	(Rupees five thousand eight hundred nineteen and paise five) only	Per Cubic metre	471408.00
					Total:-	495310.00
	Quoted rate in figures	+/-	(.....)%		
	Quoted rate in words					


ke
Executive Engineer,
NH Division HPPWD,
Raipur Bsr.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-505A Km 0/000 to 17/000(SH:- C/O R/wall in wire crate at RD 0/403 to 0/409).

Estimated cost:- 471303.00
Earnest money:- 9500.00
Time:- One month

Sr. No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost	52.92	271.00	(Rupees Two hundred seventy one and paise zero) only	Per Cubic metre	14341.00
2	Providing and laying of boulders apron laid in wire crate made with 4 mm (Four millimetre) thick G.I wire confirming to IS 280 and IS 4826 in 100x100 mm(hundred into hundred milimetre) mesh (Waved diagonal) in all heights and depths including 10% extra for laps and joints laid with stone boulders weighing not less than 40Kg(Forty kilograms) each including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specification (Latest revision) and as per direction of the Engineer-in-Charge.	142.56	3205.40	(Rupees Three thousand two hundred five and paise forty) only	Per Cubic metre	456962.00
Quoted rate in figures		+/ -	(.....)%	Total:-	471303.00
Quoted rate in words						


Executive Engineer,
NH Division HPPWD,
Raipur Bsr.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/o NH-505 A Km 0/0 to 17/0 (SH:- Construction of B/wall in wire crate at RD 0/420 to 0/436.50)

0/420 to 0/436.50)						
Construction of B/wall in wire crate at RD						
Estimated Cost:- 461743.00						
Earnest Money 9500.00						
Time :- Two Month						
S.No	Descriptions.	Quantity	Unit	Rate		Amount
				In figure	In words.	
1	Earth work road way in soil by mechanical means i/c cutting and pushing the earth to site of embankment upto a distance of 100 mtrs. (Av. Lead 50 mtrs) i/c trimming bottom and side slope in accordance with requirement of lines, grades and x- section. stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	157.74	Per cubic meter.	236.00	Rupees Two hundred thirty six and paise zero only	37227.00
2	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications(Latest revision) in all kinds of soils i.e pick work,jumper work,blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights,stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	20.79	Per cubic meter.	271.00	Rupees Two hundred seventy one and paise zero only	5634.00
3	Providing and laying of boulders apron laid in wire crate made with 4 mm (Four millimetre) thick G.I wire confirming to IS 280 and IS 4826 in 100x100 mm(hundred into hundred milimetre) mesh (Weaved diagonal) in all heights and depths including 10% extra for laps and joints laid with stone boulders weighing not less than 40kg(Forty kilograms) each including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specification (Latest revision) and as per direction of the Engineer-in-Charge.	130.68	Per cubic meter.	3205.40	Rupees Three thousand two hundred five and paise forty only	418882.00
Quoted rate in figures				+/-	(.....)%
Quoted rate in words				461743.00		

Notes: Contractor will be responsible for the following matters:-

Note:-Contractor will himself arrange the following materials:-

1.G.I.wire:- wire will be arranged by the contractor himself .

2.Accounting system will be same as is being followed as per present practice.

beet
Executive Engineer,
N.H.Division, HP.PWD,
Rampur Bsr.

SCHEDULE OF QUANTINTY

Name of Work:- A/R & M/o NH-505 A Km 0/0 to 17/0 (SH- Construction of R/wall in wire crate at RD 0/438 to 0/454.50)

Estimated Cost:- 460419.00

Earnest Money 9500.00

Time :- Two Month

S.No	Descriptions.	Quantity	Unit	Rate		Amount
				In figure	In words.	
1	Earth work road way in soil by mechanical means i/c cutting and pushing the earth to site of embankment upto a distance of 100 mtrs. (Av. Lead 50 mtrs) i/c trimming bottom and side slope in accordance with requirement of lines, grades and x- section. stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	152.13	Per cubic meter.	236.00	Rupees Two hundred thirty six and paise zero only	35903.00
2	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications(Latest revision) in all kinds of soils i.e. pick work, jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	20.79	Per cubic meter.	271.00	Rupees Two hundred seventy one and paise zero only	5634.00
3	Providing and laying of boulders apron laid in wire crate made with 4 mm (Four millimetre) thick G.I wire conforming to IS 280 and IS 4826 in 100x100 mm(hundred into hundred millimetre) mesh (Weaved diagonal) in all heights and depths including 10% extra for laps and joints laid with stone boulders weighing not less than 40Kg(Forty kilograms) each including carriage of materials by mechanical transport in all leads and lifts conforming with the MORTH Specification (Latest revision) and as per direction of the Engineer-in-Charge.	130.68	Per cubic meter.	3205.40	Rupees Three thousand two hundred five and paise forty only	418882.00
Quoted rate in figures						460419.00
Quoted rate in words			+/-	(.....)%	

Note:-Contractor will himself arrange the following materials:-

1.G.I.wire:-wire will be arranged by the contractor himself.

2.Accounting system will be same as is being followed as per present practice.


Executive Engineer,
N.H.Division, HP, PWD,
Rohatpur Bsr.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/o NH-505 A Km 0/0 to 17/0 (SH:- Construction of B/wall in wire crate at RD 0/456 to 0/476)

Estimated Cost:- 464400.00
Earnest Money 9500.00

Time :- Two Month

S.No	Descriptions.	Quantity	Unit	Rate		Amount
				In figure	In words.	
1	Earth work road way in soil by mechanical means i/c cutting and pushing the earth to site of embankment upto a distance of 100 mtrs. (Av. Lead 50 mtrs) i/c trimming bottom and side slope in accordance with requirement of lines, grades and x- section. stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	169.00	Per cubic meter.	236.00	Rupees Two hundred thirty six and paise zero only	39884.00
2	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications(Latest revision) in all kinds of soils i.e pick work,jumper work,blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights,stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	20.79	Per cubic meter.	271.00	Rupees Two hundred seventy one and paise zero only	5634.00
3	Providing and laying of boulders apron laid in wire crate made with 4 mm (Four millimetre) thick G.I wire confirming to IS 280 and IS 4826 in 100x100 mm(hundred into hundred millimetre) mesh (Weaved diagonal) in all heights and depths including 10% extra for laps and joints laid with stone boulders weighing not less than 40Kg(Forty kilograms) each including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specification (Latest revision) and as per direction of the Engineer-in-Charge.	130.68	Per cubic meter.	3205.40	Rupees Three thousand two hundred five and paise forty only	418882.00
Quoted rate in figures						464400.00
Quoted rate in words						

Note:-Contractor will himself arrange the following materials:-

1.G.I.wire:- wire will be arranged by the contractor himself.

2.Accounting system will be same as is being followed as per present practice.


Executive Engineer,
N.H.Division,HP,PWD,
Rampur Bsr.

SCHEDULE OF QUANTINTY

Name of Work:- A/R & M/o NH-505 A Km 0/0 to 17/0 (SH- Construction of R/wall in wire crate at RD 0/478 to 0/495)

Estimated Cost:- 452520.00

Earnest Money 9100.00


Time :- Two Month

S.No	Descriptions.	Quantity	Unit	Rate		Amount
				In figure	In words.	
1	Earth work road way in soil by mechanical means i/c cutting and pushing the earth to site of embankment upto a distance of 100 mtrs. (Av. Lead 50 mtrs) i/c trimming bottom and side slope in accordance with requirement of lines, grades and x- section. stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	118.66	Per cubic meter.	236.00	Rupees Two hundred thirty six and paise zero only	28004.00
2	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications(Latest revision) in all kinds of soils i.e, pick work, jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	20.79	Per cubic meter.	271.00	Rupees Two hundred seventy one and paise zero only	5634.00
3	Providing and laying of boulders apron laid in wire crate made with 4 mm (Four millimetre) thick G.I wire conforming to IS 280 and IS 4826 in 100x100 mm(hundred into hundred millimetre) mesh (Weaved diagonal) in all heights and depths including 10% extra for laps and joints laid with stone boulders weighing not less than 40Kg(Forty kilograms) each including carriage of materials by mechanical transport in all leads and lifts conforming with the MORTH Specification (Latest revision) and as per direction of the Engineer-in-Charge.	130.68	Per cubic meter.	3205.40	Rupees Three thousand two hundred five and paise forty only	41882.00
Quoted rate in figures				+/-	(.....)	452520.00
Quoted rate in words				%	

Note:-Contractor will himself arrange the following materials:-

1.G.I.wire:- wire will be arranged by the contractor himself.

2.Accounting system will be same as is being followed as per present practice.


Executive Engineer,
N.H.Division, HP.PWD,
Raipur Bsr.


SCHEDULE OF QUANTITY

Name of work:- A/R & M/O NH-05 Km 236/000 to 368/000 (SH:- P/L of kilometre stone including painting etc between Km 307/000 to 368/000)

Estimated cost:- 241235.00
Earnest money:- 4900.00

Time:- one Month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Construction /providing and fixing of reinforced cement concrete M-15 grade kilometre stone of standard design as IRC: 8, fixing in position including painting and printing with in all leads and lifts and as per direction of the Engineer-in-Charge. (5th Kilometre Stones)	12.00	5747.05	(Rupees Five thousand seven hundred forty seven and paise zero five) only	Each	68965.00
2	Construction /providing and fixing of reinforced cement concrete M-15 grade kilometre stone of standard design as IRC: 8, fixing in position including painting and printing with in all leads and lifts and as per direction of the Engineer-in-Charge. (Ordinary Kilometre Stones)	50.00	3445.40	(Rupees Three thousand four hundred forty five and paise forty) only	Each	172270.00
Quoted rate in figures		+/	(.....)%	Total:-	241235.00
Quoted rate in words						


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-05 Km 236/000 to 368/000(SH:- Breaking of existing ~~hard~~ boulder with breaker at RD 325/220 to 325/230.50 (Bhabanagar Market)).

Estimated cost:- 474225.00
Earnest money:- 9500.00
Time:- One month

Sr, No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	Excavation in Hard Rock (Blasting Prohibited) :- Excavation for roadway in hard rock (blasting Prohibited) with rock breakers including breaking rock, loading in tippers and disposal within all lift and lead upto 1000 metres, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections including Recovery of use full stones.	479.33	989.35	(Rupees Nine hundred eighty nine and paise thirty five)	Per Cubic metre	474225.00
					Total:-	474225.00
Quoted rate in figures		+/ -	(.....)%		
Quoted rate in words						

Executive Engineer,
NH Division HPPWD,
Rampur Bst.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-05 Km 236/000 to 368/000(SH:- Breaking of existing handr boulder with breaker at RD 325/080 to 325/094 (Bhabanagar Market)).			Estimated cost:- 487789.00 Earnest money:- 10000.00 Time:- One month	
--	--	--	--	--

Sr. No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	Excavation in Hard Rock (Blasting Prohibited) :- Excavation for roadway in hard rock (blasting Prohibited) with rock breakers including breaking rock, loading in tippers and disposal within all lift and lead upto 1000 metres, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections including Recovery of use full stones.	493.04	989.35	(Rupees Nine hundred eighty nine and paise thirty five)	Per Cubic metre	487789.00
Total:-						487789.00
Quoted rate in figures		+/ -	(.....)%		
Quoted rate in words						


 Executive Engineer,
 NH Division HPPWD,
 Raipur Bsr.


SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-05 Km 236/00 to 368/00(SH:- P/L G-III and 20mm thick premix carpet in pot holes along with seal coat at various reaches between Km Km / RD 312/000 to 329/000).

Estimated cost:- 398197.00
Earnest money:- 8000.00
Time:- One month

Sr, No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes(Grade-II) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/ vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density of MORTH road wing specification for road and bridge works (latest revision) and as per the direction of the Engineer-in-Charge.	18.74	3067.05	(Rupees Three thousand sixty seven and paise five) only	Per Cubic metre	57477.00
2	Tack Coat: Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 kg per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.of MORTH road wing specification for road and bridge works (latest revision) and as per the direction of the Engineer-in-Charge.	832.65	22.55	(Rupees Twenty two and paise fifty five) only	Per Square metre	18776.00
3	Providing and laying and rolling open graded premix carpet of 20mm thickness composed of 13.2mm to 5.6mm aggregates either using penetration grade bitumen of emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity finished to required level and grades to be followed by seal coat of either type -B or type C as per technical specification clause 508 By manual means, and as per the direction of the Engineer-in-Charge.	832.65	251.65	(Rupees Two hundred fifty one and paise sixtyfive) only	Per Square metre	209536.00

4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using type-A Type-B and type-C as per technical specification clause 510 (type-B) and as per the direction of the Engineer-in-Charge.	832.65	135.00	(Rupees One hundred thirty five and paise zero) only	Per Square metre	112408.00
	Quoted rate in figures	+/-	(.....)%	Total:-	398197.00
	Quoted rate in words					


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bst.


SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-05 Km 236/00 to 368/00(SH:- P/L G-III and 20mm thick premix carpet in pot holes along with seal coat at various reaches between Km Km / RD 307/000 to 312/000).

Estimated cost:- 462996.00
Earnest money:- 9500.00
Time:- One month

Cr. No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
	1. Provisioning of 20mm thick premix carpet of specification (Grade-II) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/ vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density of MORTH road wing specification for road and bridge works (latest revision) and as per the direction of the Engineer-in-Charge	21.73	2067.05	(Rupees Three thousand sixty seven and paise five) only	Per Cubic metre	66800.00
2	Tack Coat: Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 kg per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. of MORTH road wing specification for road and bridge works (latest revision) and as per the direction of the Engineer-in-Charge.	968.22	22.55	(Rupees Twenty two and paise fifty five) only	Per Square metre	21833.00
3	Providing and laying and rolling open graded premix carpet of 20mm thickness composed of 13.2mm to 5.6mm aggregates either using penetration grade bitumen of emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN static roller capacity finished to required level and grades to be followed by seal coat of either Type -B or type C as per technical specification clause 508 By manual means, and as per the direction of the Engineer-in-Charge.	968.22	251.65	(Rupees Two hundred fifty one and paise sixtyfive) only	Per Square metre	243653.00

4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using type-A Type-B and type-C as per technical specification clause 510 (type-B) and as per the direction of the Engineer-in-Charge.	968.22	135.00	(Rupees One hundred thirty five and paise zero) only	Per Square metre	130710.00
Quoted rate in figures		+	(.....)%	Total:-	462996.00
Quoted rate in words						


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bst.