

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23-

10/8789 Dated:- 31/8/22

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 06.09.2022 up to 11:00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 05.09.2022 upto 01:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Mini Secretariat cum Combind Office Building at Padhar Tehsil Padhar District Mandi (H.P.) (SH:- Providing and fixing PVC waste pipe 150mm dia., wash basin pedestal, C.P. brass sink mixer)	4,28,097/-	8,600/-	350/-	One month
2	Construction of Mini Secretariat cum Combind Office Building at Padhar Tehsil Padhar District Mandi (H.P.) (SH:- Providing and laying granite stone dado in out side of lift well)	4,18,066/-	8,400/-	350/-	One month
3	Construction of Mini Secretariat cum Combind Office Building at Padhar Tehsil Padhar District Mandi (H.P.) (SH:- Construction of brick masonry manhole)	2,73,321/-	5,500/-	350/-	One month
4	Restoration of rain damages on Barot to Mayot road Km 0/0 to 7/960 (SH:- Construction of V-Shape drain in Km 7/063 to 7/645)	3,53,577/-	7,100/-	350/-	Three months

1. **Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.

7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


Schedule of Quantity

Estimated Cost:- Rs. 428097.00
 Earnest Money:- Rs. 8600.00
 Time:- One month

Name of work:- Construction of Mini Secretariat cum Combined Office Building at Padhar Tehsil Padhar District Mandi (H.P.)
 Sub Head:- Providing and fixing PVC waste pipe 150mm dia., wash basin pedestal, C.P. brass sink mixer.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing and fixing 150mm (one hundred fifty millimetre) diameter high pressure PVC spigot and socket, waste and ventilating pipe ISI marked including jointing with approved adhesive etcetera including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	298.00 Mtr.			Per running metre	
2	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of material with in all leads, lifts and other incidentals complete in all respect as per direction and satisfaction of Engineer-in-Charge.	48.00 Nos.			Each	
3	Providing and fixing 15mm (fifteen millimeter) nominal bore C.P. brass centre hole wash basin mixer of approved quality conforming to IS standards complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	4.00 Nos.			Each	
4	Providing and fixing 15mm (fifteen millimeter) nominal bore C.P. brass sink mixer of approved quality conforming to IS standards complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	8.00 Nos.			Each	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P. PWD. at Padhar.

2

Schedule of Quantity

Estimated Cost:- Rs. 418066.00
 Earnest Money:- Rs. 8400.00
 Time:- One month

Name of work:- Construction of Mini Secretariat cum Combined Office Building at Padhar Tehsil Padhar District Mandi (H.P.)
 Sub Head:- Providing and laying granite stone dado in out side of lift well.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing and laying polished granite stone 20mm to 25mm (twenty millimetre to twenty five millimetre) thick in risers of steps, skirting, dado in required design and patterns in linear as well as curvilinear portion of the building all complete as per Architectural drawings laid over 20mm (twelve millimetre) (average) thick cement mortar 1:3 (one cement : three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the granite stone complete as per specification in all floors including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	67.68 Sqm.			Per square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- Rs. 273321.00
 Earnest Money:- Rs. ~~55000.00~~
 Time:- One month

Name of work:- Construction of Mini Secretariat cum Combined Office Building at Padhar Tehsil Padhar District Mandi (H.P.)
Sub Head:- Construction of brick masonry manhole.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Constructing brick masonry manhole in cement mortar 1:4 (one cement : four coarse sand) with R.C.C. top slab with 1:1.5:3 mix (one cement : one and half coarse sand : three graded, crushed stone aggregate 20 mm (twenty millimetre) nominal size), foundation concrete 1:4:8 mix (one cement : four coarse sand : eight graded, crushed stone aggregate 40 mm (forty millimetre) nominal size), inside plastering 12 mm (twelve millimetre) thick with cement mortar 1:3 (one cement : three coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (one cement : two coarse sand : four graded, crushed stone aggregate 20 mm (twenty millimetre) nominal size) finished with a floating coat of neat cement complete as per standard design. Inside size 90 x 80 cm (ninety into eighty centimetre) and 45 cm (forty five centimetre) deep including C.I. cover with frame (light duty) 455x610 mm (four hundred fifty five into six hundred ten millimetre) internal dimensions, total weight of cover and frame to be not less than 38 kg (thirty eight kilogram) (weight of cover 23 kg (twenty three kilogram) and weight of frame 15 kg (fifteen kilogram) with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) complete in all respect including curing and carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	25.00 Nos			Each	
					Total:-	


 Executive Engineer,
 Mandi Division No.I
 H.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 353577.00
 Earnest Money:- 7100.00
 Time:- Three months

Name of work:- Restoration of rain damages on Barot to Mayot road Km. 0/0 to 7/960.
Sub Head:- Construction of V-Shape drain in Km. 7/063 to 7/645.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Construction of V-Shape Drain with mechanically mixed and vibrated plain cement concrete M-10 (ten) grade nominal mix 1:3:6 (one cement : three sand : six graded, crushed stone aggregate 20mm (twenty millimeter) nominal size) with thickness of concrete 10cm (ten centimeter) and size of drain 47.4 x 35cm (forty seven point four centimetre into thirty five centimeter) and curing complete including cost of excavation and form work consisting as per standard drawing and HP.PWD. specifications including carriage of material within all leads, lifts and other incidentals as per the direction of Engineer-in-Charge complete in all respect.	551.00			Per running metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.I,
 M.P.P.W.D. at Padhar