

Himachal Pradesh  
Public Works Department  
PW-RD-GA-Tender-2021-22-  
To

107/4

dated:- 14-9-2022


The Executive Engineer (IT Cell)  
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & sechedule of quantity.

  
Executive Engineer,  
B&R Division, HPPWD,  
Rohru.

**Himachal Pradesh  
Public Works Department  
"NOTICE INVITING TENDERS"**

Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and eligible contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-

- |   |                                  |
|---|----------------------------------|
| 1. Date of receipt of applications for tender forms:- | 21.09.2022 upto 1:00PM           |
| 2. Date of issue/sale of tender forms:-               | 21.09.2022 upto 2:00PM to 3.00PM |
| 3. Date of receipt of tender:-                        | 22.09.2022 upto 3:30PM           |
| 4. Date of opening of tender:-                        | 22.09.2022 upto 4:00PM           |

Sr.No.	Name of Work.	Estt. Cost.	E/Money	Time.
1	R/R Damages to Various road under Rohru Section Rohru Sub-Division (SH:- Hiring of Tipper for carriage of muck etc.	Rs.162000/-	Rs.3240	1 months
2	R/R Damages to Various road under Rohru Section Rohru Sub-Division (SH:- Hiring of Tipper for carriage of muck etc.	Rs.162000/-	Rs.3240	1 months
3	C/O Civil Hospital at Rohru (SH:-Inogration / Foundation stone at Rohru	R.295973/-	Rs.5919/-	2 months
4	A/R & M/O Staff Quarter at Rohru (SH:- Steel work for water storage tank	Rs.498713/-	Rs.9974/-	2 months
5	A/R & M/O Housing Boar Colony at Samala (SH:- painting and white Washing (in Ground floer for flate No. 31,32,33,29A,30A,31A,32A	Rs. 485120/-	Rs.9702/-	2 months
6	A/R & M/O Housing Boar Colony at Samala (SH:- painting and white Washing (in Ground floer for flate No. 6,710,11,22,29,30	Rs. 485120/-	Rs.9702/-	2 months
7	A/R & M/O Circle Building at Rohru (SH:- C/O Roof work over the PMGSY Branch	Rs. 499869/-	Rs.9997/-	2 Months
8	A/R & M/O Civil Judge Cum ACJM Building at Rohru (SH:- P/F cup Board in residence at Rohru	Rs. 494373/-	Rs. 9887/-	3 Months
9	A/R & M/O Civil Judge Cum ACJM Building at Rohru (SH:- P/F cup Board in Court Room at Rohru.	Rs. 493859/-	Rs. 9877/-	2Months
10	A/R & M/O Civil Jundge Cum ACJM Building at Rohru (SH:- P/F floor tiles and WS & SI )	Rs. 499975/-	Rs. 9999/-	2 Months
11	A/R & M/O staff quarter at Rohru (SH:- P/F water storage tank for staff quarter	Rs. 479764/-	Rs. 9595/-	2 Months
12	C/O Govt. PG College Seema (SH:- C/O Play ground Pedistal in RR Masonary 1:6 Towards valley side at Rd. 0/0 to 0/12	Rs. 474157/-	Rs. 9483/-	2 Months
13	C/O Govt. P.G Degree College Seema (SH:- C/O B/Wall in RR masonary 1:6 at Auditorium Building at R D 0/0 to 0/024	Rs. 461685/-	Rs. 9234/-	2 Months
14	C/O Govt. P.G College at Seema (SH:- C/O Play Ground U-Shape drain in PCC 1:2:4 at Rd. 0/0 to 0/075 (Entance side )	Rs. 464809/-	Rs. 9296/-	2 Months
15	R/R Damages to RCD road Km. 2/0 to 21/195(SH:- C/O R/Wall in PCC 1:3:6 at Rd. 9/165 to 9/174)	Rs.497324/-	Rs. 9946/-	2 Months
16	A/R & M/O PWD Rest House & Circuit House at Rohru (SH:- Repairing of Furniture	Rs. 136935/-	Rs. 3278/-	1 Month
17	R/R Damages Samoli Bhatwari road Km. 0/0 to 7/0 (SH:- C/o R/Wall in PCC 1:4:8at Rd.3/450 to 3/470.50	Rs. 495761/-	Rs. 9995/-	2 Months
18	C/O link road from Sandasuto Shishary (HB) Dakoti Prja road Km. 0/0 to 38/522	Rs. 487022/-	Rs.9740/-	2Months
19	RR Damages to RCD road Km.2/0 to 21/195 (SH:- C/O R/Wal in PCC 1:3:6 at Rd.9/135 to 9/164	Rs. 497324/-	Rs.9946/-	2 Monthr

**Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.**

**Terms and conditions:-**The tender doucument shellbe issued only to these contractors/firms who fulfill the following criteria and submit the following doucument with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quoted the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

Executive Engineer,  
B&R Division, HPPWD, Rohru

NO.:PW-RD-GA.-Tender/2022-23--

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(S), HPPWD, Shimla-2.
3. The SE 14<sup>th</sup> Circle HPPWD, Rohru
4. All the E.E.'s under 14<sup>th</sup> Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Dated:- 14.9.22

Executive Engineer,  
B&R Division, HPPWD, Rohru

**SCHEDULE OF QUANTITY.**

Estimate Cost 162000/-  
 Earnest Money 3240.00  
 Time 30days

**Name of work :-** R/R damages on various road under Rohru section Rohru sub Divn (SH-Hiring of tipper for carriage of muck).

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of Tipper for carriage of material having capacity 200cft including POL chage shifting charge and other ancillary equipment as required ast site of work. The work shall have is carried out as per ministry of Transport specification of the Engineer in charge including all leads and lifts	30.00			Per day	
	Total				Total	

  
 Executive Engineer  
 B&R Divn HP PWD  
 Rohru



Job No. 2

### SCHEDULE OF QUANTITY.

Estimate Cost 162000/-  
Earnest Money 3240.00  
Time 30days

Name of work :-R/R damages on various road under Rohru section Rohru sub Divn (SH-Hiring of tipper for carriage of muck).

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of Tipper for carriage of material having capacity 200cft including POL chage shifting charge and other ancillary equipment as required ast site of work. The work shall have is carried out as per ministry of Transport specification of the Engineer in charge including all leads and lifts	30.00			Per day	
Total					Total	

  
Executive Engineer  
B&R Divn HP PWD  
Rohru

Job No. 3

Schedule of Qty						
Name of Work:-C/o Civil Hospital at Rohru				ESTIMATED COST		
Sh:- C/o Inogratation/Foundation Stone at Rohru				EARNEST MONEY		
				TIME LIMIT:		
				Two Months		
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Steel work welded in built up sections, trusses and framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts :-In gratings, framed, guards, bars ladders and railing, brackets and similar works :-	1694.548	kg			
2	Providing and fixing 12mm thick commercial board shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	20.4	sqm			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Rohru

206 M.O.L

Schedule of Qty						
Name of Work :- A/R & M/O Staff Quarter at Rohru				ESTIMATED COST		
Sh:- Steel Work for water Storage tank.				EARNEST MONEY		498713
				TIME LIMIT:		9974
						Two Months
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Steel work welded in built up sections, trusses and framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts :- In gratings, framed, guards, bars ladders and railing, brackets and similar works :-	3259.56	kg			
Total						

Executive Engineer  
B&R Division HPPWD  
Rohru

# Name of Work:- A/R & M/O Housing board Colony at Samala

## Schedule of Qty

Sh:-Painting and White washing( In Gound floor) for flat No 31,32,33,29A,30A,31A,32A							ESTIMATED COST	485120
							EARNEST MONEY	9702
							TIME LIMIT:	Two Months
Sr. No	Description of items.	Qty	Unit	Rate		Amount.		
				In Fig.	In Words			
1	2	3	4	5	6	7		
1	Applying white cement based wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. complete within all leads, lifts of materials and other incidentals.	2092.93	sqm					
2	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface on all floor to give an even shade over and including priming coat of distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth complete including carriage within all leads, lifts of materials and other incidentals.	2092.93	sqm					
3	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting with ready mixed paint brushing wood primer pink. including carriage within all leads, lifts of materials and other incidentals.	216.09	sqm					
4	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering and stopping including carriage within all leads, lifts of materials and other incidentals:- with enamel paint other than white.	216.09	sqm					
Total								

  
Executive Engineer  
B&R Division HPPWD  
Rohru



Job No. 6

Schedule of Qty									
Name of Work:- A/R & M/O Housing board Colony at Samala									
Sh:-Painting and White washing( In Gound floor) for flat No 6,7,10,11,22,29,30									
Sr. No	Description of items.	Qty	Unit	ESTIMATED COST			EARNEST MONEY		
				TIME LIMIT:			TIME LIMIT:		
1	2	3	4	Rate	In Fig.	In Words	Amount.	Two Months	
1	Applying white cement based wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. complete within all leads, lifts of materials and other incidentals.	2092.93	sqm	5	5	6	7		
2	Distemper (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface on all floor to give an even shade over and including priming coat of distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth complete including carriage within all leads, lifts of materials and other incidentals.	2092.93	sqm						
3	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting with ready mixed paint brushing wood primer pink. including carriage within all leads, lifts of materials and other incidentals.	216.09	sqm						
4	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering and stopping including carriage within all leads, lifts of materials and other incidentals:- with enamel paint other than white.	216.09	sqm						
Total									



Executive Engineer  
B&R Division HPPWD  
Rohru



## Name of Work :- A/R &amp; M/O Circle Building at Rohru

## Schedule of Qty

Sh:- C/o Roof work over the PMGSY Branch.		ESTIMATED COST	
		EARNEST MONEY	
		499869	9997
Sr. No		TIME LIMIT:	
1	Description of Items.	Rate	Two Months
		In Fig. 5	In Words 6 Amount. 7
1	Steel work welded in built up sections, trusses and framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts :- In gratings, framed, guards, bars ladders and railing, brackets and similar works :-	2084.486	
2	Providing and fixing M.S. B.P Sheet 2.00mm (two millimetre) thick in eaves board/ fascia/ soffits/ ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer (Base members of steel work shall be measured and paid for separately) with scaffolding work including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	24.8	
3	Providing and fixing 0.63mm thick prepainted steel sheet Tata, Durashine of approved brand and shade and design in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5microns required sizes / prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete upto floor all level with all accessories as required as per the direction of Engineer-in-charge:-0.60mm (zero point sixty millimetre) thick sheet including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	68.25	
4	Providing and fixing ridges or hips 60 cm overall prepainted steel sheets Tata, Durashine of approved brand, shade and design in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating including fixing with G.I. self drilling screws of required sizes / prepainted iron J or L hooks, bolts and nuts 6mm dia and prepainted G.I. limpet and bitumen washers complete upto floor all level with all accessories as required as per the direction of Engineer in Charges:- 0.60mm (zero point sixty millimetre) thick sheet including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	9.35	
Total			

Executive Engineer  
B&R HPPWD Divn. Rohru

## DNIT

Name of Work:- A/R & M/O Civil Judge Cum ACJM Building at Rohru.				ESTIMATED COST	
SH:- P/F cup board in residence at Rohru.				EARNEST MONEY	9887
				TIME LIMIT:	3 Months
Sr. No	Description of items.	Qty	Unit	Rate	Amount.
				In Fig.	
1	2	3	4	5	6
1	P/F 12mm thick prelaminated board both side Bwp phenol bonded exterior/interior grade sguiter with frame 1st class deodar wood complete including carriage of materials in all leads and lifts.	62.52	sqm		7
2	Providing and fixing Steel Legs complete including carriage of materials in all leads and lifts:-	30	Each		
3	Providing and fixing powder coated Aluminium tower bolts (Berrel type) transparent or dyed to required shade and colour with screws etc. complete including carriage of materials in all leads and lifts:-	150	Each		
4	150x10mm				
4	Providing and fixing powder coated Aluminium handles transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts :-	100	Each		
	125mm				
5	Providing & fixing 150 mm M.S. single acting spring hinges bright finished with necessary screws etc. complete including carriage of materials in all leads and lifts :-	40	Each		
6	P/L linolium covering to floor, plain or coloured laid with an approved adhesive on sub floor including cutting and fixing complete to sub floor including damp proofing treatment (damp proofing treatment to be measured separately for payment.) 3.2 mm to 4.5 mm thick.	81.82	sqm		
Total					

  
 Executive Engineer  
 B&R Division HPPWD  
 Rohru

Go b 010.9

**Schedule of Qty**

Name of Work:- A/R & M/O Civil Judge Cum ACJM Building at Rohru.				ESTIMATED COST		493859
SH:- P/F cup board in court room at Rohru.				EARNEST MONEY		9877
				TIME LIMIT:		Two Months
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1		2		5	6	7
1	P/F 12mm thick prelaminated board both side Bwp phenol bonded exterior/interior grade sgutter with frame 1st class deodar wood, complete including carriage of materials in all leads and lifts.	119.52	sqm			
Total						

  
Executive Engineer  
B&R Division HPPWD  
Rohru



506 No 16

Schedule of Qty

Name of Work:- A/R & M/O Civil Judge Cum ACJM Building at Rohru (SH:- P/F Floor tile and WS & SI)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		Two Months
				Rate In Fig.	In Words	Amount
1	2	3	4	5	6	7
1	Providing and fixing 10 mm thick acid and/or alkali resistant tiles of approved make and colour using acid and/or alkali resisting mortar bedding, and joints filled with acid and/or alkali resisting cement as per IS : 4457, complete as per the direction of Engineer-in- Charge In flooring on a bed of 10 mm thick mortar 1:4 (1 acid proof cement : 4 coarse sand)	163.22	sqm			
2	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	4	sqm			
3	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	4	sqm			
4	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete : White solid plastic seat with lid	4	sqm			
5	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. pan.	4	sqm			
6	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete: Semi rigid pipe	4	sqm			
7	Providing and fixing 100 mm sand cast Iron grating for gully trap.	16	sqm			
8	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	4	sqm			
9	Providing and fixing soil, waste and vent pipes : 100 mm dia Sand cast iron S&S pipe as per IS: 1729	33.6	sqm			
10	Providing and fixing toilet paper holder : C.P. brass	4	sqm			
11	Providing and fixing plain band of required degree: 100 mm dia	16	sqm			
12	P/F MS slays and clamps for sand cast iron centrifugally cast spun iron	32	sqm			

Job No. 12

13	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour waste coupling 31 mm dia of 79 mm length and 62mm breadth weighing not less than 45 cms	8	sqm			
14	p/f 3layers PR=R pipes conforming to IS 15801 UV stabilized and anti microbial fusion welded having thermal stability for hot and cold water supply complete as per direction of Engineer in Charge.	80	sqm			
15	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.	224	sqm			
16	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore	8	sqm			
17	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 .15 mm nominal bore	8	sqm			
18	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge.	8	sqm			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Rohru

Job No. 11

## Schedule of Qty

Name of Work :- A/R & M/O staff quarter at Rohru				ESTIMATED COST	
SH:- P/F water Storage tank for staff Quarter				EARNEST MONEY	479764
				TIME LIMIT:	9595
					Two Months
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	Amount. In Words
1	2	3	4	5	6
1	Steel work welded in built up sections, trusses and framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts :-In gratings, framed, guards, bars ladders and railing, brackets and similar works :-	10.8	kg		7
2	Providing and placing PVC water tank make double layer having capacity of 1000 liters (Five hundred liters) each tank necessary fittings including over flow pipe scour pipe etc and pads required for in let and out let and inside painting ball valve with cover and locking arrangements including painting of good quality complete in all respect within all leads, lifts of materials including hoisting and other incidentals.	8.262	no		
3	Making connection of galvanized steel distribution branch with galvanized mild steel main 15mm to 40mm nominal bore by providing and fixing tee including cutting and threading the pipes complete. Including carriage of materials within all leads, lifts and other incidentals.	2698.6	rmt		
	Total				

  
 Executive Engineer  
 B&R Division HPPWD  
 Rohru



10.6.2012

**Name of Work:-C/o Govt PG Degree Collage Seema.**

**Schedule of Qty**

Sh:- C/o Play ground Pedestal in R/R masonry 1:6 towards valley side at RD 0/00 to					ESTIMATED COST		474157
Sr. No					EARNEST MONEY		9483
Description of items.					TIME LIMIT:		2 Months
1	2	Qty	Unit	Rate	In Words	Amount.	
1		3	4	In Fig.	6	7	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-I or as directed by the Engineer-In-Charge.	5	cum	5			
2	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement motar(1:6) including carriage of materials with in all leads and lifts as per direction of Engineer-in-Charge.	90.63	cum				
Total							

  
Executive Engineer  
B&R Division HPPWD  
Rohru

**Schedule of Qty**

**Name of Work:-C/o Govt PG Degree Collage Seema.**

**Sh:- C/o B/wall in RR Masonery 1:6 at near Auditorium building RD 0/00 to 0/024**

				ESTIMATED COST	
				EARNEST MONEY	461685
				TIME LIMIT:	9234
					2 Months
Sr. No	Description of items.	Qty	Unit	Rate	Amount.
				In Fig.	
				In Words	
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	32.88	cum		7
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-in-Charge.	23.28	cum		
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clause 702.704.1202 and 1204 Random rubble masonry in cement mortar (1:6) including carriage of materials with in all leads and lifts as per direction of Engineer-in-Charge.	85.68	cum		
Total					

  
Executive Engineer  
B&R Division HPPWD  
Rohru

Job No. 14


# Schedule of Qty

Name of Work :- C/o Govt PG Degree Collage Seema.

SH:- C/o Play Ground U-Shape Drain in PCC 1:2:4 at RD 0/00 to 0/075(Entrance Side)

Description of items.

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		
				EARNEST MONEY		464809
				TIME LIMIT:		9296
1	2			Rate In Fig.	In Words	Two Months
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	3	4	5	6	Amount. 7
		94.5	cum			
2	Plain/Reinforced cement concrete in open foundation complete as per drawing and technical specification M20 PCC 1:2:4	57.38	cum			
	Total					

  
Executive Engineer  
B&R Division HPPWD  
Rohru



106 No. 15

**SCHEDULE OF QUANTITY**

Estimated cost Rs 497324/-  
 Eareast Money Rs9946/-  
 TIME : Two month

Name of work - R/R damages to RCD road km 2/0 to 21/195 (SH- C/O R/wall in PCC 1:3:6 at RD 9/165 to 9/174).

Sr. No	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge	11.97			per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	16.74			per cubic metre	
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	6.39			per cubic metre	
4	Providing concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specification clause 803.803, 1202 and 1203 grade 1:3:6 (1 cement 3 sand 6 graded stone aggregate within all leads and lifts as per directions of Engineer in charge	62.28			per cubic metre	
5	Providing weepholes in brick masonry/stone masonry /plain concrete abutment wing wall return wall 100mm dia A.C. pipe extending through the full width of the structures with slope of 1(V)/20(H) thorough drawing tasc complete as per drawing and technical specification clause 614.709. 1204 3.7 within all leads and lifts as per directions of Engineer in charge	21.00			Each	
6	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carriage of materials as per direction of Engineer in charge	14.40			per cubic metre	
	Total:-				Total	

Executive Engineer  
 B&R Divn HP, PWD  
 Rohnu

# SCHEDULE OF QUANTITY

Estimated cost Rs 136935/-  
Earens money Rs 3278/-  
Time :- One Month

Job No. 16

Name of work : -A/R & M/O PWD REST House & circuit House at Rohru(SH-Repairing of Furniture)

Sr No.	Sub-head and item of works.	Quantity.	Rate in figures.	Rate in words	Unit.	Amount
1	upbolstering reshtifting of sofa set/seats/using 2 thick sleep weel (32density)/with quality from sheets nad back fixing padding with clla and latest with superior quality trans cloth in proper position including cost of stitching materials sets sheeps well 40density size 500055 100 including necessary repar of wood polishing complete as per PWD wood polishing complete as per PWD specification including carriage of materils with in all leads and lifts as other incidents within all leads and lifts as per directions of Engineer in charge	65.00			Each	
2	upholstfering sofa chair and back with making of lapsesstry colth cutting the shape and fixing etc including properly scrring spenings in position with twins U hooks and came stick etc fixing coir and cotton/latest forin rubber of approved quality the sheet and back all complete including carrie of materils within all leads and lifts as per directions of Engineer in chage	35.00			per running metre	
3	Drring stool	9.00			Each	
4	Dry cleaning of mats properly as per directions of Engineer in charge including all leads and lifts of materils complete.	361.8			per sqm	
	Total					

Executive Engineer  
B&R Division HP-PWD  
Rohru



# SCHEDULE OF QUANTITY

Estimated cost Rs 495761/-  
 Earnest Money Rs 9995/-  
 TIME : Two month

Name of work - R/R damages Samoli Bhatwari road km 0/0 to 7/0(SH- C/O R/wall at wall in PCC 1:4:8 at RD 3/450 to 3/470.50).

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge	20.09			per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	18.86			per cubic metre	
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	11.89			per cubic metre	
4	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 25 mm specification clauses 802.803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	68.88			per cubic metre	
5	Providing weepholes in brick masonry/stone masonry /plain concrete abutment wing wall return wall 100mm dia AC pipe extending through the full width of the structures with slope of 1(V)/20(H) through drawing fasce complete as per drawing and technical specification clause 614.709.1204 3.7 within all leads and lifts as per directions of Engineer in charge	38.00			Each	
6	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carriage of materials as per direction of Engineer in charge	22.75			per cubic metre	
	Total:-				Total	

Executive Engineer  
 B&R Divn HP PWD  
 Rohru

Job No. 17



# SCHEDULE OF QUANTITY

Name of work:- C/O link road from Sandhasu to Shishara (HB)Dokoti Paja road km 0/0 to 3/522)

Estimated cost Rs 487022/-  
Earnest money Rs 9740/-  
Time :- Two month

SINO.	Sub-Head/Item of work.	Quantity	Rate		Unit.	Amount.
			In Figures.	In Words		
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage. disposal of unsuitable cut material in specified manner, trimming/filling of unevenness blindage and finishing of the road to specified diamensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made @300/-per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	2299.72			per cubic metre	
Total:-						

Executive Engineer  
B&R Divn HP, PWD  
Rohru

G. b. N. 18

Job No. 19

Estimated cost Rs 497324/-  
Earens Money Rs9946/-  
TIME : Two month

SCHEDULE OF QUANTITY

Name of work - R/R damages to RCD road km 2.0 to 21/195 (SH- C/O R/wall in PCC 1:3:6 at RD 9/135 to 9/164)					
Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge	11.97			per cubic metre
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	16.74			per cubic metre
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	6.39			per cubic metre
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 803.803.1202 and 1203 grade 1:3:6 (1cement 3sand 6graded stone aggregate within all leads and lifts as per directions of Engineer in charge	62.28			per cubic metre
5	Providing weepholes in brick masonry/stone masonry plain concrete abutment wing wall return wall 100mm dia AC pipe extending through the full width of the structures with slope of 1(V)20(H) through drawing face complete as per drawing and technical specification clause 614.709.1204.3.7 within all leads and lifts as per directions of Engineer in charge	21.00			Each
6	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carriage of materials as per direction of Engineer in charge	14.40			per cubic metre
Total:-					Total

Executive Engineer  
B&R Divn HP.PWD  
Rohru