

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated **24.09.2022** up to **10.30AM** and the same will be opened on the same day at **11.30AM** in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to **4.00 PM** on dated **22.09.2022** and tender forms can be obtained from this office against cash payment (nonrefundable) on **23.09.2022 (4.00PM)** and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to reject tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	A/R & M/O various roads under Dada siba Sub Division (Sh: Repair of Pot Holes on various road) (Job No. 1).	499990	10000	Two Month	350	6&8
2	A/R & M/O various roads under Dada siba Sub Division (Sh: Repair of Pot Holes on various road) (Job No. 2).	499990	10000	Two Month	350	6&8
3	Restoration of Rain damages on JhurniMour (ChintpurniTalwara road) to Nangal via sunhet road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 0/558 to 0/567.48).	498711	10000	Three Month	350	6&8
4	Restoration of Rain damages on JhurniMour (ChintpurniTalwara road) to Nangal via sunhet road Km 0/0 to 3/600 (SH:- C/o Wire Crate at RD. 1/160 to 1/170.80).	494714	10000	Three Month	350	6&8
5	Restoration of Rain damages on JhurniMour (ChintpurniTalwara road) to Nangal via sunhet road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 1/020 to 1/027 , 1/320 to 1/328 & 1/525 to 1/533).	498621	10000	Three Month	350	6&8
6	Construction of link road from main road to BariyalBehar Km. 0/0 to 2/600 (SH:- C/o 5/7 mtr. Wide formation cutting in Km. 0/0 to 0/680) (Under SCSP).	497073	10000	Three Month	350	6&8
7	Construction of link road from Kotla Behar GhattiBilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- Const. of 900 mm dia Hume pipe culvert at RD. 0/375 and 1/030) (Under Industrial Corridor).	238225	5000	Two Month	350	6&8
8	Improvement of road from Ririkut to Tlapien di Sarain Km. 0/0 to 2/600 (SH:- C/o Retaining wall at RD. 1/870 to 1/890) (Under Industrial Corridor).	434880	9000	Three Month	350	6&8
9	Improvement of road from Ririkut to Tlapien di Sarain Km. 0/0 to 2/600 (SH:- C/o Breast wall at RD. 1/015 to 1/045 and 1/780 to 1/805) (Under Industrial Corridor)	492327	10000	Three Month	350	6&8
10	Improvement& widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of Retaining wall at RD. 0/0 to 0/010 ,1/190 to 1/198 & 2/220 to 2/228) (Under Industrial Corridor).	492920	9000	Three Month	350	6&8
11	Construction of 19.75 Metre Sapn RCC T-Beam Bridge over Nari Khad at RD. 1/335 on Barnali to upper Nari road Km. 0/0 to 3/650 (SH:- C/o Cement Concrete Pavement at RD 3/200 to 3/325) (Under Industrial Corridor).	495938	10000	Three Month	350	6&8
12	Improvement& widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of U-Shape PCC Drain at RD. 1/00 to 1/390) (Under Industrial Corridor).	499977	10000	Three Month	350	6&8

13	Improvement & widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of U-Shape PCC Drain at RD. 1/975 to 2/365) (Under Industrial Corridor).	499977	10000	Three Month	350	6&8
14	Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 0/0 to 0/200) (Under Industrial Corridor).	491544	10000	Three Month	350	6&8
15	Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 0/450 to 0/600) (Under Industrial Corridor).	496360	10000	Three Month	350	6&8
16	Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 0/650 to 0/800) (Under Industrial Corridor).	497220	10000	Three Month	350	6&8
17	Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 1/500 to 1/800) (Under Industrial Corridor).	492270	10000	Three Month	350	6&8
18	Restoration of rain damages on Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace road Km. 22/200 to 60/920, MDR-46 (SH:- C/o Wire Crate in between Km. 22/200 to 32/200).	498758	10000	Three Month	350	6&8
19	A/R & M/O Pirsluhi to Rakkar via Sitpak Km. 0/0 to 2/200 (SH:- ROFD in Km. 1/540 to 1/620, C/o Breast wall at RD. 4/320 to 4/350 and V-shape Drain at RD. 4/160 to 4/216)	496569	10000	Three Month	350	6&8
20	Construction of Barnali to upper Nari via lower Nari road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 2/795 to 2/824) (RHS) (Under Industrial Corridor).	495608	10000	Three Month	350	6&8
21	Construction of Barnali to upper Nari via lower Nari road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 2/797.20 to 2/826.20) (LHS) (Under Industrial Corridor).	497258	10000	Three Month	350	6&8
22	A/R & M/O Pucca Tiala Mehre road Km. 0/0 to 11/150 (SH:- C/o Retaining wall at RD. 6/250 to 6/260).	258248	5000	Three Month	350	6&8
23	Construction of Health Institution Level -II Building at Dada Siba, Tehsil Dada Siba, Distt Kangra HP (SH:- Balance work of W.S.&S.I, M.S. Window wire gauge shutters, S.S. Railing and Plaster work Etcetra)	499146	10000	Three Month	350	6&8
24	Construction of Health Institution Level -II Building at Dada Siba, Tehsil Dada Siba, Distt Kangra HP (SH:- Providing and fixing Door Shutters and misc. works etcetra)	485118	10000	Three Month	350	6&8
25	Balance work for the C/O Rain shelter beside Path/road near Biyal Baba Temple Near Muhin in G.P. Muhin.	316106	7000	Three Month	350	6&8
26	A/R & M/O Gopipur to Chamukha road Km. 6/0 to 12/590 (SH:- C/o Retaining wall at RD. 6/501 to 6/553)	413631	8000	Three Month	350	6&8
27	Restoration of Rain damages on Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace road Km. 0/00 To 9/00, MDR-46 (SH:- C/O Retaining wall at RD 1/510 To 1/527.20)	498087	10000	Three Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest,

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER/2022-23---4235-44

DATED 14.09.2022

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.


Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

CERTIFICATE

Certified that tenders called vide this office Notice No PWD/KB/CB/Tender /2022-23 - 4235-44 dated 14.09.2022 for 27 Nos. Job are hereby invited without press notice due to exigencies / emergency of work in the public interest


Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

JOB NO 1

Estimate Cost :- Rs.4,99,990.00
Earnest Money :-Rs. 10000.00
Time Limit :- Two Month.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Dada siba Sub Division (Sh: Repair of Pot Holes on various road) (Job No. 1).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Providing laying, spreading by mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, crushed stone aggregates of Grading-II, 63mm to 45mm (sixty three millimeter to forty five millimeter) nominal size to water bound macadam specification including spreading in uniform thickness using templates, hand packing rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming with stone screening Type-B of size 11.2mm (Eleven point two millimetre) nominal size at the rate of 0.20 (zero point two zero) cubic meter per 10 Sqm. (ten square metre) and binding material at the rate 0.06cum (Zero point zero six cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical specification clause 405 and as per direction and satisfaction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	7.20	Cubic metre	Per cubic metre		
Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government. The rate is including Royalty, Malkana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	1505.20	Square metre	Per Square metre		
TOTAL					

Executive Engineer,
HPPWD Division,
Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 2

Estimate Cost :- Rs.4,99,990.00

Earnest Money :-Rs. 10000.00

Time Limit :- Two Month.

Name of work:- A/R & M/O various roads under Dada siba Sub Division (Sh: Repair of Pot Holes on various road) (Job No. 2).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Providing laying, spreading by mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, crushed stone aggregates of Grading-II, 63mm to 45mm (sixty three millimeter to forty five millimeter) nominal size to water bound macadam specification including spreading in uniform thickness using templates, hand packing rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming with stone screening Type-B of size 11.2mm (Eleven point two millimetre) nominal size at the rate of 0.20 (zero point two zero) cubic meter per 10 Sqm. (ten square metre) and binding material at the rate 0.06cum (Zero point zero six cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical specification clause 405 and as per direction and satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	7.20	Cubic metre		Per cubic metre	
Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government. The rate is including Royalty, Malkana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	1505.20	Square metre		Per Square metre	
TOTAL					

Executive Engineer,
HPPWD Division,
Kotla Behar.

JOB NO 3

Estimate Cost :- Rs. 4,98,711/-

Earnest Money :-Rs.10000/-

Time Limit :-Three Months.

Name of work:- Restoration of Rain damages on Jhurni Mour (Chintpurni Taiwara road) to Nangal via sunhet road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 0/558 to 0/567.48).

SCHEDULE OF QUANTITY

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and cleaning of slush which may arise out during (surface and sub-soil water) up to any depth and any quantum of water and pumping or bailing out water dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	48.15	Cubic metre		Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	138.11	Cubic metre		Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	22.75	Cubic metre		Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	54.00	Number		Each	
TOTAL					

Executive-Engineer,
HPPWD Division,
Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 4

Estimate Cost :- Rs. 4,94,714/-

Earnest Money :-Rs.10000/-

Time Limit :-Three Months.

ne of work:- Restoration of Rain damages on Jhurni Mour (Chintpurni Talwara road) to Nangal via sunhet road Km 0/0 to 3/600 (SH:- C/o Wire Crate at RD. 1/160 to 1/170.80).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	56.70 Cubic metre			Per Cubic metre	
Providing and laying of boulder apron Gabion wall laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm (One hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (Ten) per cent extra for laps and joints laid with stone boulders weighing not less than 40kg (Forty kilogramme) each as per drawing and MORD technical specifications Clause 1301 and as per direction and the entire satisfaction of the Engineer-in-Charge including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	187.40 Cubic metre			Per Cubic metre	
TOTAL					

Executive Engineer,
HPPWD Division,
Kotla Behar.

JOB NO 5

Estimate Cost :- Rs. 4,98,821/-

Earnest Money :-Rs.10000/-

Time Limit :-Three Months.

e of work:- Restoration of Rain damages on Jhurni Mour (Chintpurni Talwara road) to Nangal via sunhet road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 1/020 to 1/027 , 1/320 to 1/328 & 1/525 to 1/533).

SCHEDULE OF QUANTITY

Description of Item

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	63.56 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	133.50 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.12 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204,3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	69.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

JOB NO. 6

Estimate Cost :- Rs.4,97,073.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

SCHEDULE OF QUANTITY

Work:- Construction of link road from main road to Bariyal Behar Km. 0/0 to 2/600 (SH:- C/o 5/7 mtr. Wide formation cutting in Km. 0/0 to 0/580) (Under SCSP).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, width, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in according to MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 68.69 cubic metre quantity at the rate of Rs. 300/- only (Rupees three hundred only) per cubic meter shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	2686.88	Cubic metre	Per Cubic metre		
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

Estimate Cost :- Rs.2,38,225.00

Earnest Money :-Rs. 5000.00

Time Limit :- Two Month.

SCHEDULE OF QUANTITY

of work:- Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- Const. of 900 mm dia Hume pipe culvert at RD. 0/375 and 1/030) (Under Industrial Corridor).

Description of Item	Quantity			Unit	Amount
		Figures	Words		
Earth work in excavation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	77.02 Cubic metre		Per Cubic metre		
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 3:6 (one cement isto three sand isto six graded crushed stone aggregate 40mm (forty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	3.78 Cubic metre		Per Cubic metre		
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) with minimum Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate 40mm (forty millimeter) nominal size) in Cradle bedding and toe wall etc or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, for foundation and plinth and concrete cradle bedding Type-A under pipe and the like, etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 clauses 101.5 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	2.54 Cubic metre		Per Cubic metre		
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in open foundation or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in open foundation etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	27.76 Cubic metre		Per Cubic metre		

providing and laying (to level or slope) 900mm dia (Nine hundred millimeter) diameter reinforced cement concrete light duty pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (One cement to two sand) but excluding the cost of excavation, protection works, back filling, pipe bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101.5 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST, toll tax, sale tax or other taxes imposed by the Government.	15.00 Running metre	Per running metre	
providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal size 1:2:4 (one cement to two sand to four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	0.44 Cubic metre	Per Cubic metre	
earth filling (for marshy soil) in foundation, trenches and the like for Earth cushion over Hume pipe culverts etcetera with earth obtained from Approved quarry approved by Engineer-in-Charge including thoroughly watering ramming/ compacting with suitable equipment, in layers not exceeding 150mm (One Hundred fifty millimeter) in thickness complete as per MORD technical specification as per clause 305.3.9 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, octroi, toll tax, sale tax or any other taxes imposed by the Government.	15.30 Cubic metre	Per Cubic metre	
TOTAL			

Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 8

Estimate Cost :- Rs. 4,34,880/-

Earnest Money :-Rs. 9000/-

Time Limit :-Three Months.

Name of work:- Improvement of road from Ririkut to Tlapian di Sarain Km. 0/0 to 2/600 (SH:- C/o Retaining wall at RD. 1/870 to 1/890) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water' up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	45.00 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including most of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 900, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	118.20 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	30.00 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V). 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204,3.7 and as per the direction and entire satisfaction of engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	36.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 9


Estimate Cost :- Rs. 4,92,327/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

of work:- Improvement of road from Ririkut to Tiapian di Sarain Km. 0/0 to 2/600 (SH:- C/o Breast wall at RD. 1/015 to 1/045 and 1/780 to 1/805) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	86.35 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 900, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	140.10 Cubic metre			Per cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	50.00 Number			Each	
TOTAL					


 Executive Engineer,
 Kotla Behar Division,
 P.P.P.W.D. Kotla Behar.

JOB NO 10

Earnest Money :-Rs. 9000/-

Time Limit :-Three Months.

of work:-	Improvement & widening of Dehra Ghatti to village Bari road	Km. 0/0 to 2/495 (SH:- Const. of Retaining wall at RD. 0/0 to 0/010 ,1/190 to 1/198 & 2/220 to 2/228)	(Under Industrial Corridor)	Time Limit	:-Three Months.

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix of soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the other dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during watering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	65.00 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 0, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	137.00 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, I.T. toll tax, sale tax or any other taxes imposed by the Government.	17.00 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	51.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
UPPWD Kotla Behar.

JOB NO. 11

Estimate Cost :- Rs.4,95,938.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

of work:- Construction of 19.75 Metre Sapn RCC T-Beam Bridge over Nari Khad at RD. 1/335 on Barnali to upper Nari road Km. 0/0 to 3/650 (SH:- C/o Cement Concrete Pavement at RD 3/200 to 3/325) (Under Industrial Corridor).

SCHEDULE OF QUANTITY

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded washed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open undation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all roads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	18.75 Cubic metre			Per Cubic metre	
providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	75.00 Cubic metre			Per Cubic metre	
TOTAL					

Executive Engineer,
Kotla Behar Division,
MPBWD Kotla Behar.

JOB NO. 12

Estimate Cost :- Rs. 4,99,977.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

of work:- Imprpovement & widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of U-Shape PCC Drain at RD. 1/00 to 1/390) (Under Industrial Corridor).

SCHEDULE OF QUANTITY

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks etc. (blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water from face and sub soil water' up to any depth any quantum of water including cleaning of slush which may arise out during watering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	190.12	Cubic metre	Per Cubic metre		
providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, nominal mix 1:3:6 (one cement three sand into six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open excavations for all Type of structure, such as Drains and the like including pumping or bailing out water/ dewatering removal of slush which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	102.38	Cubic metre	Per Cubic metre		
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

JOB NO. 13

Estimate Cost :- Rs. 4,99,977.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

SCHEDULE OF QUANTITY

of work:- Improvment & widening of Dehra Ghatti to village Bari road Km. 0/0 to 2/495 (SH:- Const. of U-Shape PCC Drain at RD. 1/975 to 2/365) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1503 as per direction of entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during watering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and s and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed the Government	190.12 Cubic metre			Per Cubic metre	
providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, nominal mix 1:3:6 (one cement to three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundations for all Type of structure, such as Drains and the like including pumping or bailing out water/ dewatering removal the slush which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST any other taxes imposed by the Government.	102.38 Cubic metre			Per Cubic metre	
TOTAL					

Executive Engineer,
Kotla Behar Division,
APPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 14

Estimate Cost :- Rs. 4,91,544/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

Work:- Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 0/0 to 0/200) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	65.20	Cubic	metre	Per Cubic metre	
providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government	138.00	Cubic	metre	Per cubic metre	
back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	12.00	Cubic	metre	Per Cubic metre	
providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709, 1204.3.7 and as per the direction and entire satisfaction of engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	50.00	Number		Each	
TOTAL					

Executive-Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 15

Estimate Cost :- Rs. 4,96,360/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

Item of work:- Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 0/450 to 0/600) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	67.00 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 900, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	139.00 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, SST, toll tax, sale tax or any other taxes imposed by the Government.	13.00 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	51.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
APPWD Kotla Behar.

JOB NO 16

Estimate Cost :- Rs. 4,97,220/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

of work:- Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 0/650 to 0/800) (Under Industrial Corridor).

SCHEDULE OF QUANTITY

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, rapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix l, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the es and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and er deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and tform and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during watering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire tisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand o ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast ill and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including st of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 0, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials thin all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any er taxes imposed by the Government. back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge luding carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, ST, toll tax, sale tax or any other taxes imposed by the Government. providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone assonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through a full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as r drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including yality, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	68.50 Cubic metre			Per Cubic metre	
	139.50 Cubic metre			Per cubic metre	
	12.00 Cubic metre			Per Cubic metre	
	50.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
UPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 17

Estimate Cost :- Rs. 4,92,270/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

of work:- Construction of link road from Kotla Behar Ghatti Bilwan road to village Khanour up to Chowki Di Bar Km. 0/0 to 2/200 (SH:- C/o Retaining wall at in between RD. 1/500 to 1/800) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix of soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during watering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	68.50 Cubic metre			Per Cubic metre	
providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 0, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	138.00 Cubic metre			Per cubic metre	
back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	12.00 Cubic metre			Per Cubic metre	
providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	50.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
PPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 18
Estimate Cost :- Rs. 4,98,758/-
Earnest Money :-Rs.10000/-
Time Limit :-Three Months.
of work:- Restoration of rain damages on Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace road Km. 22/200 to 60/920, MDR-46 (SH:- C/o Wire Crate in between Km. 22/200 to 32/200).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix of soil, ordinary rock, hard rock, chiseling, wedging out rocks (where blasting is prohibited) complete in accordance with the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during watering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	84.50	Cubic	metre	Per Cubic metre	
providing and laying of boulder apron Gabion wall laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm (One hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (Ten) per cent extra for laps and joints laid with stone boulders weighing not less than 40kg (Forty kilogramme) such as per drawing and MORD technical specifications Clause 1301 and as per direction and the entire satisfaction of the Engineer-in-Charge including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, alkhalana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	184.68	Cubic	metre	Per Cubic metre	
TOTAL					

Executive Engineer,
HPPWD Division,
Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 19
 Estimate Cost :- Rs. 4,96,569/-
 Earnest Money :-Rs. 10000/-
 Time Limit :-Three Months.

of work:- A/R & M/O Pirsluhi to Rakkar via Sitpak Km. 0/0 to 2/200 (SH:- ROFD in Km. 1/540 to 1/620 , C/o Breast wall at RD. 4/320 to 4/350 and V-shape Drain at RD. 4/160 to 4/216)

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, width, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in accordance to MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 6.00 cubic metre quantity at the rate of Rs. 300/- only (Rupees three hundred only) per cubic meter shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	261.00 Cubic metre			Per Cubic metre	
Earth work in excavation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix oil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	69.10 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 00, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	107.40 Cubic metre			Per cubic metre	

providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government	50.00 Number			Each	
providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, nominal mix 1:3:6 (one cement three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundations for all Type of structure, such as Drains and the like including pumping or bailing out water/ dewatering removal of slush which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.12 Cubic metre			Per Cubic metre	
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 20
Estimate Cost :- Rs. 4,95,508/-
Earnest Money :-Rs. 10000/-
Time Limit :-Three Months.
Work of work:- Construction of Barnali to upper Nari via lower Nari road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 2/795 to 2/824) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the sizes and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during watering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including most of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 0, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government. rock filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government. providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through a full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	40.31 Cubic metre			Per Cubic metre	
	131.50 Cubic metre			Per cubic metre	
	43.50 Cubic metre			Per Cubic metre	
	62.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
CHPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 21


Estimate Cost :- Rs. 4,97,258/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

of work:- Construction of Barnali to upper Nari via lower Nari road Km 0/0 to 3/600 (SH:- C/o Retaining wall at RD. 2/797.20 to 2/826.20) (LHS) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the sizes and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	40.31 Cubic metre			Per Cubic metre	
providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 100, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	132.00 Cubic metre			Per cubic metre	
rock filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	43.50 Cubic metre			Per Cubic metre	
providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through a full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	62.00 Number			Each	
TOTAL					


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 22
Estimate Cost :- Rs. 2,58,248/-
Earnest Money :-Rs. 5000/-
Time Limit :-Three Months.
Name of work:- A/R & M/O Pucca Tiala Mehre road Km. 0/0 to 11/150 (SH:- C/o Retaining wall at RD. 6/250 to 6/260).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	271.20 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 900, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	56.32 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	6.32 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
SIPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 23

Estimate Cost :- Rs. 4,99,146/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

of work:- Construction of Health Institution Level-III Building at Dadasiba, Tehsil Dadasiba, Distt. Kangra HP (SH:- Balance work of W. S. & S.I., M.S. Window wire gauge shutters, S.S. Railing and Plaster work Etcetra)

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
providing, laying and fixing in trenches 75mm (Seventy five millimeters) diameter Poly Vinyl Chloride (D-plast or equivalent) pipes of working pressure not less than 4.5 Kg (Four point five Kilogramme) per square meter including filling the joints with approved adhesive complete as per HPPWD specifications and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	126.10			Running metre	
providing and fixing P.V.C. Plain Bend 75mm (Seventy five millimetre) nominal diameter ISI marked including fixing with approved adhesive etcetra complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	64.00			Each	
providing and fixing 75mm (Seventy five millimeter) diameter PVC (Polyvinyl chloride) Door Bend with oval access door ISI marked make of Supreme/Finolex Relpipe (Reliance) Vectus with insertion rubber washer, 3mm (three millimeter) thick bolts and nuts, including testing of pipes and joints complete as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00			Each	
providing and fixing 75mm (Seventy five millimetre) nominal diameter P.V.C. Tee with oval access door ISI marked including fixing with approved adhesive etcetra complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00			Each	
providing and fixing 75mm (Seventy five millimetre) nominal diameter PVC Tee ISI marked including fixing with approved adhesive etcetra complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	26.00			Each	
providing and fixing wire gauge shutters using galvanized M.S. Wire gauge of IS gauge designation 85G (eighty five galvanized) with wire of diameter 0.56mm (Zero decimal five six millimetres) for steel glazed windows and ventilators of various type categorized etcetra complete with all accessories as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.00			Each	
providing and fixing wire gauge shutters using galvanized M.S. Wire gauge of IS gauge designation 85G (eighty five galvanized) with wire of diameter 0.56mm (Zero decimal five six millimetres) for steel glazed windows and ventilators of various type categorized etcetra complete with all accessories as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	63.49			Square metre	

viding and fixing of expansion joint system related with wall joint internal external location as per drawing and direction of Engineer-in-charge. The joints shall be filled with polystyrene back or rod base members self aligning centering arrangement and support. The material shall be a such that it provides an expansion joints system suitable for vertical wall to wall/wall to corner application both new and existing construction in office building and complexes with no slipping down tendency almost the component of the joint system. The joint system shall utilized light weight with polystyrene back a rod surfaces mechanically shaping the multicellular to facilitate movement as per approved drawing, design, specification and as per the direction of Engineer-in-charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.40			Running metre	
viding and fixing of 40mm (Forty millimeter) diameter SST (Stainless steel) pipe hand rail fixed with in combination of 35mm (thirty five millimeter) diameter and 15/20 (Fifteen oblique twenty millimeter) SST (Stainless steel) pipe of three row between step railing in equal space and jointed with electric gas welding at top along with 40mm (Forty millimeter) diameter hand rail fitting in steps as per specification, approved drawing, design and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	13.60			Running metre	
er the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	213.70			cubic metre	
viding and fixing 50mm (Fifty millimeter) diameter mild steel pipe hand rail slip resistant at Two levels as 75cm (Seventy five centimeters) and 90cm (ninety centimeters) height with round ends and 25mm (Twenty five millimeter) diameter mild steel hollow balusters of 14 to 16 (fourteen to sixteen) gauge 60cm (Sixty centimeters) centre to centre welded at top with hand rail and bedded in reinforced cement concrete parapet including painting with red lead paint after the treatment of metal surface complete as per approved design and drawing as specified and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	36.05			Running metre	
viding and fixing vitreous china 600x450x250mm (Six hundred into four hundred fifty into two hundred fifty millimeter) laboratory sink of ISI mark of approved brand of Hindware/Jaquar/Cera/Star white/Snow white shade including cutting and fitting in wall and making good the same and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00			Each	
viding and fixing 15mm dia (Fifteen millimeter) diameter C.P. (Chromium Plated) Arm Operated long body Brass Bib tap with stand head manufacture of Continental series of Jaquar/classic series of Hindware/ Floral series of Cera, as per specification, approved drawing design complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00			Each	
viding and fixing PTMT waste coupling of approved quality and colour 32mm (Thirty two millimeter) nominal bore as per specification, approved drawing design as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00			Each	
viding and fixing 32mm (thirty two millimeter) nominal diameter PVC waste pipe for washbasin or sink including brass check complete of continental series of Jaquar/Classic Series of Hindware/Floral series of Cera as per direction and entire satisfaction of Engineer -In-Charge including carriage of materials within all leads, lifts and other incidentals including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	11.00			Each	

providing and fixing ISI marked, 100mm (One hundred millimeter) dia. C.P grating manufacture Continental series of Jaquar/Classic series of Hindware/Floral series of Cera for gully, floor or Nahni trap complete as per HPPWD specifications, as per direction and entire satisfaction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, or any other taxes imposed by the Government	11.00			Each	
providing and fixing ISI marked 45cm (forty five centimeters) long and 15mm (fifteen millimeters) nominal bore PVC connection with brass unions of Continental Series of Jaquar/Classic series of Hindware/ Floral series of Cera complete as per HPPWD specifications and as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.00			Each	
providing and fixing 20mm (Twenty millimeter) nominal bore High pressure with polythene plastic floats brass ball valve horizontal plunger type) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty malkhana, tax, sale tax, GST or any other taxes imposed by the Government.	4.00			Each	
providing and fixing 25mm (Twenty five millimeter) nominal bore High pressure with polythene plastic floats brass ball valve horizontal plunger type) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, royalty malkhana, tax, sales tax, GST or any other taxes imposed by the Government	4.00			Each	
providing and fixing CP (Chromium Plated) brass Jet spray manufacture of Continental series of Jaquar/Classic series of Hindware/ Floral series of Cera/ Vintage series of Kerovit shade with one meter tube as per approved drawing, design, specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	11.00			Number	
providing and fixing 100mm (one hundred millimeter) aluminium door stopper with rubber cushion screw etc to suit shutter thickness complete as per HPPWD specifications and as per the direction of Engineer-in-Charge including carriage of materials within all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	50.00			Each	
providing and fixing 75 millimetre diametre stainless steel flanges as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, tax, GST and any other taxes imposed by the Government.	40.00			Each	
providing and fixing cast iron cover (light duty) single seal 300x300mm (Three hundred into three hundred millimeter) internal provision as per approved drawing, design, specifications and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00			Each	
priming two or more coats (excluding priming coat) on new wood and wood based surfaces with ready mixed paint other than white of approved brand and manufacture of Narolac/Asian and of approved shade to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per HPPWD specifications and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, tax, GST and any other taxes imposed by the Government.	360.00			Square metre	
providing edge/half round moulding to all type of finishing stone like red Sand/marble/granite stone counters, vanities etcetra including achine polishing to edge to give high gloss finish etcetra complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	139.43			Running metre	

providing and fixing to wall ceiling and floor ISI marked 20mm(twenty millimeter) nominal bore galvanized mild steel tubes (medium Grade) of approved brand and manufacture (TATA JINDAL MAKE) Complete tube fittings and clamp including making of the wall, ceiling and floor complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	58.57			Running metre	
providing and fixing to wall ceiling and floor ISI marked 25mm(twenty five millimeter) nominal bore galvanized mild steel tubes (medium Grade) of approved brand and manufacture (TATA JINDAL MAKE) complete tube fittings and clamp including making of the wall, ceiling and floor complete and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	74.96			Running metre	
excavation in drains and channels etcetra in earth work in ail kind of classification of soil such as pick work, jumper work pick-per work, blasting work, soft and hard blasting and saturated soil, including chiselling or wedging out rocks where blasting work is prohibited or any other mixed variety or soil including shoring, strutting, de-watering and pumping or baling out water surface and Sub soil water) upto any depth or any quantum of water including slush which may arise during de-watering or removal of slush, lift upto any height stacking the excavated soil clear from the edge of excavation and then returning the stacked soil in 15cm (fifteen centimeter) layers when required into plinths, Sides of foundation etcetra consolidating each deposited layer ramming, watering and then disposing or all surplus excavated earth complete and direction of the Engineer-in Charge including carriage of material within all leads and lifts and other incidentals. The rates is inclusive of octroi, royalty, malkhana, toll tax, GST and any other taxes as imposed by the Government	7.00			cubic metre	
mm (Fifteen millimetre) thick cement plaster Pattern in plaster with 12mm (Twelve millimetre) groove with cement mortar 1:4 (one cement isto four sand) in single coat on plastered surface upto all floor level, including arrises internal rounded angles, chamfers and/or rounded angle in all girth and finished even and smooth complete as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	73.33			Square metre	
mm (Fifteen millimetre) thick cement plaster Pattern in corner with 10mm (ten millimetre) groove with cement mortar 1:4 (one cement isto four sand) in single coat on plastered surface upto al floor level, including arrises internal rounded angles Chamfers and/or rounded angle in all girth and finished even and smooth complete as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	30.24			Square metre	
providing and fixing 125mm (One hundred twenty five millimetre) oxidized M.S. (Mild steel) Handles with the necessary screws complete as per HPPWD specifications and as directed by the Engineer-In-Charge, including carriage or materials within all leads, lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	316.00			Each	
providing and fixing 200x10 mm (Two Hundred into ten millimetre) oxidized M.S. (Mild steel) Tower Bolts (Barrel type) with the necessary screws etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage or materials within all leads, lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	158.00			Each	

providing and fixing 65x35mm (sixty five into thirty five millimetres) (special quality bright finished brass cup board locks or ward be locks with six levers including necessary screws etc complete (Indian make of approved quality as per HPPWD specifications as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. the rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.00			Each	
--	-------	--	--	------	--

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 24

Estimate Cost :- Rs. 4,85,118/-

Earnest Money :-Rs. 10000/-

Time Limit :-Three Months.

Name of work:- Construction of Health Institution Level-III Building at Dadasiba, Tehsil Dadasiba, Distt. Kangra HP (SH):- Providing and fixing Door Shutters and misc. works
 etetra) Balance work

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Providing and fixing 40mm (forty millimeter) thick second class deodar wood panelled glazed or panalled and glazed shutter for doors, Window and clerestery windows including 12mm thick both side prelaminated water proof parical board of Action	15.76			Square metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	69.62			Square metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	5.94			cubic metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	360.00			Square metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	2.27			per cubic metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well					
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	19.00			Per Running Metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	27.00			Per Running Metre	
Providing and fixing 40mm (forty millimeters) thick ISI marked phenol bonded (ALPRO/Kit ply or equivalent make) flush door shutters with vision panel of glass, decorative type core of block board construction with frame of first Class hard wood and well	10.50			Per Running Metre	

Providing Cement concrete 1:3:6 (One Cement isto Three Sand isto Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 02, 803 1202 & 1203 complete as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.37			per cubic metre	
Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lift and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00			Each	
Single tee without door 110x110x110 mm (one hundred ten into one hundred ten into one hundred ten)					
Providing and fixing Vitreous China laboratory sink with C.I. or M.S. brackets painted white including cutting holes in walls and making good the same but excluding fittings complete in all respect including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00			Each	
450 mm X 350 mm X 150 mm (four hundred fifty into three hundred fifty into one hundred fifty millimetre)	2.00			Each	
600mm x 450mm x 250mm (six hundred into four hundred fifty into two hundred fifty millimetre)	6.00			Each	
Providing and fixing PTMT grating of approved quality and colour 150 mm (one hundred fifty millimetre) nominal size square 100 mm (one hundred millimetre) diameter of the inner hinged round grating with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00			Each	
Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms (six hundred ninety grams) 15 mm (fifteen millimetre) nominal bore with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00			Each	
Providing and fixing PTMT soap Dish Holder having length of 138mm (one hundred thirty eight millimetre), breadth 102mm (one hundred two millimetre), height of 75mm (seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00			Each	
Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00			Each	
75mm dia (seventy five millimetre diameter) Bend	3.00			Each	
110mm dia (one hundred ten millimetre diameter) Bend					

5mm dia (seventy five millimetre diameter) Single Tee with Door	4.00			Each	
providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes 20mm (twenty millimetre) dia, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m (one metre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	38.70			Running metre	
making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete 25 to 40 mm (twenty five to forty millimetre) nominal bore with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.00			Each	
providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931. 15 mm (fifteen millimetre) nominal bore with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00			Each	
providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball 50 mm (fifty millimetre) nominal bore, 242mm (two hundred forty two millimetre) long, weighing not less than 1240 gms (one thousand two hundred forty grams) complete in all respect including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.00			Each	
providing and fixing 1mm (one millimetre) thick M.S. sheet door with frame of 40x40x6 mm (forty into forty into six) angle iron and mm (three millimetre) M.S. Gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer Using M.S. angles 40x40x6 mm (forty into forty into six) for diagonal braces with in all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00			Each	
providing and fixing 25mm (Twenty millimetre) diameter stainless steel curtain rod and brackets plugs etcetra complete including post and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	18.00			Per Running Metre	

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 25

Estimate Cost :- Rs. 3,16,106/-

Earnest Money :-Rs. 7000/-

Time Limit :-Three Months.

Name of work:- Balance work for the C/o Rain shelter beside Path/road near Biyal Baba Temple Near Muhin in G.P. Muhin.

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Excavation in foundation trenches etcetra by mechanical means (Hydraulic excavator)/manual means in all kinds and classification of soil as pick work, pick jumper work, pick and jumper work, blasting work, (soft or hard rock), saturated soil, dewatering including wedging rock where blasting work is prohibited, chiseling and any other mixed variety of soil de-watering and/or removal of slush, stacking the excavated soil not more than 3 mtrs. (Three metres) clear from the edge of excavation and then returning the stacked soil in 15 cm. (fifteen metres) layers when required into plinths, sides of foundations etcetra, consolidating each deposited layer by ramming and watering and disposing of all surplus excavated earth as per HPPWD specification, approved Drawing, design to the entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rates is inclusive of octroi, royalty, Malkana, toll tax, GST and any other taxes as imposed by the Government.	12.48			Per Cubic metre	
Grading and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four coarse sand isto eight graded stone aggregate 40mm (forty millimetre nominal size) and curing complete excluding cost of form work in foundation and plinth in all depth as per HPPWD specification, approved Drawings, design as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST and any other taxes imposed by the Government.	0.93			Per cubic metre	
Reinforcing form work with steel plates 3.15 mm (three point one five millimetre) thick welded with angle iron in frames 30x30x5mm (Thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and heights propping etcetra with wooden battens ballies for all heights of propping and centring in all heights below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Foundation Footings, basis of columns etcetra and mass concrete including entire carriage of materials work in all leads, lifts and other incidental as per drawings and technical specifications or as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST and any other taxes imposed by the Government.	16.40			Per Square Metre	
Reinforcing form work with steel plates 3.15 mm (three point one five millimetre) thick welded with angle iron in frames 30x30x5mm (Thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and heights propping etcetra with wooden battens ballies for all heights of propping and centring in all heights below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Beams, cantilever, girders and lintels Sides and soffits of beams, beam haunchings, cantilevers, bressumers and lintels upto any height/depth upto all floor level including entire carriage of materials with in all leads, lifts and other incidental as per drawings and technical specifications or as per the direction of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST and any other taxes imposed by the Government.	19.76			Per Square Metre	
Reinforcing form work with steel plates 3.15 mm (three point one five millimetre) thick welded with angle iron in frames 30x30x5mm (Thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and heights propping etcetra with wooden battens ballies for all heights of propping and centring in all heights below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Columns, Pillars, Piers, Abutment, Posts and struts upto all floor level including entire carriage of materials within all leads lifts and other incidental as per drawings and technical specifications or as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST and any other taxes imposed by the Government.	15.96			Per Square Metre	
Reinforcing form work with steel plates 3.15 mm (three point one five millimetre) thick welded with angle iron in frames 30x30x5mm (Thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and heights propping etcetra with wooden battens ballies for all heights of propping and centring in all heights below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Flat surfaces such as soffits of suspended floors, roofs, landings, balconies and access platform, veres and the like floor etcetra In all thickness upto all floor level including entire carriage of materials in all leads, lifts and other incidental as per drawings and technical specifications or as per the direction of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll sale tax, GST and any other taxes imposed by the Government.	29.11			Per Square Metre	

providing form work with steel plates 3.15 mm (three point one five millimetre) thick welded with angle iron in frames 30x30x5mm (Thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and heights propping etcetra with wooden battens and ballies for all heights of propping and centring in all heights below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Edges of slabs and breaks in floors and walls width upto all floor level including entire carriage of materials within all leads, lifts and upto any other incidental as per drawings and technical specifications or as per the direction of Engineer-in-Charge. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	23.32			Per Running Metre
providing and laying mechanically mixed and vibrated reinforced concrete work Grade M-20 (Twenty) design mix to obtain the minimum compressive strength of 20 N/mm ² (twenty newton) per square millimeter with cement contents not less than 330 kg (three hundred thirty) kilogram per cubic meter and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in foundation footings, bases of columns etcetra and the like mass concrete complete as per HPPWD specification and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, sales tax, GST or any other taxes imposed by the Government.	3.39			Per Cubic metre
providing and laying mechanically mixed and vibrated reinforced concrete work Grade M-20 (M-Twenty) design mix to obtain the minimum compressive strength of 20 N/mm ² (twenty newton) per square millimeter with cement contents not less than 360kg (three hundred sixty) kilogramme per cubic meter and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in columns, pillars, posts and struts in all depths/thickness and upto all floor level, and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, octroi, toll tax or any taxes imposed by the government.	6.26			Per Cubic metre
brick work using Second class common burnt clay buildings bricks in plinth level upto all floor level in cement mortar 1:6 (one cement isto six bricks) and curing complete including carriage of materials within all leads, lifts and other incidental, and as per directions enire satisfaction of Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the government.	7.27			Per Cubic metre
providing and fixing 2nd class Deodar Wood work in frames of doors, windows, clerestory, windows and other frames wrough, framed and fixed in position complete upto all floor level complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, toll tax or any taxes imposed the Government.	0.07			Per Cubic metre
providing and fixing 40mm (forty millimeter) thick first class deodar wood panelled glazed or panelled and glazed shutter for doors, window and clerestery windows including bright finished/black enamelled iron butt hinges with necessary screws etcetra complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll Tax, Sale Tax or any other taxes imposed by the Government.	1.27			Per Square metre
providing and fixing 40mm (forty millimeter) thick second class Deodar Wood wire gauze shutters using galvanized MS wire gauze of IS gauge designation 85-G (eighty five-G) with wire of dia 0.63mm (zero point six three millimeters) for doors, windows and clearstory windows including bright finished black enamelled iron butt hinges, with necessary screws etcetra complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, toll tax or any other taxes imposed by the Government.	1.27			Per Square metre
providing and fixing 40x3mm (forty into three millimeter) flat iron hold fast 40cm (forty centimeter) long including fixing to frame with 10mm (ten millimeter) diameter bolts nuts and wooden plugs and embedding in cement concrete block 30x10x15cm (thirty into ten into fifteen centimeter) size of 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeter) nominal size complete as per HPPWD specification or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, toll tax or any taxes imposed by the Government.	4.00			Each
providing and fixing 100x10mm (one hundred into ten millimeter) anodized aluminum tower bolts (Barrel type) make of pilot/sheel anodized transparent or dyed to required colour and shade with screws etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, sales tax, GST or any other taxes imposed by the Government.	12.00			Each

binding and fixing 100mm (one hundred millimeter) aluminium handles make of pilot/sheet transparent or dyed to required colour and shade necessary screws etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	6.00			Each	
15mm (six millimeter) thick cement plaster to ceiling with cement mortar 1:3 (one cement isto three sand), up to all floor level complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	29.11			Per Square metre	
15mm (fifteen millimeter) thick cement plaster with cement mortar 1:4 (one cement isto six four) in single coat on fair of brick/concrete/ stone walls for interior plastering up to all floor level including arises, internal rounded angles, chamfers and/or rounded edges in all girth and finished even and smooth complete as per HPPWD specifications and as per direction and entire satisfaction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	76.87			Per Square metre	
loose materials and other foreign matters sand papered smooth to give final finish to the surface complete upto all floor level as per approved specifications, design, drawing and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	105.98			Per Square metre	
binding and laying matt finished vitrified tile of RESTILE/ NITCO/RAK/KAJARIA ETEANITY/AGL/ SOMANY of approved shade and colour of the office (thickness to be specified by the manufacture) with water absorption less then 0.08% and conforming to IS: 15622 of three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments and other taxes imposed by the Government.	17.55			Per Square metre	
binding plinth protection 50mm (fifty millimeter) thick interlocking paver block with 23cm (Twenty three centimeter) dia half round stone ware for drainage purpose fixed over cement concrete 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm nominal size) complete as directed by the Engineer-in-Charge and carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	9.84			Per Square metre	
binding and laying Tor steel reinforcement for Reinforced Cement Concrete work including bending, binding and placing in position complete including cost of binding wire and other incidentals for its completion up to all floor level complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Octroi, Toll Tax, Sales tax or any other taxes imposed by the Government.	1032.80			Per Killogram	

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 26
Estimate Cost :- Rs. 4,13,631/-
Earnest Money :-Rs. 8000/-
Time Limit :-Three Months.

Name of work:- A/R & M/O Gopipur to Chamukha road Km. 6/0 to 12/590 (SH:- C/o Retaining wall at RD. 6/501 to 6/553).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix of soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	52.16 Cubic metre		Per Cubic metre		
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 900, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	113.94 Cubic metre		Per cubic metre		
Back filling behind abutment Retaining wall/Breast wall. Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, ST, toll tax, sale tax or any other taxes imposed by the Government.	18.06 Cubic metre		Per Cubic metre		
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	45.00 Number		Each		
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

SCHEDULE OF QUANTITY

JOB NO 27
Estimate Cost :- Rs. 4,98,087/-
Earnest Money :-Rs. 10000/-
Time Limit :-Three Months.

Nature of work:- Restoration of rain damages on Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace road Km. 0/00 to 9/00, MDR-46 (SH:- C/o Retaining wall at RD. 1/510 to 1/527.20).

Description of item	Quantity	Rate in		Unit	Amount
		Figures	Words		
earth work in excavation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the sizes and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	51.72 Cubic metre			Per Cubic metre	
providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand to ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etc/tera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 900, 900, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	135.85 Cubic metre			Per cubic metre	
back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.16 Cubic metre			Per Cubic metre	
providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	43.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla-Bihar Division,
HPPWD, Kotla-Bihar.