

## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eenh-theog-hp@gov.in Phone/ Fax No.:- 01783-238900

NO.PW.THD/CB/TENDER/Tender Notice/2022 To

3340-42

Dated:- /6-9-2022

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:-

Publication of tender Notice.

Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.

Executive Engineer, NH Division, H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP

PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT)

Cell), Nigam Vihar Shimla-2 for information and further necessary action please.

Executive Éngineer, NH Division, H.P.P.W.D., Theog

## Himachal Pradesh Public Works Department Notice Inviting Tender

Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:

Date of receipt of Applications for tender forms:

Date of issue/sale of Tender forms:

Date of receipt of Tender:

Date of opening of Tender

23.09.2022 upto 12:00 PM

24.09.2022 upto 4:00 PM

26.09.2022 upto 10:30 AM

26.09.2022 upto 11:00 AM

1	Date of opening of Tender		26.0	9.2022 upto	11.00 Aivi
Sr.	Name of Works	Estimated	Earnest	Cost of	Time Period for completion
No		Cost	Money	form	Two Months
	R/R damages on Theog Kotkhai Hatkoti Road On NH 705 from Km 0/00 to 69/00(SH: Removal of landslide/slips at RD Km 44/460 to 44/560)	492178	10000/-	350/-	
2	R/R damages on Theog Kotkhai Hatkoti Road On NH 705 from M 0/00 to 69/00(Removal of Landslide/slips at RD km 37/580 to 37/630, 40/150 to 40/190,49/200 to 49/250,50/800 to 50/850 abd 57/400 to 57/450)	498741/-	10000/-	350/-	Two Months
3	R/R damages on Theog Kotkhai Hatkoti Road On NH 705 from M 0/00 to 69/00(Removal of Landslide/slips between km 44/600 to 44/680 to 46/460 to 46/500,46/600 to 46/640	487285/-	10000/-	350/-	Two Months
	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km 153/00 to 236/00(SH: Removal of landslide /slips between KM 212/00 to 224/0	348576/-	7000/-	350	Two Months
	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km 153/00 to 236/00(SH: Removal of landslide /slips between KM 170/00 to 176/0)		6000/-	350/-	Two Months

de la					
		412565/-	9000/-	350/-	Two Months
6	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km 153/00 to 236/00(SH: Removal of landslide /slips between KM 204/00	4123037			
	to 208/00)		12222/	350/-	Two Months
7	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km 153/00 to 236/00(SH: Removal of	486414/-	10000/-	330/-	
	landslide /slips between KM 193/00 to 203/00)	•			To Months
8	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km	482160/-	10000/-	350/-	Two Months
	153/00 to 236/00(SH: Removal of landslide /slips between KM 224/600 to 236/0)	* * * * * * * * * * * * * * * * * * *			
9	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km	399553/-	8000/-	350/-	Two Months
	153/00 to 236/00(SH: C/o B/wall at RD 205/630 to 205/645)			,	
10	R/R damages on Kalka Shimla Wangtoo on NH 05/ from Km 153/00 to 236/00(SH: C/o wire crate at RD 211/420 to 211/440)	486812/-	10000/-	350/-	Two Months

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from any Nationalized Bank duly pledged in favour of the executive Engineer.
- 5 The earnest Money & Cost of Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 6 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 7 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 8 The offer of the tender shall remain valid upto 120 days after the opening of tender.

- If the date given above happens to be a holiday, the same shall be processed on next working days.
- 10 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 11 satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 12 One Contractor should not have more than two works in hand at a time.
- 13 Works should be completed by the contractor within the stipulated period.

Executive Engineer, NH Division,

H.P.P.W.D., Theog Dated /6-9-2022

No/PW/NH/CB/Tender/2022 3330-39

Copy forwarded for information and necessary actions to:

- The Engineer-in Chief HP PWD Nigam Vihar Shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- The Superintending Engineer NH Circle HP PWD Shimla . It is therefore requested to kindly issue 3 the certificate the tender of above emergent nature in public interest.
- All the Assistant Engineer working under this Division
- 5 The Drawing Branch/Account Branch in this office.
- 6 Notice Board.

Executive Engineer, NH Division, H.P.P.W.D., Theog

# Certificate

Certified that the tenders of works as called vide this office NIT No/PW/NH/CB/Tender/2022- 3330-39 Dated /6-9-2022 are of urgent nature works.

Executive Engineer, NH Division, H.P.P.W.D., Theog

Nan 44/4 Sr.	ne of Work:-R/R damages on Theog-Kotkhai-Hatkoti Road on NH-705 from Km 0/00 To 69/00 (SH-:Remo	val of lands	lide/sli	ips at RD Km	Estimated Cost:-492 Earnest Money :- 10 Time :- Two Month	00.000
No	Description of Work / Item (S)	Qty.	-		Rate	Amount
1	Removal of landslides/slips clearance Removal of landslide in 1/11			In figures	In words	Amount
	Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per technical specification 302 3 5 and 1611 as per disposition by Providing the Providing	1601.10				4921
	technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge.				hundred seven And	
	and to that per direction by Engineer-in-charge.				Paisa forty only	
					, ,	
					Total	4921
	Quoted rate in Figure	+/-	(	%)		.,,,,,
-			)			
	Condition Quoted rate in Words					

Rates Should be quoted for all heights includings all leads and lifts.
 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

Executive Engineer, National Highway Division , M.P. P.W.D. Theog .

SCHEDULE OF QUANTITY  7/580 to 37/630,40/150 to 40/190,49/200 to 49/250,50/800 to 50/850 and 57/400 to 57/450)  Description of Work / Item (S)	moval of land	slide/sl	ips at RD Km	Estimated Cost:-49 Earnest Money:-1 Time:-Two Month	9999.00
Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge.	Qty. 1622.45	Cum	In figures 307.40	Rate In words Rupees three hundred seven And Paisa forty only	49874
	re +/-			Total	49874

Executive Engineer, National Highway Division , A.P. P.W.D. Theog .

Rates Should be quoted for all heights includings all leads and lifts.
 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

	ne of Work:-R/R damages on Theog-Kotkhai-Hatkoti Road on NH-705 from Km 0/00 To 69/00 (SH-:Remo 44/600 to 44/680,46/460 to 46/500,46/600 to 46/640)	val of lands	lide/sli	ips between	Estimated Cost:-48 Earnest Money :- 10 Time :- Two Month	00,000
Sr.	Description of Work / Item (S)	Oty. 1677.40 Cum		The state of the s		Amount
	Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per			In figures 290 50	Rupees two hundred ninty And Paisa	
les apriles de	technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge.				fifty only	
					1 Otto	487285
	Quoted rate in Figure	+/-	()	%)		
prosperies	Quoted rate in Words	A CONTRACTOR OF THE PROPERTY O	a transcription of			

COMPANIE OF OUR WITTE

## Condition

Executive Engineer, National Highway Division , H.P. P.W.D. Theog .

<sup>1</sup> Rates Should be quoted for all heights includings all leads and lifts

<sup>2.</sup> The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

Nai 204/ Sr.	me of Work:-R/R damages on Kalka Shimla Wangtoo on NH-05 from Km 153/00 To 236/00 (SH-:Removal 00 to 208/00)	of landslide	/slips	between km	Estimated Cost:-348 Earnest Money :- 90 Time :- Two Month	00.00	
No.	Description of Work / Item (S)	Qty.			Rate	Amount	
				In figures	In words		
	Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge.	1133.95	Cum	307.40	Rupees three hundred seven And Paisa forty only		348576
					Total		348576
	Quoted rate in Figure		( )	%)			
	Quoted rate in Words						

## Condition

Executive Engineer, National Highway Division , H.P. P.W.D. Theog .

<sup>1</sup> Rates Should be quoted for all heights includings all leads and lifts.

<sup>2</sup> The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

Sr.	ne of Work:-R/R damages on Kalka Shimla Wangtoo on NH-05 from Km 153/00 To 236/00 (SH-:Removal	of landslide	e/slips	between km	Estimated Cost:-279 Earnest Money :- 60 Time :- Two Month	00.00	
No	Description of Work / Item (S)	Qty.			Rate	Amount	
1	Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of cleares and discovered the state of the state			In figures	In words		
	mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge.	907.69	Cum	307.40	Rupees three hundred seven And Paisa forty only	i	27902
					Total	1	27902
	Quoted rate in Figure	+/-	(	%)			
101	Condition Quoted rate in Words				1	1	

Rates Should be quoted for all heights includings all leads and lifts.

 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

Executive Engineer, National Highway Division , H.P. P.W.D. Theog .

Sr.	Description of Work / Item (S)				e/slips	hetween km	Estimated Cost:-412 Earnest Money :- 90 Time :- Two Month	000.00
No		Qty.			Rate	Amount		
1	Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and dispused of			In figures	In words			
	mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge.	1342.11	Cum	307.40		412565		
					Total	412565		
	Quoted rate in Figure	+/-	(	%)				
			)					
	Condition Quoted rate in Words							

Rates Should be quoted for all heights includings all leads and lifts.
 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

Executive Engineer, National Highway Division, H.P. P.W.D. Theog.

Name of Work:-R/R damages on Kalka Shimla Wangtoo on NH-05 from Km 153/00 To 236/00 (SH-:Removal of landslide/slips between km 193/00 to 203/00) Estimated Cost:-486414.00 Earnest Money :- 10000.00 Time :- Two Months. Sr. Description of Work / Item (S) No Qty. Rate Amount Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by In figures In words mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per 1582.35 Cum 307.40 Rupees three 486414 technical specification 302.3.5 and 1611 as per direction by Engineer-in-charge. hundred seven And Paisa forty only Total 486414 Quoted rate in Figure +/-.....%) Quoted rate in Words Condition

1 Rates Should be quoted for all heights includings all leads and lifts.

2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

Executive Engineer, National Highway Division, H.P. P.W.D. Theog.

	DRAFT SCHEDULE OF QUANTITY						
236/	F T		Estimated Cost:-482 Earnest Money :- 10 Time :- One Months	00.000			
Sr.	Description of Work / Item (S)	Qty.			Rate	Amount	in the second
No				In figures	In words		
1	Removal of landslides/slips clearance. Removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lift and lead as per technical specification 302.3.5 and 1611	1431.80	cum	307.40	Rupees three hundred seven And	1	44013

Quoted rate in Figure +/-

Quoted rate in Words

Condition

Engineer - in - charge.

1 Rates Should be quoted for all heights includings all leads and lifts.

2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.

2 Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip, minimum 6 hours per day. The contractor

owner of tipper shalll bear the expenses of POL charges, repair of machinery. Any accident and other damages to private and government

propperty occur during working hour is the whole responsibility of contractor and disposal within all leads, lifts as per the direction of

3 Cement should be procured from HP State Civil Supply Corporation only.

Executive Engineer, National Highway Division , H.P. P.W.D. Theog .

1681.00

.....%)

Rupees one

thousand six

only Total

hundred eighty one

42025

482160

25.00

hour

(...

	SCHEDULE OF QUANTITY					
Nam	ie of Work:-R/R damages on Kalka-Shimla-Wangtoo Road on NH-05 km 155/00 to 236/00.(SH:- C/o B/Wall	at RD 205/	630 T		Estimated Cost:-399 Earnest Money :- 80 Time :- Two Months	00.00
	Description of Work / Item (S)	Oty.			Rate	Amount
Sr.				In figures	In words	
s	Excavation in soil by Manual Mean. Excavation ordinary soil using mechanically/ manual means including loading in truck and carring out earth to embankment site as per drawings and technical specifications clause 304, with all lifts and leads, tacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any tost public /private poperty luring course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	71.10	Cum	223.10	Rupees two hundred twenty three And Paisa ten only	15862
f I	Excavation for Structures. Earth work in excavation of foundation of structures as per drawings and technical specifications lause 304, including setting out, construction of shoring and bracing rermoval of slumps and other deleterious matter dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earh locally or road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all eads & lifts. Any loss to public /private poperty during course of excavation shall be the whole responsibility of the ontractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the irrection by the Engineer-in-charge.	6.00	Cum	398.20	Rupees three hundred ninty eigh And Paisa twenty only	
s	roviding and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical pecifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per irrection of the Engineer-in-Charge.	62.55	Cun		thousand nir hundred forty ar paisa thirty on	d d dy
e	roviding weep holes in Brickmasonry/plain/reinforced concrete abutment,wing wall/return wall with 110mm dia PVC pipe xtending through the full width of the structure with slope 1V:20H towards drawing face complete as per drawing and 'echnical Specification clause 2706 & 2200 including carriage of materials and equipment in all leads and lifts with all nodes of transportation as per the direction by the Engineer-in-charge.		Rm	t. 243.4	Rupees two hundr forty three A Paisa forty or	nd
			+		To	tal 3995
	Quoted rate in Figure	e +/-	(	%)		
_	Quoted rate in Word	s				

- Rates Should be quoted for all heights includings all leads and lifts.
  The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.
  Cement should be procured from HP State Civil Supply Corporation only.

Executive Engineer, National Highway Division, M.P. P.W.D. Theog.

1/4	ne of Work:-R/R damages on Kalka-Shimla-Wangtoo Road on NH-05 km 155/00 to 236/00.(SH:- C/o R/Wal 440).	II Wirecrat	e at K		Earnest Money :- 10 Time :- Three Mont	00.00	
r.	Description of Work / Item (S)	Qty.			Auto	Amount	
0				In figures	In words		
	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utlising the remaining earh locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	62.50	Cum	398.20	Rupees three hundred ninty eight And Paisa twenty only		2488
2	Providing and laying boulder apron laid in wire crates of 4mm dia GI Wire conforming the IS 280 and IS 4826 in 100m *100mm mesh(woven diaognally) including 10% extra for lapse and joint laid with stone boulder weighting not less than 25 kg each as per drawing and technical specification clause 1301. Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge		) Cun	3701.3	2 Rupees fiv thousand eight hundred twent eight and pais seventy on	nt ty sa ly	486
-	Quoted rate in Figure	e +/-	(	%)	10		400

Condition
1 Rates Should be quoted for all heights includings all leads and lifts.
2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.
3 Cement should be procured from HP State Civil Supply Corporation only.

Executive Engineer, National Highway Division , ELP. P.W.D. Theog .