



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- ee-sol-hp@nic.com

No.PW-SD/CB-Tender/-22-23-

9/28-33

Dated:- 18-09-22


To

The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.


Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER
(Exigency)**

Sealed item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	29.09.2022	Upto 4.00 P.M.
2	The last date sale of tender forms.	30.09.2022	Upto 4.00 P.M.
3	The date for receipt of tender forms.	01.10.2022	Upto 10.30 A.M.
4	The date of opening of tender	01.10.2022	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 01.10.2022 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs)	Time	Cost of Form
1.	Annual repair and maintenance of Solan Rajgarh bye pass road km 0/0 to 5/410 (SH: Clearance of side drain and trimming of grass between km 0/0 to 5/0)	185667/-	3750/-	Fifteen Days	Rs.350/-
2.	A/R & M/O various road under Solan Sub-Division (SH: Hiring of JCB/ loader cum excavator for removal of debris/slips & clearance of drain)	199500/-	4000/-	Three Months	Rs.350/-
3.	A/R & M/O various roads under Solan Sub Division (SH: Hiring of tipper for removal of slips on various reaches of roads)	205200/-	4150/-	Two Months	Rs.350/-
4.	A/R & M/O PWD rest house at Kandaghat distt Solan (SW: providing sanitation services by deployment of one belder/sweeper/part time worker)	99898/-	2000/-	12 Months	Rs.350/-
5.	A/R & M/O Kandaghat to Hathon road km 0/0 to 6/0 (SH: C/o PCC V-Shape drain at RD 0/640 to 0/856 and C/o	300995/-	6050/-	One Month	Rs.350/-

	PCC edge wall at RD 0/702 to 0/750)				
	Annual repair and maintenance of Jaoli Damrog Solan road km 0/0 to 5/050 (SH: Construction of U Shape drain in km 4/605 to 4/540 & 2/430 to 2/300)	149780/-	3000/-	One Month	Rs.350/-
7.	Restoration of damages due to laying OFC on Saproon Chowk to Chambaghat road km 0/0 to 3/300 (SH: C/o U Shape drain from km 0/080 to 0/170) Deposit work	498778/-	10000/-	One Month	Rs.350/-
8.	A/R & M/O various road under Solan Sub Division (SH: Clearance of side drain, white washing of parapets, drain and dressing of berms on Solan kumarhatti road between km 0/0 to 5/0 and Berti Manlog road between km 0/0 to 4/0	452561/-	10000/-	Fifteen Days	Rs.350/-
9.	A/R & M/O Salogra Ashwani Khad road km 0/0 to 7/500 (SH: Bush cutting in km 0/0 to 7/500)	52065/-	1050/-	Fifteen Days	Rs.350/-
10	C/O wearhouse for the storage of EMVs & VVPATs in kather, Teh & Distt Solan (SH: Earth work in cutting for leveling upto courtyard form RD 0/010 to 0/020)	499306/-	10000/-	One Month	Rs.350/-
11.	C/O link road from Chaura to Anji in Solan Assembly constituency km 0/0 to 5/0 under SCSP (SH: ROFD in between km 0/0 to 0/300)	480138/-	9650/-	One Month	Rs.350/-
12	C/o Lonk road from Chaura to anji in Solan Assembly constituency km 0/0 to 5/0 under SCSP (SH: ROFD in between km 0/300 to 0/660)	496871/-	9950/-	One Month	Rs.350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

SCHEDULE OF QUANTITY

SL No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
Job No. :-						
Name of work: Annual repair and maintenance of Solan Rajgarh Bye Pass road km 0/0 to 5/410 (SH:- Clearance of side Drain and Trimming of grass between km 0/0 to 5/0)						
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	5000.000 m	Per running meter.			
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	5852.000 m2	Per Square Meter			
Total :-						
Total in Words						

T/S No. 202 for the 2022-23.
Sr. No. 231 for the year 2022-23.


 Executive Engineer
 B&R Division, HP.PWD, Solan.

SCHEDULE OF QUANTITY				
Sl. No.	Description of work	Qty.	Unit	Rate In Figures Words
	Job No. 2			
	Name of work :- A/R & M/O various road under Solan Sub- Division (SH :- Hiring of JCB / loader cum-excavator for Removal of debris / slips & clearance of drain)			Estimated Cost: - Earnest Money: - Time Limit: -
	Hiring of JCB / loader cum-excavator.	210.00 hr	Per hour.	Rs. 199500.00 4000.00 Three Months
	Terms and Conditions :-			
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.			
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.			
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.			
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.			
(e)	Minimum work as per PWD norms must be executed by the machinery hired.			
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model.			
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour			
Total in Words		Total :-		

Sr. No.215 for the year 2022-23.


Executive Engineer
B&R Division-HP PWD, Solan

hpi

SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
					Estimated Cost: -	205200.00
					Earnest Money: -	4150.00
					Time Limit: -	Two months

Job No. 3

Name of work: - Annual repair and maintenance of various roads under Solan Sub Division (SH :- Hiring of tipper for removal of slips on various reaches of roads)

1	Hiring of Tipper for disposal of earthen material or slips having capacity 5.50 Cum. Per trip and minimum working hours @ 8 (eight) hours per day which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead, lift and other incidental charges	50 day	Per day			
Total:-						

Total in Words


Sr. No. 249 for the year 2022-23.


 Executive Engineer
 B&R Division, HP.PWD, Solan.

SCHEDULE OF QUANTITY

Sl.No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Job No. 4				Estimated Cost:	99898.00
					Earnest Money:	2000.00
					Time: -	12 months.
	Name of work :- A/R & M/O PWD Rest House at Kandaghat, Distt. Solan (SW :- Providing sanitation services by deployment of one beldar / sweeper / Part time worker)					
1	Sweeping in and around the circuit house / Rest house including cleaning and washing of floors out side and inside rest house, wash room, kitchen, drain by deploying labour (Timing of labour shall be 7.30am to 10.00am and 4.00pm to 6.30pm at specified places i.e. five hours per day or one thousand eight hundred twenty five hours per annum i.e. 1 Job) as per direction of Engineer in Charge including carriage of all labour, equipment and material to various location through all modes of transportation in all lead, lift and other incidental charges.	1.000	Job Per Job			
Total :-						
Total in Words						

Sr. No. 164 for the year 2022-23.


 Executive Engineer
 B&R Division, HP.PWD, Solan.

SCHEDULE OF QUANTITY

SL No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Job No. :- 15				Estimated Cost: -	300995.00
					Earnest Money: -	6050.00
					Time limit : -	One month
Name of Work :- A/R & M/O Kandaghat to Hathon road from km 0/0 to 6/0 (SH:- C/O PCC V- Shape drain at RD. 0/640 to 0/865 and C/O PCC edge wall at RD. 0/0702 to 0/750)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	54.030 m3	Per Cubic Meter			
2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20 (twenty) millimetres nominal size) mechanically mixed and vibrated in open foundations including form work and curing complete as per drawings and MORD technical specifications clause 802, 803.1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	16.030 m3	Per Cubic Meter			

SCHEDULE OF QUANTITY					
Sl. No.	Description of work	Qty.	Unit	RATE In Figures Words	AMOUNT Rs.
3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and plinths Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer in-Charge including carriage of materials with in all leads and lifts and other incidentals.	48.000 m3	Per Cubic Meter		
Total :-					
Total in Words					

T/S No. 189 for the 2022-23,
Sr. No. 238 for the year 2022-23.


Executive Engineer
B&R Division HP PWD, Solan.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
Job No. 6						
					Estimated Cost: -	149780.00
					Earnest Money: -	3000.00
					Time Limit: -	One Month

Name of Work :- Repair and maintenance of Jatoli Damrog Solan road km 0/0 to 5/050 (SH:- Construction of U-Shape drain in km 4/605 to 4/540 & 2/430 to 2/300)

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) Dimensons and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	35,100 m3	Per Cubic Meter			
2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 40mm (forty millimeters) nominal size) Mechanically mixed,vibrated and curing comolete including the cost of form work complete in open foundations and plinths for all type of structure as per drawings and technical specifications clause 802, 803,1202 and 1203(eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) curing complete as per HP.PWD. specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	28,280 m3	Per Cubic Meter			
Total in Words		Total:-				

T/S No.79 for the 2022-23.
Sr. No.115 for the year 2022-23.


Executive Engineer
B&B Division HP.PWD Solan.

SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	
					Estimated Cost:-	Rs. 498778.00
					Earnest Money:-	100000.00
					Time Limit:-	One Month
Name of Work :-Restoration of damages due to laying of OFC on Saproon Chowk to Chambaghat road Km 0/0 to 3/300 (SH:- C/O U Shape drain form km 0/080 to 0/170) Deposit work.						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling/ wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	54.000 m ³	Per Cubic Meter			
2	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per PWD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads and all incidental charges.	25.880 m ³	Per cubic meter.			
3	Providing and laying reinforced cement concrete RCC Grade M-25 (Twenty five) 1:1.5:3 (one cement isto one and half sand isto three graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size mechanically mixed, vibrated and curing complete in super structure including cost of form work as per drawings and MORD Technical Specification Clauses 800.1205.4 and 1205.5 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	3.600 m ³	Per Cubic metre			

Job No. 7

SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	
4	Steel reinforcement for R.C.C. work Thermo-Mechanically Treated bars of grade Fe-500D or more, including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2148.300 kg	Per Kilogramme			
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	1355.800 kg	Per kilogramme			
6	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	50.000 No	Each			
Total in Words		Total:-				

T/S No.221 for the 2022-23
Sr. No. 265 for the year 2022-23.


Executive Engineer
B&R Division, HP.PWD. Solan.


SCHEDULE OF QUANTITY

Sl.No.	Description of work	Qty.	Unit	RATE In Figures Words	AMOUNT Rs.
Job No. 8					
				Estimated Cost: -	452561.00
				Earnest Money: -	10000.00
				Time Limit: -	Fifteen days

Name of work: - Annual Repair & Maintenance of various road under Solan Sub- Division (SH:-Clearance of side drain, white washing of parapets, drain and dressing of berms on Solan Kumarhatti road between km 0/0 to 5/0 and Berti Manlog road Between km 0/0 to 4/0)

1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of	7500.000 m	Per running meter.		
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	6900.000 m2	Per Square Meter		
3	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 (One nine one five) and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	1088.000 m2	Per Square Meter		
4	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface and dressing it in entire length to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903, and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	4500.000 m2	Per Square Meter		
Total:-					
Total in Words					

T/S No.228 for the 2022-23.
Sr. No. 268 for the year 2022-23.


Executive Engineer
B&R Division, HP.PWD, Solan.

SCHEDULE OF QUANTITY

Sl.No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	Rs.
	Job No.				Estimated Cost: -	52065.00
					Earnest Money: -	1050.00
					Time Limit : -	Fifteen days

Name of work : - Annual Repair & Maintenance of Salogra Ashwani Khad road km 0/0 to 7/500(SH:-Bash cutting in km 0/0 to 7/500)

1	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	23140.000	m2	Per Square Meter		
Total:-						

Total in Words

T/S No.229 for the 2022-23.
Sr. No. 269 for the year 2022-23.


Executive Engineer
B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	
	Job No. :- 16				Estimated Cost: -	Rs. 499306.00
					Earnest Money: -	10000.00
					Time: -	One month
	Name of work :- Construction of Warehouses for the storage of EVMs & VVPATs in Kather, Tehsil & Distt. Solan (SH:- Earth work in cutting for leveling upto courtyard form Rd. 0/010 to 0/020)					
1	Cutting in earth work in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiselling and wedging out of rock; (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting out to required lines, levels as shown on the drawing and as directed by the Engineer-in- Charge at site, according to the H.P.PWD. specification of and sorting out useful & unuseful materials and transportation of the unuseful materials on approved dumping sites or otherwise (to be arranged by the contractor including payment of prescribed dumping charges of Municipal Committee / Local body if levied any) to the satisfaction of Engineer in Charge through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and with all kind of labour, machineries, tools, equipments and safety measures and incidentals necessities to complete the work by mechanical means and labour (if any required). All useful materials, such as stones, shingles, aggregate and slates shall be probably stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation and used / removed as per the direction of Engineer in Charge. Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges.	842.000	m ³	Per	Cubic Meter	
Total :-						
Total in Words						

T/S No.226 for the 2022-23
Sr. No. 263 for the year 2022-23.


Executive Engineer
B&R Division, H.P.PWD, Solan.

B-2

SCHEDULE OF QUANTITY

Sl.No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
Job No. :- 17						480138.00
						9650.00
						One month
Name of Work :-Construction of link road from Chaura to Anji in Solan Assembly Constituency km 0/0 to 5/0 under SCSP (SH:- 60) ROFD in between km. 0/0 to 0/300)						
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site. according to the HP.PWD. specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required).Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2801.270	m3 Per Cubic metre			
Total in Words		Total:-				

T/S No.222 for the 2022-23
Sr. No. 266 for the year 2022-23.


Executive Engineer
B&R Division-HP.PWD. Solan.

SCHEDULE OF QUANTITY

Sl.No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
					Estimated Cost: -	496871.00
					Earnest Money: -	9950.00
					Time limit: -	One month

Job No. :- **1R**

Name of Work :- Construction of link road from Chaura to Anji in Solan Assembly Constituency km 0/0 to 5/0 under SCSP (SH:- ~~66~~ ROFD in

Name of Work :- Construction of link road from Chaura to Anji in Solan Assembly Constituency km 0/0 to 5/0 under SCSP (SH:- 66 ROFD in		between km. 0/300 to 0/660)					
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site. according to the HP.PWD. specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required).Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2898.900	m3	Per	Cubic metre		
Total in Words		Total:-					

T/S No.223 for the 2022-23
Sr. No. 267 for the year 2022-23.



Executive Engineer
B&R Division HP.PWD. Solan.

Exigency Certificat

It is certified that the tenders which were invited vide this Office NIQ NO.PW.SD.CB.Tender/2022-23-9128-33 dated: 19.09.2022 are the works of emergent nature of work & in public interest.

Dated:- 19 September.2022

Place:-Solan.


**Executive Engineer,
Solan B & R Division,
H.P.P.W.D, Solan.**