

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23-

11984-86

Dated:- 21/9/22

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 27.09.2022 up to 11:00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 26.09.2022 upto 01:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Annual repair and maintenance of Non Residential building in Kamand Sub Division HPPWD Kamand (SH:- Construction of wire crated Breast wall back side of Junior Engineer Office Kataula at RD 0/0 to 0/015)	2,36,885/-	4,700/-	350/-	One month
2	Annual repair and maintenance of Non Residential building in Kamand Sub Division HPPWD Kamand (SH:- Providing and laying Cement concrete M-10 grade on approach road to Junior Engineer Office Kataula at RD 0/0 to 0/180)	4,57,130/-	9,100/-	350/-	One month
3	Annual repair and maintenance of Non Residential building in Kamand Sub Division HPPWD Kamand (SH:- Construction of wire crated breast wall on approach road to Junior Engineer Office Kataula at RD 0/0 to 0/020)	4,66,943/-	9,300/-	350/-	One month
4	Annual repair and maintenance of Non Residential building in Kamand Sub Division HPPWD Kamand (SH:- Construction of wire crated breast wall on approach road to Junior Engineer Office Kataula at RD 0/020 to 0/040)	4,75,456/-	9,500/-	350/-	One month
5	Annual repair and maintenance of Non Residential building in Kamand Sub Division HPPWD Kamand (SH:- Construction of wire crated breast wall on approach road to Junior Engineer Office Kataula at RD 0/040 to 0/050)	2,38,032/-	4,800/-	350/-	One month
6	Annual repair and maintenance of Non Residential building in Kamand Sub Division under Mandi Division No. I, HPPWD, at Padhar (SH:- Construction of retaining wall for Junior Engineer Office Kataula at RD 0/0 to 0/017)	3,82,647/-	7,700/-	350/-	One month
7	Annual repair and maintenance of Non Residential building in Kamand Sub Division under Mandi Division No. I, HPPWD, at Padhar (SH:- Construction of retaining wall for Junior Engineer Office Kataula at RD 0/017 to 0/034)	3,82,647/-	7,700/-	350/-	One month

8	Annual repair and maintenance on residential building Kamand HPPWD, Kamand under Mandi Division No. I, HPPWD, Padhar. (SH:- Providing and applying painting, distemping etcetera in PWD Rest House at Prasher).	3,42,767/-	6,900/-	350/-	One month
---	---	------------	---------	-------	-----------

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)

Schedule of Quantity

Estimated Cost:- 236885.00
 Earnest Money:- 4700.00
 Time:- One month

Name of work:- Annual repair and maintenance of Non Residential building in Kamand Sub Division H.P.P.W.D. Kamand.
 Sub Head:- Construction of wire crated Breast wall back side of Junior Engineer Office Kataula at R.D. 0/0 to 0/015.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	65.47 Cum.			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	81.00 Cum.			Per cubic metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar.

SCHEDULE OF QUANTITY

Estimated Cost:- 457130.00

Earnest Money:- 9100.00

Time :- One month

Name of work:- Annual repair and maintenance of Non Residential building in Kamand Sub Division H.P.P.W.D. Kamand. (Sub Head:- Providing and laying Cement concrete M-10 grade on approach road to Junior Engineer Office Kataula at R.D. 0/0 to 0/180.)

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	2 Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3 67.50	4	5	6 Per cubic metre	7
	TOTAL:-					



Executive Engineer,
Mandi Division No. 1,
H.P. PWD, at Padhar.

Schedule of Quantity

Estimated Cost:- 466943.00
 Earnest Money:- 9300.00
 Time:- One month

Name of work:- Annual repair and maintenance of Non Residential building in Kamand Sub Division H.P.P.W.D. Kamand.
Sub Head:- Construction of wire crated breast wall on approach road to Junior Engineer Office Kataula R.D. 0/0 to 0/020.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	99.60 Cum.			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	165.60 Cum.			Per cubic metre	
				Total:-		



 Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 475456.00
 Earnest Money:- 9500.00
 Time:- One month

Name of work:- Annual repair and maintenance of Non Residential building in Kamand Sub Division H.P.P.W.D. Kamand.
 Sub Head:- Construction of wire crated breast wall on approach road to Junior Engineer Office Kataula R.D. 0/020 to 0/040.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	116.40 Cum.			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	165.60 Cum.			Per cubic metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 H.P.P.W.D. at Padhar.

Schedule of Quantity

Estimated Cost:- 238032.00
 Earnest Money:- 4800.00
 Time:- One month

Name of work:- Annual repair and maintenance of Non Residential building in Kamand Sub Division H.P.P.W.D. Kamand.
Sub Head:- Construction of wire crated breast wall on approach road to Junior Engineer Office Kataula R.D. 0/040 to 0/050.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	58.80 Cum.			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	82.80 Cum.			Per cubic metre	
				Total:-		

Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- Rs. 382647.00
Earnest Money:- Rs. 7700.00
Time:- One month

Name of work:- Annual repair and maintenance of Non residential building in Kamand Sub-Division under Mandi Division No.1, HP.PWD. at Padhar.
Sub Head:- Construction of retaining wall for Junior Engineer office at Kataula at RD 0/00 to 0/017.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	24.25 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	56.70 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.82 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	16.00 Nos.			Each	
					Total	

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 382647.00
 Earnest Money:- Rs. 7700.00
 Time:- One month

Name of work:- Annual repair and maintenance of Non residential building in Kamand Sub-Division under Mandi Division No.1, HP.PWD. at Padhar.
 Sub Head:- Construction of retaining wall for Junior Engineer office at Kataula at RD 0/017 to 0/034.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	24.25 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	56.70 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.82 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	16.00 Nos.			Each	
					Total	


Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- 342767.00
 Earnest Money:- 6900.00
 Time:- One month

Name of work:- Annual repair and maintenance non residential building Kamand HP.PWD. Kamand under Mandi Division No.I HP.PWD. at Padhar.
Sub Head:- Providing and applying painting, distemper etcetera in PWD Rest House at Prasher

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In Words		
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new work (two or more coats) over and including water thinnable priming coat with cement primer complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	2103.48 Sqm.			Per square metre	
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams per litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge..	170.10 Sqm.			Per square metre	
3	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications :Painting wood work with Deluxe Multi Surface Paint of required shade with Two or more coats applied @ 0.90 ltr/10 sqm (at the rate of zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (at the rate of zero point eighty litre per ten square metre) of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	863.90 Sqm.			Per square metre	
	Total:-					


 Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar