

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form No. 6 and 8 are hereby invited by the Executive Engineer (NH) Division HPPWD Nahan on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **23.09.2022** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **22.09.2022 04:00 PM**


The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 120 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH-907A Km 0/00 to 78/00 (SH:- Repair of Pot hole in Km 40/00 to 78/00).	4,12,226/-	8500/-	2 Month	350/-
2	Ordinary repair to Kala Amb Paonta Sahib Dehradun Road on NH 72 (New NH 07) Km 46/00 to 103/00 (SH:- Construction of PC U Shape side drain at RD 72/800 to 73/00)	4,95,062/-	9900/-	2 Month	350/-
3	Ordinary repair to NH 73A (New NH 907) on Jagadhari Chachchhrauli Khirzabad Batta Chowk road Km 45/880 to 53/300 (SH:- Providing and fixing Delineators between Km 46/00 to 53/00).	4,23,684/-	8500/-	2 Month	350/-
4	Ordinary repair to Kala Amb Paonta Sahib Dehradun road on NH 72 (New NH-07) Km 46/00 to 103/00 (SH:- Providing and fixing Delineators between Km 82/00 to 83/280, 83/850 to 85/950, 86/050 to 88/00 and 89/00 to 90/250).	3,97,961/-	8000/-	2 Month	350/-
5	Ordinary repair to Kala Amb Paonta Sahib Dehradun Road on NH 72 (New NH-07) Km 46/00 to 103/00 (SH:- Construction of PCC U-shape drain at RD 94/850 to 94/950 (RHS).	3,94,900/-	8000/-	2 Month	350/-

CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.


Executive Engineer
N.H. Division, H.P.P.W.D.
Nahan

9. The offer shall remain valid upto 120 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

Executive Engineer
NH Division HPPWD
Nahan

For & on behalf of Governor of Himachal Pradesh

No. PW/NHD-NHN/TA-Tender Notice/ 2022-23: 3843-93 dated:- 14-9-2022.

Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.

Executive Engineer
NH Division HPPWD
Nahan

Job No. 1

Name of Work:- Ordinary Repair to Nahan Do Saraka Sarahan Kumarhatti Road On NH 907 A Km 0/00 to 78/00 (SH :- Repair of Pothole in Km 40/00 to 78/00)

SCHEDULE OF QUANTITY

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost Rs :-		
				Earnest Money Rs :-		
				Time Limit :-		
				In Word	In Figure	Amount
1	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2	981.35	Per Square metre			412226.00/- only
						8500.00/- only
						2 Months


Executive Engineer,
NH. Division,
HP.PWD., Nahan,

Job No. 2

Name of Work:- Ordinary Repair to Kala Amb Paonta Sahib Dehradun Road on NH 72 (New NH 07) km 46/00 to 103/00 (SH:- Construction of PCC U Shape Side Drain at RD 72/800 to 73/00)

SCHEDULE OF QUANTITY

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost Rs :-		
				Earnest Money Rs :-		Amount
				In Word	In Figure	
				Time Limit :-		2 Months
1	Excavation for Structures earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including all leads, lifts and carriage as per entire satisfaction of Engineer-in-charge.	126.00	Per Cubic metre			
2	Providing and laying Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications, RCC M-20 (Twenty) mixed mechanically, vibrated & placing in all depths including form work curing complete, conforming to Ministry of Surface Transport specification clause 1500,1700 & 2100 (latest revision) including all leads, lifts and carriage of materials by all mode of transportation and as per direction and satisfaction of the Engineer-in-Charge.	51.40	Per Cubic metre			
3	Providing and laying non pressure NP-2 class (light duty) R.C.C pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :	12.50	Per Rmt			
4	Supply, fitting and placing HYSD bar reinforcement in foundation complete as per drawing and technical specification. ,conforming to Ministry of Surface Transport specification clause 1600 & 2200 (latest revision) including all leads, lifts and carriage of materials by all mode of transportation and as per direction and satisfaction of the Engineer-in-Charge.	0.17	Each			

Executive Engineer,
NH. Division,
HP.PWD., Nahan,

Job No. 3

SCHEDULE OF QUANTITY						
Name of Work:- Ordinary Repair to NH 73A (New NH 907) on Jagadhari Cachchhrauli Khirzabad Batta Chowk road KM 45/880 to 53/300 (SH:- Providing and fixing Delineators between km 46/00 to 53/00)						
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost Rs :-		423684.00/- only
				Earnest Money Rs :-		8500.00/- only
				Time Limit :-		2 Months
1	Road Delineators :- Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm high above ground level, painted black and white in 15 cm wide strips, fitted with 80 x 100 mm rectangular or 75 mm dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 and the drawings including all leads lifts and carriage of materials complete as per entire satisfaction of the Engineer-in-Charge.	560	each	Rates in		Amount
				In Word	In Figure	


 Executive Engineer,
 NH. Division,
 HP.PWD., Nahan,

Job No. 4

SCHEDULE OF QUANTITY

Name of Work:- Ordinary Repair to Kala Amb Paonta Sahib Dehradun Road on NH 72 (New NH 07) KM 46/00 to 103/00 (SH:- Providing and fixing Delineators between km 82/00 to 83/280, 83/850 to 85/950, 86/050 to 88/00 and 89/00 to 90/250)

to 103/00 (SH:- Providing and fixing Delineators between km 82/00 to 83/280, 83/850 to 85/950,86/050 to 88/00 and 89/00 to 90/250)				Estimated cost Rs :-	397961.00/- only
				Earnest Money Rs :-	8000.00/- only
				Time Limit :-	2 Months
Sr.No	Description of item/Sub Head	Quantity	Unit	Rates in	
				In Word	In Figure
1	Road Delineators :- Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm high above ground level, painted black and white in 15 cm wide strips, fitted with 80 x 100 mm rectangular or 75 mm dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 and the drawings including all leads lifts and carriage of materials complete as per entire satisfaction of the Engineer-in-Charge.	526.00	each		
					Amount


Executive Engineer,
NH. Division,
HP.PWD., Nahan,

Job No. 5

SCHEDULE OF QUANTITY						
Name of Work:- Ordinary Repair to Kala Amb Paonta Sahib Dehradun Road on NH 72 (New NH 07) km 46/00 to 103/00 (SH:- Construcion of PCC U Shape Side Drain at RD 94/850 to 94/950)(RHS)				Estimated cost Rs :-		
				Earnest Money Rs :-		
				Time Limit :-		
				2 Months		
Sr.No	Description of item/Sub Head	Quantity	Unit	Rates in		Amount
				In Word	In Figure	
1	Excavation for Structures earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including all leads, lifts and carriage as per entire satisfaction of Engineer-in-charge.	94.50	Per Cubic metre			
2	Providing and laying Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications, RCC M-20 (Twenty) mixed mechanically , vibrated & placing in all depths including form work curing complete , conforming to Ministry of Surface Transport specification clause 1500,1700 & 2100 (latest revision)including all leads, lifts and carriage of materials by all mode of transportation and as per direction and satisfaction of the Engineer-in-Charge.	14.40	Per Cubic metre			
3	PCC 1:3:6 in Foundation Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including all leads, lifts and carriage as per entire satisfaction of Engineer-in-charge.	38.25	Per Rmt			
4	Supply, fitting and placing TMT bar reinforcement in foundation complete as per drawing and technical specification. clause 1000 and 1202 including all lead and lifts and carriage of materials as per entire satisfaction of Engineer-in-Charge.	1080.00	Per Kg			

Executive Engineer,
NH. Division,
HP.PWD., Nahan,