



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 19/09/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 17.09.2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	C/o link road Bada Saloor Kaurawala Km. 0/0 to 0/600 (SH:- Providing and laying Metalling and Tarring in Km. 0/0 to 0/500)	Rs. 3,37,063/-	Rs. 6,800/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on link road Kothipura to Parohi Deoth road Km. 0/0 to 8/600 (SH:- C/o Edge wall protection work for drain work).	Rs. 1,77,239/-	Rs. 3,600/-	Rs. 350/-	Three Month
3	Construction of Sub-Tehsil Building at Namhol (SH:- Construction of balance work of P/F Reprinted Steel sheet in Roofing)	Rs. 4,34,431/-	Rs. 8,700/-	Rs. 350/-	Three Month
4	Providing Protection work to Govt. High School building at Loharda in Distt. Bilaspur (HP) (SH:- C/o B/wall in P.C.C.) Deposit work	Rs. 1,51,840/-	Rs. 3,100/-	Rs. 350/-	Three Month
5	Construction of link road from Helipad to village Burhal Km. 0/0 to 3/500 (SH:- C/o 900mm dia hume pipe culverts at RD 1/095 to 1/390)	Rs. 1,99,663/-	Rs. 4,000/-	Rs. 350/-	Three Month
6	Restoration of Rain damages on Niharkhan Basla Km. 0/0 to 0/900 (SH:- C/o B/wall at RD 0/150 to 0/177)	Rs. 2,67,346/-	Rs. 5,400/-	Rs. 350/-	Three Month
7	Construction of Sub-Tehsil Building at Namhol (SH:- Construction of balance work in R.C.C. work, Providing and fixing door and window and C/o R/wall and Edge wall)	Rs. 4,51,136/-	Rs. 9,100/-	Rs. 350/-	Three Month
8	A/R & M/O Rajghat Sai Magzine Trivanighat road Km. 0/0 to 7/0 (SH:- Providing and laying interlocking block pavement at RD 5/400 to 5/495 & 6/935 to 6/970 & V-shape PCC drain at RD 5/400 to 5/520)	Rs. 3,69,344/-	Rs. 7,400/-	Rs. 350/-	Three Month
9	Construction of Sub-Tehsil Building at Namhol (SH:- Construction of balance of Providing and fixing Steel Truss work)	Rs. 4,99,606/-	Rs. 10,000/-	Rs. 350/-	Three Month
10	Balance work of store Shed/site office of Kothipura Section of Sub-Division No. III Bilaspur (SH:- Balance work P/F CGI Sheet Roofing, Tiles Flooring white washing, priming in Existing/New store Shed/office and Boundau wall at Nouni)	Rs. 3,48,698/-	Rs. 7,000/-	Rs. 350/-	Three Month
11	Construction of Sub-Tehsil Building at Namhol (SH:- Construction of balance work of P/L Tile and Painting work)	Rs. 3,52,238/-	Rs. 7,100/-	Rs. 350/-	Three Month
12	C/o link road from SNB road to village Khal Tibba Km. 0/0 to 7/0 (SH:- C/o 900mm dia hume pipe culverts at RD 0/500 and 0/720) Deposit work	Rs. 4,38,978/-	Rs. 8,800/-	Rs. 350/-	Three Month
13	Construction of Sub-Tehsil Building at Namhol (SH:- Construction of balance work of P/F Steel Truss and P/F G.I. Pipe)	Rs. 4,21,674/-	Rs. 8,500/-	Rs. 350/-	Three Month
14	C/o link road from SNB road to village Khal Tibba Km. 0/0 to 7/0 (SH:- C/o 900mm dia hume pipe culverts at RD 1/330 and 1/480) Deposit work	Rs. 4,40,155/-	Rs. 8,900/-	Rs. 350/-	Three Month
15	C/o link road from Main road to Gugga Basti in GP Tarsooh Km. 0/0 to 1/400 (SH:- Providing and laying in GP 1/0 to 1/200) Deposit work	Rs. 1,50,303/-	Rs. 3,100/-	Rs. 350/-	Three Month
16	Restoration of Rain damages on link road to village Bhuwai Km. 0/0 to 2/285 (SH:- C/o P.C.C. as a R/wall at RD 0/120 to 0/128)	Rs. 2,02,248/-	Rs. 4,100/-	Rs. 350/-	Three Month

17	Restoration of Rain damages on link road village Thurva to Harijan Basti Karotiwalla in GP Dharot in Km. 0/0 to 1/100 (SH:- C/o R/wall at RD 0/225 to 0/269)	Rs. 2,17,250/-	Rs. 4,400/-	Rs. 350/-	Three Month
18	Restoration of Rain damages on Kuthela Kairyan Bagchhal road Km. 0/0 to 10/815 (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RDS) for the year 2022-23 Job No. 11	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
19	Restoration of Rain damages on Baner Zakatkhana road Km. 0/0 to 7/0 (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RDS) for the year 2022-23 Job No. 12	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
20	Restoration of Rain damages on various road under Swarghat Sub-Division HPPWD Swarghat (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RDS) for the year 2022-23 Job No. 13	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
21	Restoration of Rain damages on CMM road NH-205 Km. 86/0 to 127/0 (SH:- Hiring of Excavator cum loader for removal of slips, clearing of road side drain and dressing of berms Km. 116/0 to 121/0) for the year 2022-2 Job No. 5	Rs. 49,581/-	Rs. 1,000/-	Rs. 350/-	One Month
22	Restoration of Rain damages on various road under Namhol Sub-Division (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RDS) for the year 2022-23 Job No. 4	Rs. 99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
23	Improvement of Navgaon Beri road Km. 4/350 to 23/700 (SH:- Providing and laying G-I, G-II, G-III in Km. 14/485 to 14/670) Deposit work	Rs. 2,02,512/-	Rs. 4,100/-	Rs. 350/-	Three Month
24	Construction of link road Katal Sandheli via Sanon Km. 0/0 to 7/0 (SH:- C/o 900mm dia hume pipe culvert at RD 0/080, 0/170 and 0/350) Deposit work	Rs. 3,09,828/-	Rs. 6,200/-	Rs. 350/-	Three Month
25	Repair of Rain Damages from SNB road to link road village Khal Tibba Km. 0/0 to 7/0 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 0/0 to 3/500) Deposit work for the year 2022-23 Job No. 9	Rs. 1,02,310/-	Rs. 2,100/-	Rs. 350/-	One Month
26	Repair and Maintenance on Rajpura Chilla Charanmore road 0/0 to 4/400 (SH:- Providing Tag welding by electric plant on tags provided for joining and fixing of crash barrier at various RDs between 0/410 to 0/165 and 1/166 to 2/375)	Rs. 98,518/-	Rs. 2,000/-	Rs. 350/-	One Month
27	Repair of Rain Damages from SNB road to link road village Khal Tibba Km. 0/0 to 7/0 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 3/500 to 7/0) Deposit work for the year 2022-23 Job No. 10	Rs. 1,02,310/-	Rs. 2,100/-	Rs. 350/-	One Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall summarily rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2022-

8973-81

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-1
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.
Dated:- 07-09-2022

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.			Estimated cost:- Rs.3,37,063/-Only.			
			Earnest Money :- Rs.6,800/-			
			Time:- Three Months.			
NAME OF WORK:- C/O link road Bada Saloor kaurawala km 0/00 to 0/600 (SH:- providing and Laying Metaling & Tarring in km 0/00 to 0/500)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 -1.00 (Zero point seven zero to one point zero)Kilogramme per Square metre using mechanical means as per Technical Specifications Clause 502. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax ,building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1601.25	Square metre.		Per Square metre.	
2	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 Kg. (Zero point two five to Zero point three zero)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1601.25	Square metre.		Per Square metre.	
3	Providing , laying and rolling of open-graded premix carpet of 20mm (Twenty millimetre)compacted thickness composed of crushed stone aggregate 13.2 mm to 5.6 mm (Thirteen point two millimetre to five point six millimetre) @ 0.27 cubic metres (Zero point two seven) per 10 square metre (Ten Square metre) mixed with penetration grade paving bitumen V.G-30 (Viscosity grade-Thirty) at the rate of 14.6 kg.(Fourteen point six kilogramme) per ten square metre of road surface to required line, grade and level to serve as wearing course on a previously prepared base including mixing and heating binder and aggregate in suitable plant, laying with paver finisher and rolling with a three wheel 80-100 KN (Eighty - hundred) capacity static road roller finished to required level and grade to be followed by seal coat of type-B by mechanical means as per MORD technical specification 2014. clause 508 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax ,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1601.25	Square metre.		Per Square metre.	

4	Providing and laying seal coat for sealing the voids in bitumenous surface laid to the specified levels, grade and cross fall using Type-B and as per Technical Specifications, 2014 Clause 510 using Bitumen (S-90) by Mechanical means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax ,goods and service tax, building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1601.25	Square metre		Per Square metre	
	Total					

Executive Engineer,
Bilaspur Division No. II,
HP. PWD, Bilaspur

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,77,239/-Only.						
Earnest Money :- Rs.3,600/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain damages on link road Kothipura to Parohi Deoth road km 0/00 to 8/600 (SH:- C/O edge wall protection work for drain work)						
Sr No.	Description of items.	Quantity		Rates in		Amount
		Figure.	Words.	Figure.	Words.	
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Cubic Metre		Per Cubic Metre	
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203, P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement three sand :six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.00	Cubic metres		Per Cubic metre	
Total						

Executive Engineer,
Bilaspur Division No. II,
M.P. P.W.D., Bilaspur (M.P.)

SCHEDULE OF QUANTITY.									
Name of Work:- Construction of Sub Tehsil building at Namhol (SH:- Construction of balance work of P/F Preprinted Steel sheet in Roofing)				Estimated Cost:- Rs.=4,34,431/-Only.					
				Earnest money:-Rs. 8,700/-					
				Time:- Three Month					
Sr No.	Description of items.	Quantity		Rates in.		Unit	Total		
				Figure	Words.				
1	2	3	4	5	6	7	8		
1	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts , 6mm (Six millimetre)diameter with preprinted limpet and rubber washers complete with all accessories including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	463.54	Square Meter			Per Square metre	8		
2	Providing and fixing ridges or hips 60cm. (Sixty centimetres)overall with 0.60mm (Zero point sixty millimeter) thick preprinted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20(Twenty) microns over 5 (Five) micron primer coating + back coat of polyester of 5 (Five) Microns over five microns primer coating including fixing with preprinted iron, J or L hooks bolts and nuts ,6mm(Six millimetre) diameter and preprinted G.I limpet and bitumen washer complete with all accessories as required as per the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	25.00	Running metre.			Per Running metre.			
3	Providing and fixing valleys 60cm. (Sixty centimetre) overall .60mm(Sixty millimetre) thick preprinted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of back coat of polyester of 5 micron over 5 (Five)microns primer coating including fixing with preprinted iron, J or L hooks, bolts and nuts , 6mm(Six millimetre) diameter and preprinted G.I limpet and bitumen washer complete with all accessories as required including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Running Meter			Per Running Meter			
4	Providing and fixing, 15cm. (Fifteen Centimetre) Wide 45cm. (Forty five centimeter) Overall semi-circular plain G.I sheet gutters with iron brackets, 40x3(Forty into three) millimetre size bolts and nuts and washer etc. including making necessary connections with rain-water pipe complete including carriage of materials within all leads, lifts and other incidentals, including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	30.00	Running metre			Per Running metre			
5	Providing and fixing polycarbonatd transparent sheet 1.20mm thick in roofing with galvanised J or L hooks bolts and nuts with G.I. Limpet and bitumen rubber washer complete with all accessories as required as per direction of Engineer-in-Charge including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.53	Square Meter			Per Square Meter			
						Total Rs.			

Executive Engineer,
Bilaspur Division No. 11.
Sd/- P.W.D. Bilaspur P.

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.1,51,840/-Only.									
Earnest Money :- Rs.3,100/-									
Time:- Three Months.									
NAME OF WORK:- Providing Protection work to Govt. High School building at Loharda in Distt. Bilaspur (HP) (SH:- C/O B/wall in P.C.C) (Deposit Work)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
				Figure.	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable compacted thickness including shorting and shuttering and pumping not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.62	Cubic Metre			Per Cubic Metre	7		
2	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300, 1603.1, 1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road way, camber, embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of blasting work/soft rock and 1/10th of jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.20	Cubic Metre			Per Cubic Metre			
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1.5.10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.50	Cubic metre.			Per Cubic metre			

4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v), 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos.			Each.	
Total							

Executive Engineer,
Bilaspur Division No. II.
Mr. PWD., Bilaspur M.P.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,99,663/-Only.

Earnest Money :- Rs.4,000/-

Time:- Three Months.

NAME OF WORK:- Construction of link road from Helipad to village Burhal km 0/0 to 3/500(SH):- C/O 900 mm dia Hume Pipe culverts at RD 1/095 (P 1/390)

Description of items.

Sr No.	Quantity	Figure.	Words.	Unit	Amount
1	83.74	4	5	Per Cubic Metre	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.				
2	7.53			Cubic metres	
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8)(One Cement four sand eight graded crushed stone aggregate) 40mm (Forty millimetre size) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802,803,1203and 1205.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.				
3	21.62			Cubic metres	
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203, P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand : six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.				
4	15.00			Running metre	
4	Providing and laying (to level or slopes) 900mm dia (Nine hundred millimetre dia) reinforced cement concrete pipe I.S. Class NP2 for culverts on first class bedding of granular material in single row, including fixing collars, with cement mortar 1:2 (One Cement two sand) but excluding the cost of excavation, M.O.R.D Technical specification clause 1108 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.				

5	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses 802,803,1202 and 1203 (1:5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.06	Cubic metre.			Per Cubic metre	
6	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.			Each.	
7	Providing concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802 ,803,1202 and 1204 , P C C grade M-20 Nominal mix (1:2:4) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.226	Cubic metre.			Per Cubic Metre	
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification,1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.62	Cubic metre.			Per Cubic Metre	
Total							

Executive Engineer,
Bilaspur Division H.A. II.
H.R. P.W.D., Bilaspur (C.P.)

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs.=2,67,346/-Only.	
		Earnest money:-Rs. 5,400/-	
		Time:- Three Months.	
.Name of Work:- Restoration of Rain damages on Niharkhan Basla km 0/00 to 0/900 (SH:- C/o B/wall at RD 0/150 to 0/177)			
Sr No.	Description of items.	Quantity	
		3	4
		Figure	Words.
		5	6
		Unit	Total
		7	8
1	2		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out, dressing of sides and bottom and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs., carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.06	Cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(one cement : Five sand: ten graded stone aggregate 40 mm (forty millimetre) nominal size on ground or under water and curing complete and including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.45	Cubic metre
9	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.00	Nos
			Each
			Total

Executive Engineer,
Bilaspur Division No. II,
J.P. PWD., Bilaspur, S.O.

SCHEDULE OF QUANTITY.

							Estimated Cost:- Rs.=4,51,136/-Only.
							Earnest money:-Rs. 9,100/-
							Time:- Three Month
Name of Work:- Construction of Sub Tehsil building at Namhol (SH:- Construction of balance work in R.C.C work , Providing and Fixing Door & Window and C/O R/wall & Edge wall)							

Sr No.	Description of items.	Quantity	Rates in.		Unit	Total
			Figure	Words.		
1	2 Providing form work with steel plates 3.15 mm (Three point fifteen millimetres) thick welded with angle iron in frames, 30x30x5mm (Thirty into five millimetres) so as to give a fair finish including centering, shuttering, strutting and propping etcetra with wooden battens and ballies upto height propping and centering below supporting floor to ceiling and removal of the same for insitu reinforced concrete and plain concrete work Columns pillar, post and struts, square, rectangular or polygonal in plan. including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	4	5	6	7
1						8
i)	Columns pillar, post and struts, square, rectangular or polygonal in plan.	52.49	Square Meter			Per Square Meter
ii)	Beams Cantilever girders and lintels, sides and soffits of beams, beams haunchings, cantilevers, bressumers and lintels in all heights and depth from floor..	10.87	Square Meter			Per Square Meter
2	Providing and laying mechanically mixed & vibrated cement concrete 1:1.5:3 (One cement: One point five sand : three graded crushed stone aggregate of 20mm (Twenty millimetres) nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in upto floor all level including carriage of material within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. .					
i)	Columns pillars posts and struts upto all floor level etc.	3.20	Cubic Meter			Per Cubic Meter
ii)	Suspended floor roofs landing and shelves and their support balconies, beams, girders, bressumers and cantilever upto all floor level .	1.49	Cubic Meter			Per Cubic Meter
3	Providing Tor steel reinforcement for Reinforced Cement Concrete work including bending, binding straighting and placing in position complete in all heights including cost of binding wires completed and other incidentals due for its completion for all floors including carriage of materials within all leads, lifts and other incidentals. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	800.00	Kilogram.			Per Kilogram.
4	Precast concrete block masonry (including quion blocks,jamb blocks, closer etc.) with solid concrete blocks of approved size made of cement concrete 1:3:6(One Cement three sand six graded stone aggregate, 40mm and down guage foundation and plinth upto all floor level,in cement mortar 1:6(One Cement six sand)including carriage of materials within all leads, lifts and other incidentals including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other constuction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.04	Cubic Meter.			Per Cubic Metre

5	15 mm(fifteen millimetres) cement plaster in single coat in cement mortar 1:6 (One cement :six sand) on the rough side of brick/ concrete/ stone walls for interior plastering upto all heights including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finishing even and smooth including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	58.30	Square Meter		Per Square Meter	
6	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	55.79	Cubic Metre		Per Cubic Metre	
7	Stone soling properly hand packed filling interslices with kharanja Stone and consolidating with power road road to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.58	Cubic metres		Per Cubic metre	
8	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . P.C.C, grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand :six graded stone aggregate 40mm (Forty millimetre)/nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	38.90	Cubic metres		Per Cubic metre	
9	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.14	Cubic metre.		Per Cubic metre	
10	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Nos.		Each	

11	Providing and laying Interlocking concrete block pavement, having thickness, 60mm (Sixty millimetre) as per drawings and Technical Specification clause 1504, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	108.00	Square metre.			Per Square metre.
12	supplying and fixing glass panes with putty and nails including removal of brokenglass panes wherever necessary :-plain glass 4mm thick. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	37.21	Square Meter			Per Square Meter
13	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought, framed and fixed in position 2nd class deodar wood including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.05	Cubic metre.			Per Cubic metre.
14	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows, including black enamelled iron butt hinges with necessary screws, 40mm (Forty millimetres) Second Class Deodar wood, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.85	Square metre.			Per Square Metre
15	Kota stone slab flooring 20 mm (average) thick base of cement mortar 1:4(1 cement : 4 sand) laid over and jointed with gray cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete. 25mm thick. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.12	Square Meter			Per Square metre
16	Kota stone slab 25mm thick in risers of steps skirting dado and pillar laid on 12mm (average) thick cement mortar 1:3(One cement three sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab. including rubbing and polishing complete including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.19	Square Metre			Per Square Metre
17	Providing and laying Duro stone vetrified tiles Nitco or its equivalent(300x300mmx8mm)(Three hundred milimetre into three hundred milimetre into Eight milimetre) in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm(Twelve milimetre) thick cement mortar 1:3 (One cement : Three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.04	Square Meter			Per Square Meter
Total:-						

Executive Engineer,
Bilaspur Division No. 11.
UP. P.W.D., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,69,344/-Only.

Earnest Money :- Rs.7,400/-

Time:- Three Months.

NAME OF WORK:- A/R & M/O Rajghat Sai Magazine Trivenighat road km 0/00 to 7/900 (SH:-Providing and laying interlocking concrete block pavement at R.D 5/400 to 5/495 & 6/935 to 6/970 & V-Shape P/C drain at RD 5/400 to 5/520)

Sr No.	Description of items.	Quantity		Rates in Words.		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification. 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 119.80	Cubic Metre	4	5	Per Cubic Metre	7
2	Providing, laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with waterat OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and technical specification clause 406 by Mechanical means with 1km lead including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same	43.55	Cubic metres			Per Cubic metre	
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803, 1202 & 1203 P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand : six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.46	Cubic Metre			Per Cubic Metre	
4	Providing and laying interlocking concrete block pavement, having thickness, 80mm (Eighty millimetre) as per drawings and Technical Specification clause 1504, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	435.50	Square metre.			Per Square metre.	
Total							

EXECUTIVE Engineer,
Bilaspur Division Hq. II
HRA PWD., Bilaspur M.P.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.							
							Estimated Cost:- Rs.=4,99,606/-Only.
							Earnest money:-Rs. 10,000/-
							Time:- Three Month
Name of Work:- Construction of Sub Tehsil building at Namhol (SH:- Construction of balance work of Providing & Fixing Steel Truss Work)							
Sr No.	Description of items.	Quantity	Rates in.			Unit	Total
			Figure	5	Words.		
1	2	3	4	5	6	7	8
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings, framed guards, bars ladders, railing brackets and similar work including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.43	Quintal.			Per Quintal.	
2	Providing and fixing moulded hand rail of M.S. hollow pipe 50mm(Fifty) millimetre dia welded in straight length over M.S. flat at top of vertical balusters including one coat of red oxide priming coat complete (M.S. flat & balusters of railings shall be measured & paid separately, including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	102.20	Running metre			Per Running Metre.	
							Total Rs.

Executive Engineer,
Bilaspur Division No. II,
H.R. PWD., Bilaspur (C.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,48,698/-Only.

Earnest Money :- Rs.7,000/-

Time:- Three Months.

NAME OF WORK:- Balance work of Store shed/site office of Kothipura Section of Sub-Division No-III Bilaspur (SH:-Balance work P/F CGI Sheet Roofing , Tiles Flooring Whitewashing, priming in Existing/ New store shed/ Office & Boundary wall at Nouni)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	12.11			Per Cubic Metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	25.80			Per Cubic metre	
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.850			Per Cubic Metre	
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.16			Per Cubic Metre	
5	Half brick masonry with non modular fly ash bricks of class designation 10, conforming to IS :12894, in super structure above plinth and upto floor V level cement mortar 1:4 (1 cement : 4 coarse sand including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	24.000			Per square metre	
6	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:4 (1 cement : 4 coarse sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.020			Per Cubic metre	
7	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (1 cement: 6 fine sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	142.880			Per square metre	

8	6 mm cement plaster of mix 1:3 (1 cement : 3 fine sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	20.693	square metre			Per square metre
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments to complete edge flooring with bricks of class designation Description Size of Tile 600x600 mm sqm 1360.70 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	12.28	square metre			Per square metre
10	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	9.14	square metre			Per square metre
11	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. Kiln seasoned and chemically treated hollow wood 35 mm thick shutters including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.880	square metre			Per square metre
12	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : Second class teak wood including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	3.798	square metre			Per square metre
13	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 250x16 mm including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.000	Nos.			Each.
14	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. Complete including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	14.000	Nos.			Each.

15	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :125 mm including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	16.000	Nos.		Each.
16	Distemping with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	96.340	square metre		Per square metre
17	Finishing walls with water proofing cement paint of required shade :New work (Two or more coats applied @ 3.84 kg/10 sqm) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	55.460	square metre		Per square metre
18	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	17.340	square metre		Per square metre
19	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	17.340	square metre		Per square metre
20	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	100.00	Kilogram		Per Kilogram
21	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	6.60	Cubic metre.		Per Cubic metre
22	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. GATE including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	205.800	Kilogram		Per Kilogram

23	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating not less than 275 gm/m ² 0.63 mm thick with zinc coating not less than 275 gm/ m ² including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	32.700	square metre		Per square metre
Total:-					

Executive Engineer,
 Bilaspur Division No. 11,
 H.P. PWD, Bilaspur.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.							
		Estimated Cost:- Rs.=3,52,238/-Only.					
		Earnest money:-Rs. 7,100/-					
		Time:- Three Month					
Name of Work:- Construction of Sub Tehsil building at Namhol (SH:- Construction of balance work of P/L Tile & Painting Work)							
Sr No.	Description of items.	Quantity	Rates in.		Unit	Total	
			Figure	Words.			
1	2	3	4	5	6	7	8
1	Providing and fixing M.S. BP Sheet 1.66mm One point sixty six millimetre)to 2mm (Two)millimetre thick in eaves board /facia /soffit /ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge. (Base members of steel work shall be measured & paid separately) including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	147.41	Square Meter			Per Square metre	
2	Providing and fixing 75 mm x60mm scrolls to suit to rounded hand rail in straight length complete second class deodar woodincluding carriage of materials within all leads, lifts and other incidentalsincluding carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.22	Running metre.			Per Running metre.	
3	Providing and laying Duro stone vetrified tiles Nitco or its equivalent(300x300mmx10mm)(Three hundred millimetre into three hundred millimetre into Ten millimetre) in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm(Twelve millimetre) thick cement mortar 1:3 (One cement : Three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	91.40	Square Meter			Per Square Meter	
	Painting two coats (excluding priming coat)on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt,dust and other foreign matter :- Ready mixed paint other than white including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	698.17	Square Meter			Per Square Meter	
4	Polishing two coats with french polish on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt,dust,and sand paped smooth and including a coat of wood fillerincluding carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.77	Square Meter			Per Square Meter	

5	P/F PVCspigot and socket waste and ventilating pipes(lead caulked joints to be measured and paid for separately 110 mm(One hundred ten millimetre) diameter, including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.00	Running metre.			Per Running metre.	
6	P/F PVCspigot and socket waste and ventilating pipes(lead caulked joints to be measured and paid for separately and 50 mm(Fifty millimetre), including carriage of materials within all leads, lifts and other incidentals diameter. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	No			Each	
						Total Rs.	

Executive Engineer,
 Engineer Division
 PWD., Bhopal
 P.

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=4,38,978/-Only.		
				Earnest money:-Rs. 8,800/-		
				Time:- Three Month.		
Name of Work:- C/o link Road from SNB road to Village Khál Tibba km 0/00 to 7/00 (SH:-C/O 900 MM dia Hume pipe culverts at Rd 0/500 & 0/720) (Deposit Work)						
Sr No.	Description of items.	Quantity	Unit	Rates in.		Total
				Figure	Words.	
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out, consolidation of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs., dressing of sides and bottom and backfilling in trenches with excavated suitable material. upto 3.00 mtrs. depth, including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	79.86	Cubic metre			Per Cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(one cement is to four sand is to eight graded stone aggregate 25 mm (Twenty five millimetre) nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.91	Cubic metre			Per Cubic metre
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification PCC 1:4:8 (One :Cement :four sand: eight graded crushed stone aggregate)40 mm (Forty Millimetre) .The minimum cement content should be not less than 170 kg per cubic metre including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.76	Cubic metre			Per Cubic metre
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803, 1202& 103 P.C.C. Grade M 10 (1:3:6) (One cement : Three coarse sand : Six graded stone aggregate) The minimum cement content should be not less than 220 kg per cubic metre including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.04	Cubic metre			Per Cubic metre
5	Providing and laying reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular materials in single row including fixing colour with cement mortar 1:2 but excluding excavation protection work and parapets clause 1106. 900 mm dia including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Running metre			Per Running metre

6	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802.804, 805, 806, 807, 1202 & 1204 .P.C.C. grade M-15 (i) Nominal mix 1:2.5:5(One Cement two and half sand five graded stone aggregate 40 mm nominal size. The minimum cement contents should not be less than 225 kg per cubic meter including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.92	Cubic Metre		Per Cubic Metre
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803, 1202& 103 PCC 1:2:4(One Cement :two sand : four garded stone aggregate). The minimum cement content should be not less than 320 kg per cubic metre M-20 flooring including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.220	Cubic Metre		Per Cubic Metre
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.48	Cubic Metre		Per Cubic Metre
					Total Rs.

Executive Engineer,
Bokaro Division No. 11,
P.W.D., Dhanbad

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs.=4,21,674/-Only.	
		Earnest money:-Rs. 8,500/-	
		Time:- Three Month	
Sr No.	Name of Work:- Construction of Sub Tehsil building at Namhol (SH- Construction of balance work of P/F Steel Truss & P/F G.I Pipe)	Quantity	
		Figure	Words.
1	Description of items.	Rates in.	
		Figure	Words.
1	2	3	4
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings, framed guards, bars ladders, railing brackets and similar work, including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.63	Quintal.
2	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint and in Trusses and trussed purlins in building including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	55.56	Quintal.
3	Providing & Fixing G.I pipe 100 mm dia (One hundred millimeter) dia including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.40	Running metre
		Total Rs.	

Executive Engineer,
Bilaspur Division No. II.
P.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs.=4,40,155/-Only.				Earnest money:-Rs. 8,900/-				Time:- Three Month.			
Name of Work:- C/o link Road from SNB road to Village Khal Tibba km 0/00 to 7/00 (SH:-C/O 900 MM dia Hume pipe culverts at Rd 1/330 & 1/480) (Deposit Work)													
Sr No.		Description of items.		Quantity		Rates in.		Unit		Total			
						Figure		Words.					
1		2		3		4		5		6		7	
1		Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out, consolidation of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs., dressing of sides and bottom and backfilling in trenches with excavated suitable material -upto 3.00 mtrs. depth, including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		79.37	Cubic metre							Per Cubic metre	8
2		Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(one cement is to four sand is to eight graded stone aggregate 25 mm (Twenty five millimetre) nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work complete in all respect as per drawing and technical specification including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		43.91	Cubic metre							Per Cubic metre	
3		Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification PCC 1:4:8 (One :Cement :four sand: eight graded crushed stone aggregate)40 mm (Forty Millimetre) .The minimum cement content should be not less than 170 kg per cubic metre including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		7.76	Cubic metre							Per Cubic metre	
4		Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202& 103 P.C.C. Grade M 10 (1:3:6) (One cement : Three coarse sand : Six graded stone aggregate) The minimum cement content should be not less than 220 kg per cubic metre including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		21.98	Cubic metre							Per Cubic metre	
5		Providing and laying reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular materials in single row including fixing colour with cement mortar 1:2 but excluding excavation protection work and parapets clause 1106. 900 mm dia including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		15.00	Running metre							Per Running metre	

6	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802.804, 805, 806, 807, 1202 & 1204 .P.C.C. grade M-15 (i) Nominal mix 1:2.5:5(One Cement two and half sand five graded stone aggregate 40 mm nominal size. The minimum cement contents should not be less than 225 kg per cubic meter including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.92	Cubic Metre			Per Cubic Metre	
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202& 103 PCC 1:2:4(One Cement :two sand : four garded stone aggregate). The minimum cement content should be not less than 320 kg per cubic metre M-20 flooring including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.220	Cubic Metre			Per Cubic Metre	
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.92	Cubic Metre			Per Cubic Metre	
						Total Rs.	

Executive Engineer,
Bilaspur Division No. II,
Bilaspur P.O., Bilaspur P.O.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=1,50,303/-Only.
							Earnest money:-Rs. 3,100/-
							Time:- Three Months.
Name of Work:- C/O Link road from Main road to Gugga Basti in GP Tarsooh km 0/00 to 1/400(SH):- Providing & laying solling in GP 1/00 to 1/200) (Deposit work)							
Sr No.	Description of items.	Quantity	Rates in.		Unit	Total	
			Figure	Words.			
1	2	3	4	5	6		
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	703.50	square metre		Per square metre		
2	consolidation of sub grade with road roller including making good the undulations etc. with earth or quarry soil etc and re-rolling the sub grade including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	703.50	square metre		Per square metre		
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405 of MORD specification 2014 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.35	Cubic metre		Per Cubic metre		
						Total Rs.	

Executive Engineer,
Bilaspur Division No. 11,
P.O. FWD., Bilaspur P.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,02,248/-Only.
 Earnest Money :- Rs.4,100/-
 Time:- Three Months.

Quantity at RD 0/120 to 0/128)

Sr No.	NAME OF WORK:- Restoration of Rain damages on link road to Village Bhuwai km 0/00 to 2/285 (SH:- C/O P.C.C as a R/wall at RD 0/120 to 0/128)	Quantity			Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.	Figure.		
1	2 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3		4		5	6	7
1		42.16	Cubic Metre				Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses.802,803,1202 and 1203 (1:5:10) without plum. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.44	Cubic metre.				Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Cubic metre.				Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.				Each.	
Total								

Executive Engineer,
 Bilaspur Division No. II
 H.P. & D.D. Division P

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=217250/-	
				Earnest Money:- Rs. 4400	
Name of work: - Restoration of Rain damages on Link Road village Thurva to Harijan Basti Karotiwalla in G.P Dharot in Km 0/0 to 1/100(SH:- C/O R/wall at Rd 0/225 to 0/269)				Time:-Three Month.	
Sr.No	Sub-head and item of work.	Quantit y	Rate	Unit	Amount
1	Earth work in excavation for structure as per drawing and technical specifications clause 305.1 I/C setting out constructions of shoring and bracing, removal of stumps and other deleterious materials and disposal up to a lead of 50m,dressing of slides and bottom and backfilling in trenches with excavated suitable materials. 1. ordinary (1) up to 3 meter depth including carriage of material ,with in all leads and lifts as per direction of Engineer-in -charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.54		per cubic metre	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 P.C.C nominal mix 1:5:10 (40 mm aggregates) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	91.94		per cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification,1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.60		per cubic metre	
4	Providing weep holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with all leads and lifts as per direction of Engineer in charge. The rate includes octroi, royalty Malkana toll tax imposed by the Government	36.00		Each	
				Total Rs.	

Executive Engineer,
Nilesapur Division No. II
K.P.

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain Damages on Kuthela Kairyan Bagchhal road km 0/00 to 10/815 (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-11						
Sr No.	Description of items.	Quantity	Rate In In Figure	In words.	Unit	Amount
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00	5	Hours	Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bilaspur Division No. II
H.P. PWD, Bilaspur (P.)

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain Damages on Baner Zakatkhana road km 0/00 to 7/00(SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-12						
Sr No.	Description of items.	Quantity	Rate In Figure	In words.	Unit	Amount
1	3	4	5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	127.00	Hours		Per Hours	
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bilaspur Division No. II.
H.R. PWD, Bilaspur, P.D.

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain damages on Various road under Swarghat Sub Division HPPWD Swarghat (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-13						
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00 Hours	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Excavator Division No. II
HPPWD, Swarghat

21

SCHEDULE OF QUANTITY.					
		Estimated Cost:- Rs.=49,581 /-Only.			
		Earnest Money:- Rs.= 1,000/-			
		Time:- one Months.			
Name of work :- Restoration of Rain damages on CMM road NH-205 km 86/00 to 127/00 (SH:- Hiring of Excavator cum loader for removal of slips , clearing of road side drain & dressing of berm km116/00 to 121/00) For the Year 2022-23 Job No.-5					
Sr No.	Description of items.	Quantity	Rate In In Figure	Unit	Amount
1	3	4	5		6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.00	Hours	Per Hours	6
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
	Total				

Executive Engineer,
Bilaspur Division No. 11.
H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.		
				Earnest Money:- Rs.= 2,000/-		
				Time:- one Months.		
Name of work :- Restoration of Rain damages on Various road under Namhol Sub-Division (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RDs) For the Year 2022-23 Job No.-4						
Sr No.	Description of items.	Quantity		Rate In		Unit
		In Figure		In words.		Amount
1	3	4	5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	127.00	Hours	Per Hours		
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
	Total					

Executive Engineer,
Bilaspur Division No. 11.
MR PWD., Bilaspur

SCHEDULE OF QUANTITY.

						Estimated cost: - Rs.2,02,512/-Only.
						Earnest Money :- Rs. 4,100/-
						Time:- Three Months.
NAME OF WORK:- Improvement of Navgoan Beri road km 4/350 to 23/700 (SH:- Providing and laying G-I, G-II, G-III in km 14/485 to 14/670). (Deposit Work)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	S	3	4	5	6	7
1	Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP.PWD, Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	623.00	Square metre.		Per Square metre.	7
2	Consolidation of sub-grade with road roller including making good the undulation etcetra with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP.PWD, specification including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	623.00	Square metre.		Per Square metre.	
3	Providing laying spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade and camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -1 (One) as per Technical Specification Clause 405. (By Mechanical means) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.30	Cubic metres		Per Cubic metre	
4	Providing laying spreading and compacting crushed stone aggregates of specific 63 to 45mm sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade and camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -2 (75mm) as per Technical Specification Clause 405(i). (By Mechanically means) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.73	Cubic metres		Per Cubic metre	

5	Providing laying spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN (Eighty -Hundred) in stages to proper grade and camber applying and brooming stone screening/binding materials to fill-up the interstices of course aggregate watering and compacting to the required density Grading-3 as per Technical Specification Clause 405.1)(By Mechanical means). including carriage of materials, within all leads , lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	109.03	Cubic metres			Per Cubic metre
						Total:-


 Executive Engineer,
 Bridge Division No. II,
 H.P. Road, Satepalli,

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.3,09,828/-Only.									
Earnest Money :- Rs.6,200/-									
Time:- Three Months.									
NAME OF WORK:- Construction of link road Katal Sandheli via Sanan km 0/00 to 7/00 (SH:- C/O 900 mm dia RCC Hume pipe culvert at Rd 0/080,0/170 and 0/350) (Deposit Work)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	122.75	Cubic Metre		Per Cubic Metre				
2	Providing and laying mechanically mixed and vibrated concrete, for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8)(One Cement four sand eight graded crushed stone aggregate)40mm(Forty millimetre size)nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802,803,1203and 1205.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.31	Cubic metres		Per Cubic metre				
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand : six graded stone aggregate 40mm (Forty millimetre)nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.06	Cubic metres		Per Cubic metre				
4	Providing and laying (to level or slopes)900mm dia/ Nine hundred millimetre dia (reinforced cement concrete pipe I.S.Class NP2 for culverts on first class bedding of granular material in single row, including fixing collars, with cement mortar 1:2(One Cement two sand)but excluding the cost of excavation, M.O.R.D Technical specification clause 1108 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges. The rates includes octroi royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.50	Running metre.		Per Running metre.				

5	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses 802,803,1202 and 1203 (1:5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	53.22	Cubic metre.		Per Cubic metre	
6	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.		Each.	
7	Providing concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1204, P.C.C grade M-20 Nominal mix (1:2:4) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.330	Cubic metre.		Per Cubic Metre	
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.72	Cubic metre.		Per Cubic Metre	
Total						

Executive Engineer,
Bilaspur Division No. II.
H.P. PWD, Bilaspur (H.P.)

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=1,02,310 /-Only.		
				Earnest Money:- Rs.= 2,100/-		
				Time:- one Months.		
Name of work :- Repair of Rain Damages from SNB road to link road village Khal Tibba km 0/00 to 7/00 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 0/00 to 3/500) (Deposit Work) For the Year 2022-23 Job No.-9						
Sr No.	Description of items.	Quantity	Rate In In Figure	Rate In In words.	Unit	Amount
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 130.00	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bilaspur Division No. II.
HP, PWD., Bilaspur.

SCHEDULE OF QUANTITY									
						Estimated cost :-Rs.98518/Only.			
						Earnest Money:- Rs.2000/			
						Time:- Three Months.			
Name of work:- Repair and Maintenance on Rajpura Chilla Charanmore Road Km 0/o to 4/400.(SH:- Providing Tag welding by electric plant on legs provided for jointing and fixing of crash barriers at various RDs between 0/410 to 1/165 & 1/166 to 2/375)									
Sr No.		Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	2	3	4	5	6	7			
1	Providing Tag welding by electric plant on legs provided for jointing and fixing of crash for their safety and stability including hire charges of Electric gennerator set carriage og welding and set and generator to site in all leads and lifts as per direction of Engineer-in- Charge.	272.00 Rmt			Per Running Meter				

hbf
 Executive Engineer,
 District Engineer Hq. II,
 U.P. PWD, Meerut P.

SCHEDULE OF QUANTITY.					Estimated Cost:- Rs.=1,02,310 /-Only.	
					Earnest Money:- Rs.= 2,100/-	
Name of work :- Repair of Rain Damages from SNB road to link road village Khal Tibba km 0/00 to 7/00 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 3/500to 7/000) (Deposit Work) For the Year 2022-23 Job No.-10					Time:- one Months.	
Sr No.	Description of items.	Quantity	Rate In Figure	In words.	Unit	Amount
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 130.00 Hours	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer,
Bikaner Division No. II.
HP. PWD, Bikaner (I.P.)