



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

E- Mail id – ee-bit2-hp@nic.in
Phone No. 01978-222551

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 30/09/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 29/09/2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Construction of link road from NH-205 to village Nal Km. 0/0 to 1/500 (SH:- C/o 900mm dia hume pipe culvert at RD 0/080 and 0/504)	Rs 2,04,122/-	Rs. 4,100/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on Kutehla Kairyan Bagchhal road Km. 0/0 to 10/815 (SH:- P.C.C. as R/wall at RD 3/110 to 3/125 and P.C.C. as B/wall at RD 2/315 to 2/325)	Rs 1,98,169/-	Rs. 4,000/-	Rs. 350/-	Three Month
3	Construction of Additional Accommodation to HPPWD Rest House at Namhol (SH:- Providing and laying 60mm thick cobble stone flooring in courtyard) Job No. 1	Rs.4,10,483/-	Rs. 8,300/-	Rs. 350/-	Three Month
4	Restoration of Rain damages on Namhol Rest House road Km. 0/0 to 0/300 (SH:- P.C.C. as R/wall at RD 0/246 to 0/254)	Rs. 1,37,300/-	Rs. 2,800/-	Rs. 350/-	Three Month
5	Repair and Maintenance on Laraghat to Bholi road Km. 0/0 to 10/500 (SH:- Providing and laying Thermoplastic paint in Km. 0/0 to 3/0 and 8/0 to 9/500)	Rs. 2,83,500/-	Rs. 5,700/-	Rs. 350/-	Three Month
6	Construction of Additional Accommodation to HPPWD Rest House at Namhol (SH:- Providing and laying 60mm thick cobble stone flooring in courtyard) Job No. 2	Rs.4,10,202/-	Rs. 8,300/-	Rs. 350/-	Three Month
7	Restoration of rain damages on link road Harizen Basti Tarsooh Km. 0/0 to 1/200 (SH:- C/o 900mm dia RCC hume pipe culvert at RD 0/780)	Rs. 2,11,999/-	Rs. 4,300/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on link road from Swarghat to Manjher via Matnoh Km. 0/0 to 5/950 (SH:- C/o wire crate as a B/wall at RD 3/631 to 3/661)	Rs. 2,14,960/-	Rs. 4,300/-	Rs. 350/-	Three Month
9	Construction of Additional Accommodation to HPPWD Rest House at Namhol (SH:- Providing and laying 60mm thick cobble stone flooring in courtyard) Job No. 3	Rs.4,09,499/-	Rs. 8,200/-	Rs. 350/-	Three Month
10	Restoration of Rain damages on link road from Swarghat to Manjher via Matnoh Km. 0/0 to 5/950 (SH:- C/o wire crate as a B/wall at RD 3/495 to 3/510)	Rs. 3,05,117/-	Rs. 6,200/-	Rs. 350/-	Three Month
11	Repair and Maintenance of Assistant Engineer office building at Swarghat Distt. Bilaspur (HP) N.R. Building (SH:- Construction of store/chowkidar room)	Rs. 1,08,552/-	Rs. 2,200/-	Rs. 350/-	Three Month
12	Construction of Additional Accommodation to HPPWD Rest House at Namhol (SH:- Providing and laying 60mm thick cobble stone flooring in courtyard) Job No. 4	Rs.4,09,106/-	Rs. 8,200/-	Rs. 350/-	Three Month
13	A/R & M/O link road to village Badoh Km. 0/0 to 2/0 (SH:- C/o wire crate as a B/wall at RD 0/780 to 0/800 and 0/900 to 0/925)	Rs.2,23,476/-	Rs. 4,500/-	Rs. 350/-	Three Month
14	Restoration of Rain damages on NH-205 CMM road Km. 86/0 to 127/0 (SH:- Hiring of Excavator cum loader/JCB and Tractor with Trolley for removal of slips, filling of berms and dressing of berms, clearance of drain at RD in Km. 100/0 to 105/0) for the year 2022-23 Job No. 16	Rs.1,07,540/-	Rs. 2,200/-	Rs. 350/-	One Month
15	Construction of Additional Accommodation to HPPWD Rest House at Namhol (SH:- Providing and laying 60mm thick cobble stone flooring in courtyard) Job No. 5	Rs.4,07,898/-	Rs. 8,200/-	Rs. 350/-	Three Month
16	Widening of Navgaon Beri road Km. 4/350 to 23/700 (SH:- Improvement /widening of road at RD 14/405 to 14/465)	Rs.87,953/-	Rs. 1,800/-	Rs. 350/-	Three Month

17	Restoration of Rain damages on Swahan Katiard Pangwana Km. 0/0 to 6/935 (SH:- Hiring of Excavator cum loader/JCB and Tractor with Trolley for removal of slips, filling of berms and dressing of berms, clearance of drain at various RD) for the year 2022-23 Job No. 15	Rs.1,09,631/-	Rs. 2,200/-	Rs. 350/-	One Month
18	Widening of Navgaon Beri road Km. 4/350 to 23/700 (SH:- Improvement /widening of road at RD 14/405 to 14/465)	Rs.97,469/-	Rs. 2,000/-	Rs. 350/-	Three Month
19	Restoration of Rain damages on link road from SNB road to village Mayooh (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) for the year 2022-23 Job No. 14	Rs.99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
20	Restoration of Rain damages on Kutehal Kairyan Bagchhal road Km. 0/0 to 10/815 (SH:- Extension of existing of 90mm dia hume pipe culvert at Rd 1/950)	Rs. 54,669/-	Rs. 1,100/-	Rs. 350/-	Three Month
21	Restoration of Rain damages on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- C/o R/wall at Rd 17/315 to 17/323)	Rs.99,789/-	Rs. 2,000/-	Rs. 350/-	Three Month
22	Restoration of Rain damages on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- C/o R/wall at Rd 17/323 to 17/331)	Rs.99,918/-	Rs. 2,000/-	Rs. 350/-	Three Month
23	Restoration of Rain damages on link road to village Kachouli road Km. 0/0 to 5/0 (SH:- C/o P.C.C. R/wall at RD 2/998 to 3/006.50)	Rs.49,663/-	Rs. 1,000/-	Rs. 350/-	Three Month
24	Restoration of Rain damages on CMM road NH-205 Km. 86/0 to 127/0 (SH:- Hiring of Excavator cum loader/JCB for removal of slip, clearing of road side drain and dressing of berm Km. 105/0 to 116/0) for the year 2022-23 Job No. 7	Rs.99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
25	Annual repair of link road for village Kala-Johar Km. 0/0 to 0/765 (SH:- C/o 1.50 meter span slab culvert at RD 0/525) Deposit work	Rs.4,97,107/-	Rs. 10,000/-	Rs. 350/-	Three Month
26	Construction of link road Bholi to lower Bholi Gassour(including 1 No. Bridge) from Km. 0/0 to 2/320 under Nabard (SH:- Preparation of detailed project report CBR test & preparation of detailed estimate for bridge)	Rs.1,53,600/-	Rs. 3,100/-	Rs. 350/-	Three Month
27	Construction of link road to village Nalag in Km. 0/0 to 1/900 (SH:- C/o R/wall at RD 0/370 to 03/85) Deposit work	Rs.2,34,938/-	Rs. 4,700/-	Rs. 350/-	Three Month
28	Construction of Circular Ambulance/jeepable road along the periphery of AIIMS Boundary wall in Km. 0/0 to 3/500 (SH:- Hiring of Excavator cum loader for formation cutting of Ambulance/jeepable road) Deposit work for the year 2022-23 Job No. 8	Rs.99,949/-	Rs. 2,000/-	Rs. 350/-	One Month
29	Restoration of Rain damages on link road to village Mayooh Km. 0/0 to 6/930 (SH:- C/o wire crate as a B/wall at RD 0/110 to 0/130)	Rs.95,533/-	Rs. 2,000/-	Rs. 350/-	One Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall summarily rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

Dated:- 20/09/2022

No.PW/NBT/CB/Tender-State/EA-1/2022-

10104-09

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-1
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,04,122/- Only.

Earnest Money :- Rs.4,100/-

Time:- Three Months.

NAME OF WORK:- Construction of link road from NH-205 to village Nal km 0/0 to 1/500 (SH:- C/O 900 mm dia RCC Hume pipe culvert at Rd 0/080 and 0/504)

Description of items.

Sr No.	Quantity	Figure.	Words.	Unit	Amount
1	3	4	5	6	7
1	81.32	Cubic Metre		Per Cubic Metre	
2	6.87	Cubic metres		Per Cubic metre	
3	21.85	Cubic metres		Per Cubic metre	
4	12.50	Running metre		Per Running metre	

2
Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Providing and laying mechanically mixed and vibrated concrete, for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8) (One Cement four sand eight graded crushed stone aggregate) 40mm (Forty millimetre size) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 802.803, 1203 and 1205.5 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges. The rates includes octroi, royalty, Malkana toll tax goods and service tax building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203, P.C.C. grade M-10 (i) Nominal mix 1:3:6 (One cement three sand six graded stone aggregate 40mm (Forty millimetre) nominal size. The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Providing and laying (to level or slopes) 900mm dia (Nine hundred millimetre dia) reinforced cement concrete pipe I.S. Class NP2 for culverts on first class bedding of granular material in single row, including fixing collars, with cement mortar 1:2 (One Cement two sand) but excluding the cost of excavation, M.O.R.D Technical specification clause 1108 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charges. The rates includes octroi, royalty, Malkana toll tax goods and service tax building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.

5	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification/Clauses 802, 803, 1202 and 1203 (1:5:10) without plum. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	37.80	Cubic metre.		Per Cubic metre
6	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.		Each.
7	Providing concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802, 803, 1202 and 1204, P.C.C grade M-20 Nominal mix (1:2:4) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.226	Cubic metre.		Per Cubic Metre
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.24	Cubic metre.		Per Cubic Metre
Total					

Executive Engineer,
Bilaspur Division (No. H)
J.P. PWD., Bilaspur (M.P.)

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.1,98,169/-Only.									
Earnest Money :- Rs.4,000/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain Damages on Kuthela Kairyan Bagchhal road km 0/00 to 10/815 (SH:- P.C.C as R/wall at Rd 3/110 to 3/125 and P.C.C as B/wall at Rd 2/315 to 2/325)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
		Figure.	Words.	Figure.	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	44.40	Cubic Metre			Per Cubic Metre	7		
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses 802,803,1202 and 1203 (1:5:10) without plum. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	82.60	Cubic metre.			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.40	Cubic metre.			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	58.00	Nos.			Each.			
Total									

Executive Engineer,
Bilaspur Division No. 11.
(H.A. PWD., Bilaspur)

SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.4,10,483/- Only.					
Earnest Money :- Rs.8,300/- Only					
Time:- Three Months.					
NAME OF WORK:- Construction of Additional Accommodation to HP.PWD Rest House at Namhol (SH:- Providing and Laying 60 mm Thick cobble stone flooring in courtyard) Job No-1					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2	3	4	5	6
1	Providing and Laying Heavy Duty Cobble Stone 100x100x60 mm (One Hundred into One Hundred into Sixty millimeter) of approved shade stone laid over 20 mm (twenty millimeter) average thick base of cement mortar 1:3 (one cement three coarse sand) with joints finished flush including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	146.10	Square Meter		Per Square Meter
Total					

Executive Engineer,
Bilaspur Division No. H
HP.PWD, Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.1,37,300/-Only.	
							Earnest Money :- Rs.2,800/-	
							Time:- Three Months.	
NAME OF WORK:- Restoration of Rain Damages on Namhol Rest House road km 0/00 to 0/300 (SH:- P.C.C as R/wall at Rd 0/246 to 0/254)								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
	2	3	4	5	6	7		
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil,ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsss and lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.80	Cubic Metre		Per Cubic Metre	7		
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	59.84	Cubic metre.		Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.52	Cubic metre.		Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	Nos.		Each.			
Total								

Executive Engineer,
Bilaspur Division Mo. H.
H.P.W.D., Bilaspur

5

SCHEDULE OF QUANTITY.					
Estimated Cost:- Rs.2,83,500/-					
Earnest Money:- Rs.5,700/-					
Time:- Three Months.					
Name of work:- Repair & Maintenance on Laraghat to Bholi road km 0/00 to 10/500(SH):- Providing and laying Thermoplastic paint in km 0/00 to 9/500)					
Sr No.	Sub-head and item of Work.	Quantity	Rates. Figure.	Words.	Unit. Amount.
1	Providing and laying of hot applied Thermoplastic compound 2.5mm thick including reflectorising glass beads @ 250 gms. Per Sqm area , thickness of 2.5mm is exclusive of surface applied glass beads as per IRC-35 .The finished surface to be level uniform and free from streaks and holes as per MORTH Specifications including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rates includes octroi, ,Malikana toll tax ,goods and service tax ,building and other construction work, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	450.00			Per Square metre.
				Total Rs.	

Executive Engineer,
Bilaspur Division Muz. H.
H.D. PWD., Bilaspur H.P.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,10,202/- Only.

Earnest Money :- Rs.8,300/- Only

Time:- Three Months.

NAME OF WORK:- Construction of Additional Accommodation to HP.PWD Rest House at Namhol (SH:- Providing and Laying 60 mm Thick cobble stone flooring in courtyard/d) Job No-2

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2 Providing and Laying Heavy Duty Cobble Stone 100x100x60 mm (One Hundred into One Hundred into Sixty millimeter) of approved shade stone laid over 20 mm (twenty millimeter) average thick base of cement mortar 1:3 (one cement three coarse sand) with joints finished flush including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	146.00	4 Square Meter	5 Per Square Meter	6 7	
Total							

Executive Engineer,
Bilaspur Division Ms. H.
HP, PWD., Bilaspur P

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=2,11,999/-Only.
 Earnest money:-Rs. 4,300/-
 Time:- Three Month.

Name of Work:- Restoration of Rain damages on Link Road Harizan Basti Tarsooh km 0/00 to 1/200 (SH):- C/O 900 mm dia RCC Hume Pipe Culvert at RD 0780)

Sr No.	Description of items.	Quantity	Rates in.		Unit	Total
			Figure	Words.		
		3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge, including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	40.06	Cubic Metre			Per Cubic Metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(One :Cement :five sand: Ten graded crushed stone aggregate) 40 mm (Forty Millimetre)nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.98	Cubic metre			Per Cubic metre
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification PCC 1:4:8 (One :Cement :four sand: eight graded crushed stone aggregate)40 mm (Forty Millimetre) nominal size.The minimum cement content should be not less than 170 kg per cubic metre including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.88	Cubic metre			Per Cubic metre
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202& 1203 P.C.C. Grade M 10 (1:3:6) (One cement : Three coarse sand : Six graded stone aggregate)40 mm (Forty Millimetre) nominal size . The minimum cement content should be not less than 220 kg per cubic metre including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.99	Cubic metre			Per Cubic metre
5	Providing and laying reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work and parapets clause 1106. 900 mm dia including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running metre			Per Running metre

6	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802.804, 805, 806, 807, 1202 & 1204. P.C.C. grade M-15 (i) Nominal mix 1:2:5.5 (One Cement two and half sand five graded stone aggregate 40 mm nominal size. The minimum cement contents should not be less than 225 kg per cubic meter including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.96	Cubic Metre			Per Cubic Metre
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 & 103 PCC 1:2:4 M-20 (One Cement :two course sand: four graded crushed stone aggregate) 20mm nominal size. The minimum cement content should not less than 320 kg per cubic metre flooring including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.11	Cubic Metre			Per Cubic Metre
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.36	Cubic Metre			Per Cubic Metre
9	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Nos			Each
						Total

Executive Engineer,
Bikampur Division No. H.
K.P. PWD., Baleshwar P.

SCHEDULE OF QUANTITY.

						Estimated cost:- Rs.2,14,960/-Only.
						Earnest Money :- Rs.4,300/-
						Time:- Three Months.
NAME OF WORK:-Restoration of Rain damages on Link Road from Swarghat to Manjher via Matnoh km 0/00 to 5/950(SH:- C/O Wire crate as a B/wall at RD 3/631 to 3/661)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	77.10	Cubic Metre		Per Cubic Metre	7
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301 including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.62	Cubic metre		Per Cubic metre	
					Total:-	

Executed by Engineer,
Bilaspur Division No. H.
HP-PWD, Bilaspur

SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.4,09,499/- Only.					
Earnest Money :- Rs.8,200/- Only					
Time:- Three Months.					
NAME OF WORK:- Construction of Additional Accommodation to HP.PWD Rest House at Namhol (SH:- Providing and Laying 60 mm Thick cobble stone flooring in courtyard) Job No-3					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2	3	4	5	6
1	Providing and Laying Heavy Duty Cobble Stone 100x100x60 mm (One Hundred into One Hundred into Sixty millimeter) of approved shade stone laid over 20 mm (twenty millimeter) average thick base of cement mortar 1:3 (one cement three coarse sand) with joints finished flush including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	145.75	Square Meter		Per Square Meter
Total					

Executive Engineer,
Bilaspur Division No. H.
HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.									
NAME OF WORK:- Restoration of Rain damages on Link Road from Swarghat to Manjher via Matnoh km 0/00 to 5/950(SH):- C/O Wire crate as a R/wall at RD 3/495 to 3/510)									
Estimated cost:- Rs.3,05,117/- Only.									
Earnest Money :- Rs.6,200/-									
Time:- Three Months.									
Sr No.	Description of items.	Quantity	Rates in			Unit	Amount		
			Figure.	4	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting up to any leads and upto any lift including dressing of stumps and other deleterious matter, and disposal of excavated suitable approved material. to the original surface in layers sides and bottom and backfilling in trenches with compacted thickness including shorting and shuttering and pumping not exceeding 150mm (one hundred fifty millimeters) up to all depth and any quantum of water including cleaning of slush which or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.29	Cubic Metre		Per Cubic Metre	7			
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire confirming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	199.22	Cubic metre		Per Cubic metre				
3	Construction of embankment with approved material obtained from borrow pits with a lift up to 1.5mtr and lead up to 1000mtr as per technical specification clause 301.5. Including carriage of materials within all leads and lifts as per direction of Engineer in Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.10	Cubic metre.		Per Cubic metre.				
							Total:-		


 Executive Engineer,
 Bilaspur Division Mo. H.
 B.P.W.D., Bilaspur M.P.

SCHEDULE OF QUANTITY.

NAME OF WORK:- Repair and Maintenance of Assistant Engineer office building at Swarghat Distt. Bilaspur (HP) (N.R building) (SH:-Construction of store/ Chowkidar Room)		Estimated cost:- Rs.1,08,552/-Only. Earnest Money :- Rs.2,200/- Time:- Three Months.					
Sr No.	Description of items.	Quantity	Figure.	Rates in Words.	Unit	Amount	
1	2 Providing form work with steel plates 3.15 mm (Three point fifteen millimetres) thick welded with angle iron in frames, 30x30x5mm (Thirty into five millimetres) so as to give a fair finish including centering, shuttering, strutting and propping etcetra with wooden battens and ballies upto height propping and centering below supporting floor to ceiling and removal of the same for insitu reinforced concrete and plain concrete work Columns pillar, post and struts, square, rectangular or polygonal in plan, including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	4	5	6	7	
i)	Flat surfaces such as soffits of suspended floor, roofs, landing and the like floor etc. up to any thickness.	13.21	Square Meter		Per Square Meter		
ii)	Beams Cantilever girders and lintels, sides and soffits of beams, beams haunchings, cantilevers, bressumers and lintels in all heights and depth from floor..	8.41	Square Meter		Per Square Meter		
2	Providing and laying mechanically mixed & vibrated cement concrete 1:2:4(One cement, two sand : four graded crushed stone aggregate of 20mm (Twenty millimetres) nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in upto floor all level including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.71	Cubic Meter		Per Cubic Metre		
3	Providing Tor steel reinforcement for Reinforced Cement Concrete work including bending, binding straightening and placing in position complete in all heights including cost of binding wires completed and other incidentals due for its completion for all floors including carriage of materials within all leads, lifts and other incidentals, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	325.20	Kilogram		Per Kilogram.		
4	Brick work using 2nd class common burnt clay building bricks in foundation, plinth and -Super-structure upto floor all level (Second Class Bricks). Cement mortar 1:6 (One cement, six sand) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.77	Cubic Meter		Per Cubic Meter		
5	6 mm plaster to ceiling in cement mortar 1:3(One Cement three sand) including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	15.84	Square Metre		Per Square Metre		

6	15 mm(fifteen millimetres) cement plaster in single coat in cement mortar 1:6 (One cement : six sand) on the rough side of brick/ concrete/ stone walls for interior plastering upto all heights including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finishing even and smooth including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	58.39	Square Meter		Per Square Meter
7	Providing and fixing 10mm (Ten millimetre)thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundred millimetre into six hundred millimetre into ten millimetre manufactured of approved shade and colour in flooring, treads of 1:3 (One cement : Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.43	Square Meter		Per Square Meter
8	White glazed tiles 6 mm thick in skirting, risers of steps and Dado 12 mm (Twelve millimeter) thick cement mortar 1:3 (One cement and three sand) and jointed with cement slurry including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.25	Square metre		Per Square Meter
9	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. (Eighty five G) with wire of dia 0.56 mm (Zero point five six)millimetre/for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws. 2nd class Deodar wood including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.60	Square Meter.		Per Square metre
10	Providing and fixing fly proof of galvanised M.S wire gauge of I.S gauge designation . 85 g with wire of dia 0.56mm to windows and clerestory windows including 60x20mm bedding with 2nd class deodar wood), including carriage of materials, with in all leads and lifts as directed by the Engineer -in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.42	Square Metre		Per Square metre
11	Providing and fixing aluminium tower bolts (barrel type) anodized colour and shade with bolts and nuts screws etc. 150 X 10mm (One hundred fifty into Ten millimetre) complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	No.		Each
12	Providing and fixing aluminium handles anodized transparent or dye to required colour and shade with necessary screws 125mm(One hundred twenty five millimetre)etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	No.		Each

13	Distemper two coats with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.92	Square Meter		Per Square Meter
14	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces (two coats) to give an even shade after thoroughly brushing the surface to remove all dirt dust and remains of loose, powdered material including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.31	Square Meter		Per Square Meter
15	Providing and fixing PVC water storage tank of ISI 12701 marked G.I Inlet & outlet connection, 15 mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement i/c hoisting to all heights above ground level 1000 litres net capacity tank including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each.
16	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (Medium grade) tube fittings and clamps including making good the wall, ceiling and floor 15 mm (Fifteen millimetre) nominal bore including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.60	Running metre		Per Running Metre.
17	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes Finolex ISI marked including fixing with approved adhesive 75 mm (Seventy Five millimetre) diameter etc. complete including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.50	Running metre.		Per Running metre.
18	Providing and fixing PVC floor trap ISI marked of self cleaning design, including fixing with approved adhesive, cost of cutting and making good the wall and floors 110x75mm. (One hundred ten into Seventy five millimetre) etc. complete including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each.
19	Providing and fixing 100 mm (One hundred millimetre) dia chromium plated grating of superior quality for floor, gully/Nahini trap including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		Each.

20	Providing and fixing stainless steel kitchen sink of approved standard ISI make with drain board and C.P. waste with C.I or M.S. brackets painted white including cutting holes and making good the same but excluding fitting 610 x 510 mm (Six hundred ten into Five hundred ten millimetre) with bowl depth 200 mm (Two hundred millimetre) including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	Nos.			Each
21	Providing and fixing chromium plated brass soap dish with C.P. brass brackets fixed to wooden cleats with C.P. brass screws including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00	Nos.			Each
22	Providing and fixing waste pipe flexible (coil type 32 mm (thirty two millimeter) including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1.00	Nos.			Each
23	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms 15 mm (Fifteen millimetre) nominal bore including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Nos			Each
24	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting with ready mix paint brushing with white lead for priming including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.77	Square Meter			Per Square Meter
25	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt dust and other foreign matter, sand papering and stopping with enamel paint other than white including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.73	Square Metre			Per Square Metre
26	Providing and Fixing bright finished/and black enamelled iron (helical door sprong 150 mm) including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.00	Nos			Each
Total:-						

Executive Engineer,
Bilaspur Division No. II.
MR PWD., Bilaspur

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,09,106/- Only. Earnest Money :- Rs.8,200/- Only Time:- Three Months.				
NAME OF WORK:- Construction of Additional Accommodation to HP.PWD Rest House at Namhol (SH:- Providing and Laying 60 mm Thick cobble stone flooring in courtyard) Job No-4						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Providing and Laying Heavy Duty Cobble Stone 100x100x60 mm (One Hundred into One Hundred into Sixty millimeter) of approved shade stone laid over 20 mm (twenty millimeter) average thick base of cement mortar 1:3 (one cement three coarse sand) with joints finished flush including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 145.61	4	5	6 Per Square Meter	7
Total						

Executive Engineer,
Bilaspur Division No. II.
H.R. PWD., Bilaspur D.P.

SCHEDULE OF QUANTITY.									
NAME OF WORK:- A/R & M/O Link Road to village Badoh km 0/00 to 2/00(SH:- C/O Wire crate as a B/wall at RD 0/780 to 0/800 & 0/900 to 0/925)				Estimated cost:- Rs.2,23,476/-Only.			Earnest Money :- Rs.4,500/-		
Sr No. Description of items.				Time:- Three Months.					
	Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
				Figure.	Words.				
	1	2	3	4	5	6	7		
	1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	143.55	Cubic Metre		Per Cubic Metre		7	
	2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire confirming to IS 280 and IS 4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301, including cost of form work and curing complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.62	Cubic metre		Per Cubic metre			
								Total:-	

Executive Engineer,
Bilaspur Division (No. II)
M. PWD., Bilaspur (P.P.)

SCHEDULE OF QUANTITY.					Estimated Cost:- Rs.=1,07,540 /-Only.		
					Earnest Money:- Rs.= 2,200/-		
					Time:- one Months.		
Name of work :- Restoration of Rain Damages on NH-205 CMM road km 86/00 to 127/00(SH):- Hiring of Excavator cum loader/JCB and Tractor with trolley for removal of slips, filling berms and dressing of berms, clearance of drain at Rd in km 100/00 to 105/00)For the Year 2022-23 Job No.-16							
Sr No.	Description of items.	Quantity		Rate In In Figure	In words.	Unit	Amount
1	3.	4		5			6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	95.00	Hours			Per Hours	
2	Providing one number tractor with trolley in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge .The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	95.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The tractor with trolley will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
Bilaspur Division No. II.
HB PWD., Bilaspur.

SCHEDULE OF QUANTITY.								Estimated cost:- Rs.4,07,898/- Only.			
								Earnest Money :- Rs.8,200/- Only			
								Time:- Three Months.			
NAME OF WORK:- Construction of Additional Accommodation to HP.PWD Rest House at Namhol (SH:- Providing and Laying 60 mm Thick cobble stone flooring in courtyard) Job No-5											
Sr No.	Description of items.	Quantity		Rates in			Unit	Amount			
				Figure.	Words.						
1	2	3		4	5	6	7				
1	Providing and Laying Heavy Duty Cobble Stone 100x100x60 mm (One Hundred into One Hundred into Sixty millimeter) of approved shade stone laid over 20 mm (twenty millimeter) average thick base of cement mortar 1:3 (one cement three coarse sand) with joints finished flush including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	145.18	Square Meter			Per Square Meter					
Total											

Executive Engineer,
Bilaspur Division No. II.
HP. PWD., Bilaspur P.

SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.87,953/-Only.					
Earnest Money :- Rs. 1,800/- only					
Time:- Three Months.					
NAME OF WORK:- Widening of Navgoan Beri road km 4/350 to 23/700 (SH:- Improvement/ Widening of road at RD 14/405 to 14/465)					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2	3	4	5	6
2	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing .and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana toll tax, Goods& service Tax or other taxes imposed by the Government. A recovery of useful stones for 19.37 cubic metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item	387.46	Cubic Metre		Per Cubic Metre
Total:-					

Executive Engineer,
Bilaspur Division No. II.
Dr. PWD., Bilaspur P.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=1,09,631 /-Only.
							Earnest Money:- Rs.= 2,200/-
							Time:- one Months.
Name of work :- Restoration of Road Damages on Swahan Katirad Pangwana km. 0/0 to 6/935). (Hiring of Excavator cum loader/JCB and Tractor with trolly for removal of slips, filling berms and dressing of berms, clearance of drain at various RD)For the Year 2022-23 Job No.-15							
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
			In Figure	In words.			
1	3	4	5				6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	113.00	Hours			Per Hours	
2	Providing one number tractor with trolly in good condition on hire bases at site of work for removal of slip within all leads and lifts as per direction of Engineer -in charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The tractor with trolly will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
Bilaspur Division No. II.
H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.97,469/-Only. Earnest Money :- Rs. 2,000/- only Time:- Three Months.				
NAME OF WORK:- Widening of Navgoan Beri road km 4/350 to 23/700 (SH:- Improvement/ Widening of road at RD 14/540 to 14/585)						
Sr No.	Description of items.	Quantity		Rates in		Unit
				Figure.	Words.	
1	2 Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300, 1603.1, 1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing .and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax, Goods& service Tax or other taxes imposed by the Government. A recovery of useful stones for 21.47 cubic metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item	3 429.38	Cubic Metre	4	5	6 Per Cubic Metre
Total:-						7

Executive Engineer,
Bilaspur Division No. II.
H.A. PWD., Bilaspur P

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.	
				Earnest Money:- Rs.= 2,000/-	
				Time:- one Months.	
Name of work :- Restoration of Rain damages on link road from SNB road to Village Mayoith (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various RD) For the Year 2022-23 Job No.-14					
Sr No.	Description of items.	Quantity		Rate In	
		In Figure	In words.	Unit	Amount
1	3	4	5		6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	127.00	Hours	Per Hours	
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
	Total				

Executive Engineer,
Bilaspur Division No. II.
N.P.W.D., Bilaspur P.

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.54,669/-Only.	
							Earnest Money :- Rs.1,100/-	
							Time:- Three Months.	
NAME OF WORK:- Restoration of Rain Damages on Kuthela Kairyan Bagchhal road km 0/00 to 10/815 (SH:- Extension of existing of 900 mm dia hume Pipe Culvert at RD 1/950)								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
1	2 Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and cartiage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 34.49	Cubic Metre	4 5	6 Per Cubic Metre	7		
2	Providing and laying mechanically mixed and vibrated concrete, for plain / reinforced concrete in open foundations for all type of structure complete of plain cement concrete (Nominal mixed 1:4:8)(One Cement four sand eight graded crushed stone aggregate) 40mm(Forty millimetre size)nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work as per drawing and M.O.R.D technical specification Clause 802,803,1202 and 1203 including cartiage of materials, within all leads and lifts as per direction of Engineer-in-Charges .The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.68	Cubic metres		Per Cubic metre			
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C grade M-10 (i) Nominal mix 1:3:6 (One cement : three sand :six graded stone aggregate 40mm (Forty millimetre)nominal size.The minimum cement contents should not be less than 250 Kg. (Two hundred fifty kilogram per cubic on ground or under water and curing complete including cartiage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.03	Cubic metres		Per Cubic metre			
4	Providing and laying(to level or slopes)900mm dia(Nine hundred millimetre dia)reinforced cement concrete pipe I.S.Class NP2 for culverts on first class bedding of granular material in single row, including fixing collars, with cement mortar 1:2(One Cement two sand)but excluding the cost of excavation, M O R D Technical specification clause 1108 including cartiage of materials, within all leads and lifts as per direction of Engineer-in-Charges .The rates includes octroi,royalty, Malkana toll tax goods and service tax,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running metre.		Per Running metre.			

5	Providing concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802 ,803,1202 and 1204 , P.C.C grade M-20 Nominal mix (1:2:4) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.113	Cubic metre.			Per Cubic Metre	
Total							

Executed Engineer,
 District Engineer No. 11,
 District Engineer,
 P.A. PWD., Gwalior M.P.

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.99,789/-Only.									
Earnest Money :- Rs.2,000/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:-C/O R/Wall at RD 17/315 to 17/323)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
				Figure.	Words.				
1	2	3		4	5	6	7		
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.12	Cubic Metre			Per Cubic Metre			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802.803, 1202 and 1203 (1.5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.32	Cubic metre.			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.48	Cubic metre.			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Nos.			Each.			
Total									

Executive Engineer,
Bilaspur Division Mo. II.
H.P. P.W.D., Bilaspur P.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.99,918/-Only.						
Earnest Money :- Rs.2,000/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:-C/O R/Wall at RD 17/323 to 17/331)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.32	Cubic Metre		Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1.5:10) without plumb, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	42.32	Cubic metre.		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.96	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Nos.		Each.	
Total						

Executive Engineer,
Bilaspur Division No. II,
H.A. PWD., Bilaspur P

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.49,663/-Only.						
Earnest Money :- Rs.1,000/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages of link road to village Kachouli road km 0/00 to 5/00 (SH:-C/O P.C.C R/Wall at RD 2/998 to 3/006.50)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.42	Cubic Metre		Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802.803, 1202 and 1203 (1:5:10) without plum. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.98	Cubic metre.		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.61	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.		Each.	
Total						

Executive Engineer,
Bilaspur Division No. II.
Bilaspur P.W.D., Bilaspur (C.P.)

SCHEDULE OF QUANTITY.					
Name of work :- Restoration of Rain damages on CMM road NH-205 km 86/00 to 127/00 (SH:- Hiring of Excavator cum loader for removal of slips , clearing of road side drain & dressing of berm km 105/00 to 116/00) For the Year 2022-23 Job No.-7			Estimated Cost:- Rs.=99,949 /-Only. Earnest Money:- Rs.= 2,000/- Time:- one Months.		
Sr No.	Description of items.	Quantity	Rate In In Figure In words.	Unit	Amount
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00 Hours	5	Per Hours	6
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
Total					

Executed by _____
Bilaspur Division No. II.
HP PWD., Bilaspur.

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs.4,97,107/-Only.			Earnest money:-Rs. 10,000/-			Time:- Three Month.		
Name of Work:- Annual Repair of link road for village Kala-Johar km 0/00 to 0/765(SH):- C/O 1.50 meter span slab culvert at RD 0/525) (Deposit Work)										
Sr No.	Description of items.	Quantity	Rates in.			Unit	Total			
			Figure	Words.	Figure			Figure	Words.	Figure
1	2	3	4	5	6	7	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	30.51	Cubic Metre			Per Cubic Metre				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(One Cement :five sand: Ten graded crushed stone aggregate) 40 mm (Forty Millimetre)/nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	25.86	Cubic metre			Per Cubic metre				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification PCC 1:4:8 (One Cement four sand: eight graded crushed stone aggregate)40 mm (Forty Millimetre) nominal size.The minimum cement content should be not less than 170 kg per cubic metre including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	5.20	Cubic metre			Per Cubic metre				
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803, 1202& 1203 P.C.C. Grade M 10 (1:3:6) (One cement : Three coarse sand : Six graded stone aggregate)40 mm (Forty Millimetre) nominal size . The minimum cement content should be not less than 220 kg per cubic metre including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	50.72	Cubic metre			Per Cubic metre				
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C. grade M-25 (i) Nominal mix 1:1.5:3(One Cement one and half sand three graded stone aggregate 20mm nominal size) The Cement content not less than 400 kg per cubic metre, including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.75	Cubic Metre			Per Cubic Metre				

6	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802.804, 805, 806, 807, 1202 & 1204 P.C.C. grade M-15 (i) Nominal mix 1:2:5.5 (One Cement two and half sand five graded stone) aggregate 40 mm nominal size. The minimum cement contents should not be less than 225 kg per cubic meter including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.96	Cubic Metre		Per Cubic Metre
7	Supplying, fitting and placing HYSD bar reinforcement (Fe-500) in Super-Structure complete as per drawings and Technical Specifications Clause 1002, 1010 and 1202 cutting bending binding and placing in position complete, including cost of binding wire and carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.56	metric Tonne		Per metric Tonne
8	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 & 103 PCC 1:2:4 M-20 (One Cement two course sand: four graded crushed stone aggregate) 20mm nominal size. The minimum cement content should not be less than 320 kg per cubic metre flooring including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.25	Cubic Metre		Per Cubic Metre
9	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.94	Cubic Metre		Per Cubic Metre
10	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos		Each
					Total

Executive Engineer,
Bikanpur Division No. II,
HP, PWD., Bikanpur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,53,600/-Only.

Earnest Money :- Rs. 3100/- only

Time:- Two Months.

NAME OF WORK:- Construtcion of Link Road Bholi to lower Bholi Gassour (Incliding 1No Bridge) from Km 0/0 to 2/320 under Nabard (SH:- Preparation of detailed project report CBR test & preparation of detailed estimate for bridge.

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Preparation of detailed proeject report for road after conducting Topographical survey plan and mark provisions on the survey plan which include the following provision as given below: (a) Topographical survey by digital total station with two second accuracy showing all features on survey plan like trees,culverts,bridges,electric poles,telephone poles,hand pimps ,schools, Habitant villages etc, (b) Draw cross sections at 15m (fifteen metre) intervals,L-Section and calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable. (c) Preparation of survey plan showing all provision on the topographical survey plan and preparation of Detailed project report as per MORD guidelines. Submission of draft copy & after getting approval from the competent authority the same may be fair out and be supplied in six sets duly printed A-4 size, relevant drawing on A-4 size alongwith soft copy of DPR & Drawings in CD Format will also be submitted	3 2.320	4	5	6 Per Kilometre	7
2	Conducting CBR value and pavement Design of Crust as per IRC:37-2018.	6 000	No		Each	
3	Preparation of Detailed estimate of Bridge on the basis of GAD Drawing including submission of 6 set+Soft copy of estimate for Bridge.	1 000	No		Rach	
Total:-						

Conditions:- 1. 75 % payment will released after approval of Manuscript DPR from the competent authority.

2. The balance payment will be released after submission of fair DPR in required set alongwith soft copy.

Executive Engineer,
Bilaspur Division No. II.
H.P. PWD., Bilaspur H.P.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.2,34,938/-Only.						
Earnest Money :- Rs.4,700/-						
Time:- Three Months.						
NAME OF WORK:- Construction of link road to Village Nalag in km 0/00 to 1/900 (SH:-C/O R/Wall at RD 0/370 to 0/385) (Deposit Work)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.35	Cubic Metre		Per Cubic Metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	98.40	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification ,1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.25	Cubic metre		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.00	Nos		Each.	
Total						

Executive Engineer,
Bijapur Division No. II
H.P.W.D., Bijapur P.

SCHEDULE OF QUANTITY.				Estimated Cost:- Rs.=99,949 /-Only.	
				Earnest Money:- Rs.= 2,000/-	
				Time:- one Months.	
Name of work :- Construction of Circular Ambulance / Jeepable road along the periphery of AIIMS Boundary wall km 0/0 to 3/500 (SH:- Hiring of Excavator cum loader for formation cutting of Ambulance / Jeepable road)(Deposit Work) For the Year 2022-23 Job No.-5					
Sr No.	Description of items.	Quantity	Rate In In Figure	Unit	Amount
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavey or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 127.00	5 Hours	Per Hours	6
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
	Total				

Executive Engineer,
Bilaspur Division No. II.
H.P. P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.95,533/-Only.
							Earnest Money :- Rs.2,000/-
							Time:- Three Months.
NAME OF WORK:- Restoration of Rain damages on link to village Mayoht km 0/00 to 6/930(SH):- C/O Wire crate as a B/wall at RD 0/1100 to 0/130)							
Sr No.	Description of items.	Quantity	Figure.	Words.	Unit	Amount	
1	2	3	4	5	6	7	
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsand lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.20	Cubic Metre		Per Cubic Metre	7	
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301, including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	62.50	Cubic metre		Per Cubic metre		
						Total:-	

Executive Engineer,
Bilaspur Division No. II.
H.P. PWD., Bilaspur(H.P.)