

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed item rate tenders are hereby invited on Form No.6 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 24-09-2022 upto 11.00 A.M and shall be opened on the same day 11.30 A. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working day before opening upto 2:00 P.M. The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S.N	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs)	Time	Cost of Form
1	C/O Jaman Ki Ser Harkaghat road Km 0/0 to 9/330 (SH:- P/L interlocking Paver block in Km 2/00 to 2/100) Under MMGPY (Deposit)	413804/-	8500/-	One Month	Rs.350/-
2	C/O Jaman Ki Ser Harkaghat Road Km 0/0 to 9/330 (SH:- P/L interlocking Paver block in Km 1/860 to 1/980) Under MMGPY (Deposit)	496564/-	10000/-	One Month	Rs.350/-
3	Construction of Boundary Wall around CCI building Village Nal Post office Dhangyar, tehsil Pachhad Distt. Sirmour H.P. (SH:- Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan, Village Nal).	452617/-	9500/-	One Month	Rs.350/-
4	Construction of Boundary Wall around CCI building Village Nal Post office Dhangyar, tehsil Pachhad Distt. Sirmour H.P. (SH:- Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan, Village Nal).	458400/-	9500/-	One Month	Rs.350/-
5	A/R v& M/O Oachghat Narag Road Km 0/0 to 14/0 (SH:- P/L interlocking Paver block in Km 0/0 to 0/100)	413804/-	8500/-	One Month	Rs.350/-
6	R/R damages on various roads under Galgal Shikore Sub Division (SH:- Removal of slips)	112840/-	2200/-	One month	Rs. 350/
7	R/R damages on Dilman Shinaghat road Km 0/0 to 0/750 (SH:- C/O PCC B/Wall between RD 0/170 to 0/200))	218798/-	4500/-	One month.	Rs. 350/
8	A/R & M/O Lawassa Chowki Preet Nagar road Km 0/0 to 42/0 (SH: - C/O B/Wall between RD 37/735 to 37/750).	198753/-	4000/-	One month.	Rs. 350/
9	A/R & M/O to various roads under Dilman Sub Division (SH:- Supply of fuel wood for patch work)	65000/-	1300/-	One month.	Rs. 350/
10	Sarahan Charech Mandi Kharana road Km 0/0 to 7/0 (SH:- ROFD in Km 5/0 to 5/450, R/Wall at RD 5/007 to 5/022)	498933/-	10000/-	One month.	Rs. 350/
11	A/R & M/O Narag Wasni Dinger road Km 0/0 to 17/600(SH:- Curve improvement at various RD's)	494031/-	10000/-	One month.	Rs. 350/
12	Construction of Link road from Naina Tikker Dagothar via Kenchi Mod 0/0 to 7/0 (SH: - ROFD from Km 0/215 to 0/295).	495256/-	10000/-	One month.	Rs. 350/
13	Construction of Link road from Naina Tikker Dagothar via Kenchi Mod 0/0 to 7/0 (SH: - ROFD from Km 0/495 to 0/580).	494035/-	10000/-	One month.	Rs. 350/

14	C/o Sub Tehsil office building at Narag Tehsil Pachhad Distt Sirmour H.P (SH:- C/O building portion including water supply and sanitary installation work, C/O septic tank, soak pit, rain water harvesting tank site development & C/O B/Wall , C/o approach road Balance work.	111345/-	2200/-	One month.	Rs. 350/
15	C/O Baru Sahib Road km 0/0 to 1/720 (SH:- C/O R/Wall of G.I wire crate at RD 0/945 to 0/960 (SCSP) Deposit.	394232/-	8000/-	One month.	Rs. 350/
16	C/O Dungaghat Baghtan road Km 0/0 to 13/0 (SH:- ROFD in Km 1/795 to 1/805, 3/435, to 3/455, , 8/840, 8/860 & C/O Unlined drain between Km 6/500 to 12/500)MNP	418277/-	8400/-	One month.	Rs. 350/
17	A/R & M/O on Chaurighat Sarsoo road Km 0/0 to 5/800 (SH:- Clearance of side drains, Maintenance of earthen shoulders)	454311/-	9000/-	One month.	Rs. 350/
18	C/O Banad Bohal Gagal Shikore road km 0/0 to 5/250 (SH:- C/O G-I wire crate at RD 3/580 to 3/595) Under MMGPY deposit	374557/-	7500/-	One month.	Rs. 350/
19	A/R & M/O Narag Wasni Dinger road Km 0/00 to 17/600 (SH:- Clearance of side drains, Maintenance of earthen shoulders)	446737/-	9000/-	One month.	Rs. 350/
20	C/O Banad Bohal Gagal Shikore road km 0/0 to 5/250 (SH:- C/O PCC drain, PCC Parapets in various RD's) Under MMGPY deposit	495953/-	10000/-	One month.	Rs. 350/

CERTIFICATE: - It is certificate that the tenders of above work are exigency/emergent nature and in Public interest.

TERMS & CONDITIONS:-

1. The contractor/bidders must submit their Permanent Income Tax account number /GST number on the tender alongwith copy of the same be attached with the application.
2. The contractor /Firms should attach copy of Registration /renewal with the application.
3. The contractor/bidders should quote his rate both in figures and words the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc., before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender rejected after due date and time will be rejected.
6. The contractor/Firm should be produce the detail of works in hand in HPPWD and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractor who does not have more than two works in hand in any HPPWD circle/Division up to Rs 1.00 crore each.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The officer shall remain valid up to 95 days.
10. The provisions of guidelines issued vide Principal Secretary (PW) to the Govt. of HP Shimla vide notification No PBW (B) A (3) 1/2020 dated Shimla-2 the 22th July 2020 regarding adoption of CPWD works manual 2019 & n other publication of CPWD in HPPWD shall also be applicable.
11. The tender form will not be issued to those contractors whose performance found un satisfactory.
12. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

NO.PW-SRN/Tender/2022-23-

Copy forwarded to the following for information and necessary action to:-

1. The Deputy Commissioner Nahan District Sirmour (H.P).
2. The Superintending Engineer 12th Circle HP.PWD Nahan.
3. The Executive Engineer IT (Cell) Nigam Vihar HP.PWD, Shimla for uploaded of notice inviting Tender on departmental website please.
4. All the Assistant Engineer working under this Division.
5. All the leading contractor working under this division.
6. The notice board.

-sdr
Executive Engineer,
Sarahan B&R Division,
HP.PWD, Sarahan.

Dated:- 17/9/2022

huse
Executive Engineer,
Sarahan B&R Division,

SCHEDULE OF QUANTITY

Name of work:- Oachghat Narag Road km 0/0 to 14/0 (SH:- P/L interlocking Paver block in km 0/0 to 0/100)

Estimated cost:-Rs. 4,13,804/-

Earnest money:- Rs. 8500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.			7
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per cubic meter.			
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	305.00	Per Square meter.			


Executive Engineer
Sarahan Division,
HP PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Jamun ki ser Harkaghat Road km 0/0 to 9/330 (SH:- P/L interlocking Paver block in km 1/860 to 1/980)

Estimated cost:-Rs. 4,96,564/-
Earnest money:- Rs. 10000/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per cubic meter.			
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	366.00	Per Square meter.			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Construction of Boundary Wall around CCI Building, Village Nal, Post Office Dhangyar, Tehsil Pachhad, Distt. Sirmaur (H.P.)
(SH: Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan, Village Nal)

Estimated cost:-Rs. 4,52,617-

Earnest money:- Rs. 9500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	76.80	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.80	Per Cubic Metre.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	32.000	Each			
4	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be struttred on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc.complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of for separately). Payment to be made per metre cost of total length of barbed wire used.	3300.00	Per Running Metre			


Executive Engineer
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- Construction of Boundary Wall around CCI Building, Village Nal, Post Office Dhangyar, Tehsil Pachhad, Distt. Sirmaur (H.P.)
(SH: Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan , Village Nal)

Estimated cost:-Rs. 4,58,400/-

Earnest money:- Rs. 9500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	26.62	Per Cubic Metre.			7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	53.85	Per Cubic Metre.			
3	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20 (Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3.28	Per cubic meter.			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	13.95	Per Cubic Metre.			
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	15.000	Each			
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works (Code 10.25.2)	1550.00	Per kg			

Subh
Executive Engineer,
Sarhan Division,
HPPWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- C/O Jamun ki ser Harkaghat Road km 0/0 to 9/330 (SH:- P/L interlocking Paver block in km 2/00 to 2/100)

Estimated cost:-Rs. 4,13,804/-
Earnest money:- Rs. 8500/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per cubic meter.			
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	305.00	Per Square meter.			

Dr. Jyoti
Executive Engineer,
Sarhan Division,
HP PWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R damages on various roads under Dilman Sub -Division (SH:- Removal of slips in various RD's)

Estimated cost:-Rs. 1,12,840/-

Earnest money: - Rs. 2500/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3 1240.00	4 Per Cubic Metre.	5	6	7


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R damages on Dilman Shinaghat road km 0/0 to /750 (SH:- C/O PCC B/Wall between RD 0/170 to 0/200)

Estimated cost:-Rs. 2,18,798/-
Earnest money:- Rs. 4500/-
Time Limit:- two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	35.20	Per Cubic Metre.			
	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	3.40	Per cubic meter.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	41.80	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	6.00	Each			


Executive Engineer,
Sarahan Division,
HP PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Lawassa Chowki Preet Nagar road km 0/0 to 42/0 (SH:- C/O B/Wall at RD 37/735 to 37/750)

Estimated cost:-Rs. 1,98,753/-
Earnest money:- Rs. 4000/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.65	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	39.30	Per Cubic Metre.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	20.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	8.25	Per Cubic Metre.			

Excellence Engineers
Sarhan Division,
H.P.P.W.D., Sarhan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to various roads under Dilman Sub-Division (SH:- Supply of feul wood for patch work)

Estimated cost:-Rs. 65000/-

Earnest money:- Rs. 1,300/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures. 5	in words 6	
1	2 Supply and stacking of dry mixed hard fuel wood of small size and stacked in proper stacks of proper size as per PWD specification and as per the direction of engineer in charge including carriage of material in all leads and lift including all incidental charges.	3 130.00	4 Quintal			7


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Sarahan Charech Mandi kharana road km 0/0 to 7/0 (SH:- ROFD in km 5/0 to 5/450 , R/Wall at RD 5/007 to 5/022)

Estimated cost:-Rs. 4,98,933/-
Earnest money:- Rs. 10,000/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 35.80 cum (thirty five point eighty) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1688.00	Per cubic metre.			
2	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	33.60	Per Cubic Metre.			
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	47.33	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven), including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	20.00	Each			

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.00	Per Cubic Meter.			


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Narag Wasni Dinger raod km 0/0 to 17/600 (SH:- Curve improvement at various RD'S)

Estimated cost:-Rs. 494031/-
Earnest money:- Rs. 10,000/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangements of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.84 cum (two hundred nienty seven point eighty four) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	2215.06	Per cubic metre.			


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Construction of Link road from Naina Tikker Dagother Via Kanchi More 0/0 to 7/0 (SH:- ROFD from km 0/215 to 0/295)

Estimated cost:-Rs. 4,95,256/-

Earnest money: - Rs. 10,000/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 218.30 cum (Two hundred eighteen and paise thirty) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1523.02	Per cubic metre.			


Executive Engineer
Sarhan Division,
HP.PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- Construction of Link road from Naina Tikker Dagother Via Kenchi More 0/0 to 7/0 (SH:- ROFD from km 0/495 to 0/580)

Estimated cost:-Rs. 4,94,035/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge for smooth riding. The recovery for stones, whether useful or not, for 212.46 cum (two hundred twelve point forty six) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3 1541.45	4 Per cubic metre.	5 5	6 6	7 7


Executive Engineer
Sarhan Division,
H.P.W.D., Sarhan

SCHEDULE OF QUANTITY

Name of work:- C/O of Sub-Tehsil office building at Narag Tehsil Pachhad Distt. Sirmour H.P (SH:- C/O building portion including water supply and sanitary installation work , C/O spetic tank, Soak pit, rain water harvesting tank site devolpement & C/O B/Wall C/O approach road Balance work)

Estimated cost:-Rs. 1,11,345/-

Earnest money:- Rs. 2500/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Providing and fixing anodized aluminum grill (anodized transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/ pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodized aluminum standard section around the opening, all complete as per requirement and direction of Engineering-charge. (Only weight of grill to be measured for payment).	119.51	Per Cubic Metre.			
2	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.57	Per Cubic Meter.			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY
Name of work:- C/O Baru Mangarh Road km 0/0 to 1/720 (SH:- C/O R/Wall of G.I wire crate at RD 0/930 to 0/960)

Estimated cost:- Rs. 3,94,232/-
Earnest money:- Rs. 8000/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	33.00	Per Cubic Metre.			
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	121.88	Per Cubic Metre.			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	35.10	Per Cubic Metre.			
4	Excavating supplying and filling of local earth (Including royalty) by mechanical transport upto a lead of 5 km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches plinth sides of foundation etc complete.	55.50	Per Cubic Metre.			


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

DRAFT SCHEDULE OF QUANTITY

Estimated

418277

Name of work:- C/O Dungaaght bagthan road km 0/0 to 13/0 (SH:- ROFD in km 1/795 to 1/805, 3/435 to 3/455, 8/840 to 8/860 & C/O Unlined drain between km 6/500 to 12/500)MNP

Earnest money: - Rs. 10000/-
Time Limit: - Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangements of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 114.09 cum (one hundred fourteen and paise zero nine) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1140.91	Per Running Metre			
2	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307.	6000.00	Per square metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/ R & M/O on Chrighat Sarsoo road km 0/0 to 5/800 (SH:- Clearance of side drains, Maintenance of earthan shoulders)

Estimated cost:- Rs. 4,54,311/-

Earnest money:- Rs. 10000/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of earth from the choked hill side drain as well as catch water drain and sperading it on the deppressed berms (wherever required and disposing of supulous soil on th valley side manually , as per the directions of the Engineer in Charge including carriage of all labour equipments and material to various locations through all model of transportation in all leads and lidts including all incidental charges	5460.00	Per Running Metre			
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903	7664.00	Per square metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Banad Bohal Gagal Shikore road km 0/0 to 5/250 (SH:- C/O G.I wire crate at RD 3/580 to 3/595)MMGPY Deposit

Estimated cost:-Rs. 3,74,557/-

Earnest money:- Rs. 7500/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	47.81	Per Cubic Metre.			
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	117.19	Per. Cubic Metre.			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	42.97	Per Cubic Metre.			

Executive Engineer
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,46,737/-

Name of work:- A/ R & M/O on Narag wasni dinger road km 0/00 to 17/600 (SH:- Clearance of side drains, Maintenance of earthan shoulders)

Earnest money:- Rs. 9500/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of earth from the choked hill side drain as well as catch water drain and sperading it on the deprsressed berms (wherever required and disposing of supulous soil on th valley side manually , as per the directions of the Engineer in Charge including carriage of all labour equipments and material to various locations through all model of transportation in all leads and lidts including all incidental charges	6200.00	Per Running Metre			
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903	6710.00	Per square metre			

July
Executive Engineer,
Sarahan Division,
HP PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- CC/O Banad Bohal Gagah Shikore road km 0/0 to 5/250 (SH:- C:- C/O PCC drain, PCC Parapets in various RDs) under MMGPY deposit)

Estimated cost:-Rs. 4,95,953/-

Earnest money:- Rs. 10000/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	103.27	Per Cubic Metre.			
2	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	61.87	Per Cubic Metre.			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix (1:2.5:5) i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.96	Per Cubic Metre.			


 Engineer
 Sarahan Division,
 HP.PWD., Sarahan