



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740

Dated 24-09-22

No.-PW/OSDN/ Tender-NIT/2021-22 9405-15
To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD.
Nirmand



Phone No.-01904-255140
Fax No. 01904-255740

NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on 06.10.2022 up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on 04.10.2022 between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on 04.10.2022 between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money	Time	Cost of tender form Rs.
1	R/R Damage on Anni Basta road Km 0/000 to 20/120 (SH;- Hiring of JCB for removal of slips dressing of road surface and construction of road side Kutchha drain in Km 0/000 to 20/210)	3,50,000/-	7000	Three Months	350/-
2	R/R Damage on various road under Neether Sub Division (SH;- Hiring of tipper for carriage of excavated earth for removal up to dumping site and shifting of others material on various road under Durah Section)	99,522/-	2000/-	One Months	350/-
3	R/R Damage on various road under Neether Sub Division (SH;- Hiring of tipper for carriage of excavated earth for removal up to dumping site and shifting of others material on various road under Neether Section)	99,522/-	2000/-	One Months	350/-
4	Periodical maintenance of Showad to Karana road Km 0/000 to 5/600 (SH;- Providing annual surface including surface correction with G-III in Km 6/000 to 8/000, 11/000 to 12/000 and 15/000 to 15/600 for the year 2022-23 balance work thereof)	2,84,316/-	6000/-	One Months	350/-

It is certified that the above tenders i.e Sr. No 1 to 4 are very urgent nature, So may be uploaded on department website in public interest


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand

on behalf of Governor of Himachal Pradesh

Name of work :- R.R. damages on Anni Basta road km. 0/00 to 20/210 (SH:- Hiring of JCB for removal of slips, dressing of road surface and construction of road side kutchra drain in km., 0/00 to 20/210 .)

SCHEDULE OF QUANTITY

Estimated Cost Rs.350000.00
Earnest Money Rs. 7000.00
Time :- Three months.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. The scroll hour of the machine up to site of work will fully be born by the contractor.	280.00			Per Hour	
					Total	

Executive Engineer,
Outer Seraj Division,
HP. PWD, Nirmand.

Name of work :- R.R. damages on various roads under NeetherSub-Division. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on various roads under Neether Section .)

Estimated Cost Rs. 99522
Earnest Money Rs.2000/-
Time :- One month.

SCHEDULE OF QUANTITY

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	194.00			Per Hour	
					Total	

Executive Engineer,
Outer Seraj Division,
HP. PWD, Nirmand.

SCHEDULE OF QUANTITY


Name of work :- R.R. damages on various roads under NeetherSub-Division. (SH:- Hiring of tipper for carriage of excavated earth for removal up to dumping sites and shifting of other materials on various roads under Durah Section.)

Estimated Cost Rs. 99522
Earnest Money Rs.2000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	194.00			Per Hour	
	Total					


Executive Engineer,
Outer Seraj Division,
HP. PWD, Nirmand.

Schedule of quantity									
name of work:- Periodic Maintenance of Showad Karana road K.M. 0/0 to 15/600,SH:- Providing annual surfacing including surface correction with WBM grading-3 in km 6/00 to 8/00, 11/00 to 12/0 and 15/00 to 15/600 for the year 2022-23) balance work thereof.									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-		284316.00	
				Figures	Words	Time	Earnest Money	One month	AMOUNT
1	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 404, including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	4.56	Per Cubic Metre						
2	Providing and applying priming coat with bitumen emulsion (SS-1) using bitumen distributor at the rate of 0.85 kg. (Zero point eight five Kilogramme) per sqm. on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of Ministry of rural Development 2004 clause of 503 including carriage of materials, plants equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	60.85	Per Square Metre						
3	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion pressure distributor @ 0.275 kg (Zero point two seven five Kilogramme) per square metre of the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of clause 503 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	608.48	Per Square Metre						
4	Providing and laying 30 mm (thirty millimetre) thick bituminous concrete with 100-120 PH batch type hotmix plant producing and average output of 75 tonne (Seventy five tonne) using crushed aggregates of specified grading premixed with bituminous binder @ 5.5 (Five point five) percent or mix and filler including addition Zycotherm @ 0.10 % (zero point ten percent) of weight of bitumen, transporting the hot mix to work site lying with a hydro static paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem roller to achieve the desired compection as per MORTH specification No. 50 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	18.26	Per Cubic Metre						
Total in Figures									


 Executive Engineer,
 Outer Seraj Division,
 HPPWD, Nirmal

Signature of Tenderer with seal