

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.PW-GHR-CB-NIT/E-Tendering / 2022-23-
To

10980-90

Dated:-

4th 10
2022

The Executive Engineer, (IT Cell)
Nirman Bhawan,
Nigam Vihar, Shimla.

Subject: -

Publishing of Tender Notice.

Sir,

Enclosed please find herewith the tender notice for uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of H.P. letter No. (PBW) BA(3)/2020 dated 16th July, 2021 as the work mentioned in the Tender Notice are urgent in nature and in public interest.

DA:- As above.

Yours faithfully,

Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

Copy along with copies of Notice forwarded for information:-

1. The Engineer-in-Chief HP.PWD.Shimla.
2. The Chief Engineers (MZ) HP.PWD Mandi.
3. The Superintending Engineer, 1st.Circle, HP.PWD Mandi.
4. The computer cell O/O Executive Engineer (IT Cell) Nirman Bhawan Nigam Vihar Shimla-2 for uploading the NIT on departmental site.
5. The Assistant Engineers working under the division.
6. Notice Board.
7. H.D.M./A.B.in this office.

Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

**Himachal Pradesh
Public works Department
Notice inviting Tender**

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **12-10-2022** up to 11.00 A.M. and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T./ tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on **11-10-2022**. The applications for issue of tender forms will be received up to 2.00 P.M. on **10-10-2022**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tenders shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr.No	Name of road/work	Estimated Cost	Earnest Money	Cost of Tender Form	Time Limit	Class of contractor
1	RRD on Shimla Mandi via Tattapani road km 146/000 to 181/400 (SH: Removal of Land slide slips at Various RDs)	4,92,396/-	10000/-	350/-	Two Months	D & C
2	RRD on Shimla Mandi via Tattapani road km 146/000 to 181/400 (SH: Removal of Land slide at RDs 179/900 to 180/090 and 177/920 to 178/150)	4,78,579/-	10000/-	350/-	Two Months	D & C
3	RRD on Chail Moviseri road km 0/00 to 11/200 (SH: Removal of Land slide slips at Various RDs)	4,93,767/-	10000/-	350/-	Two Months	D & C
4	Construction of Dhanotu Rohangaloo road km 0/00 to 32/400 (SH: Providing and fixing speed Breakers on various RD's)	4,12,755/-	8300/-	350/-	Two Months	D & C
5	Construction of Shimla Mandi road km 115/0 to 147/0 (Providing and fixing speed Breakers on various RD's)	4,71,720/-	9500/-	350/-	Two Months	D & C
6	Construction of Kuthachi Badhu via Sanjala KM 0/00 to 9/000 (SH: Providing and laying CC Pavement in Km 0/965 to 1/200)	4,51,397/-	10000/-	350/-	Two Months	D & C
7	Construction of Kuthachi Badhu via Sanjala KM 0/00 to 9/000 (SH: Providing and laying CC Pavement in Km 0/495 to 0/540, 0/675 to 0/840 and 0/930 to 0/950)	4,70,271/-	10000/-	350/-	Two Months	D & C
8.	Construction of Govt. Sen. Sec. School Chachiot Distt. Mandi H.P. (SH: construction of Toilet Block and Distempering) Deposit work.	3,91,264/-	8000/-	350/-	Three Months	D & C

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors shall show their registration / renewal of enlistment before issue of tender form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. Tenders Forms will be issued to those contractors who have sufficient experience in execution of similar types of works.
5. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
6. Contractors will have to submit appropriate **Earnest Money** in the shape of **F.D.R. GST No , ITR for the year 2021-22 and Pan No.** with the applications for getting issued the tender forms, failing which, the forms would not be issued.
7. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% and below 30% of estimated cost will be summarily rejected.
8. The contractor can apply only for one work at a time.

Executive Engineer,
Gohar Division,
H.P. PWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 492396/- only
Earnest Money: Rs 10000/- only
Time :- Two months

Name of Work :-RR Damages on Shimla Mandi via Tattapani road KM 146/000 to 181/400 (SH:- Removal of Land Slide slips at various RDs)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	4711.92			Per Cubic Metre	-
					Total	-


 Executive Engineer
 Gohar Division (B&R)
 HPPWD G.O.

SCHEDULE OF QUANTITY

Estimate Cost: Rs.478579/- only
 Earnest Money: Rs 10000/- only
 Time :- Two months

Name of Work :-RR Damages on Shimla Mandi via Tattapani road KM 146/000 to 181/400 (SH:- Removal of Land Slide at RDs 179/900 to 180/090 and 177/920 to 178/150)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	4579.70			Per Cubic Metre	
					Total	


 Executive Engineer
 Gohar Division (B&R)
 HPPWD Gohar

73

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 493767/- only
Earnest Money: Rs 10000/- only
Time :- Two months

Name of Work :-RR Damages on Chail Moviseri road KM 0/000 to 11/200 (SH:- Removal of Land Slide slips at various RDs)

S. No.	Sub Head and item of work	Dyt.	Rate in		Unit	Amount
			Figure	Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	4725.04			Per Cubic Metre	-
					Total	-


 Executive Engineer
 Gohar Division (B&R)
 H.P.PWD Gohar

DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 4,12,755/- only

Earnest Money: Rs 8300/- only

Time : Two month

Name of Work :- Construction of Dhanotu Rohangaloo road km 0/0 to 32/400 SH: Providing and fixing speed Breakers on various RD's

S. No.	Description of items.	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and fixing mode of sturdy plastic speed breakers AL-1006, diamention 350 mm x250 mm x50mm (three hundred fifty millimetre into two hundred fifty millimetre into fifty millimetre), 500x425x50 mm (fifty into four hundred twenty five into fifty millimetre) 500x425x75 mm (five hudhred into four hundred twentyfive into seventy five millimetre) Reflector PMMA in Amber colour and HP Moduled in ABS PC alloy are highly resident to severe impacts and harsh weather condtion. Its dovetail interlocking subnits make it bind perfectly into a one firmbump. the pre colour materials (Black/Yellow) and UV Stabiliar keep them perpetually colorful. Seudded with reflector on either side, they are clearly visible to the motorists during night hous. these breakers are idenl for private , Colonies, Hospital school , Colleges, universities, Security check points, Parking areas, loading sites, etc, in cities, Easily removable, these breakers can easily be relocated aas designed with in all leads and lifts of materials and as per directionof Engineer-in-Charge.	105.00	Rmt		Per running metre	
					Total	


 Executive Engineer
 Gohar Division
 HPPWD Gohar

DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 4,71,720/- only

Earnest Money: Rs 9500/- only

Time : Two month

Name of Work :- Construction of Shimla Mandi road km 115/0 to 147/0 SH: Providing and fixing speed Breakers on various RD's

S. No.	Description of items.	Qty.	Rate in		Unit	Amount
			Figure	Word		
1	Providing and fixing mode of sturdy plastic speed breakers Al-1006, diamention 350 mm x250 mmx50mm (three hundred fifty milimetre into two hundred fifty milimetre into fifty milimetre), 500x425x50 mm (fifty into four hundred twenty five into fifty milimetre) 500x425x75 mm (five hudnred into four hundred twentyfive into seventy five milimetre) Reflector PMMA in Amber colour and HP Moduled in ABS PC alloy are highly resident to severe impacts and harsh weather condntion. Its dovetail interlocking subnits make it bind perfectly into a one firmbump. the pre colour materials (Black/Yellow) and UV Stabiliar keep them perpetually colorful. Seudded with reflector on either side, they are clearly visible to the motorists during night hous. these breakers are idenl for private , Colonies, Hospital school , Colleges, universities, Security check points, Parking areas, loading sites, etc, in cities, Easily removable, these breakers can easily be relocated aas designed with in all leads and lifts of materials and as per directionof Engineer-in-Charge.	120.00	Rmt		Per running metre	
					Total	

(Signature)
Executive Engineer

Gohar Division

HPPWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 4,51,397/- only
Earnest Money: Rs 10,000/- only
Time : Two months

Name of Work :- Construction of Kutahchi Badhu via Sanjala KM 0/000 to 9/000 (SH:- Providing and laying CC Pavement in KM 0/965 to 1/200)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Rupees Nil		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials including 100 mm spread thickness (finished work including moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	10.72			Per Cubic metre	-
2	Providing and laying in position cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering with in all leads, lifts and other incidentals as per direction of Engineer -In -Charge complete in all respect.	67.95			Per Cubic metre	-
					Total	-

[Signature]
Executive Engineer
Gohar Division (R&R)
HPPWD Gohar

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 4,70,271/- only

Earnest Money: Rs 10,000/- only

Time : Two months

Name of Work :- Construction of Kutahchi Badhu via Sanjala KM 0/000 to 9/000 (SH:- Providing and laying CC Pavement in KM 0/495 to 0/540, 0/675 to 0/840 and 0/930 to 0/950)

S. No.	Sub Head and item of work	Qty.	Rate in		Unit	Amount
			Figure	Rupees Nil		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	10.63			Per Cubic metre	-
2	Providing and laying in position cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	70.91			Per Cubic metre	-
					Total	-


 Executive Engineer
 Gohar Division (B&R)
 HPPWD Cuttack

SCHEDULE OF QUANTITY

NAME OF Work:-Construction of Govt Sen Sec, School Chaichiot Distt Mandi (HP) (SH:- Construction of Toilet Block and Distempring) Deposit Work				Estimated Cost:- 391264 /- Earnest Money:- 8000/- Time :- Three Months		
S.No	Description of item	Qty.	In Fig.	Rate		Amount
				In word	Unit	
1.00	2	3	4	5	6	7
1	Providing and laying plain cement concrete in superstructure as per drawing and technical specifications R.C.C grade M 20 nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate) within all leads, lifts and carriage of materials and other incidentals. including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge. work in	1.31			cum	
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge. work in					
2.1	For door window and ventilator and glazed partition frames	199.92			Per Kg	
2.2	For shutter of door window and ventilator	247.54			Per Kg	
3	Providing and fixing 12 mm thick Pre-laminated particle board with decorative lamination on both sides, board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge.	36.80			Per Sqm	
4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 200x10mm (two hundred into ten millimetre) including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge. work	2.00			Each	
5	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150X10 mm including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	2.00			Each	
6	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	4.00			Each	
7	Providing and fixing ISI marked oxidised M.S. single acting spring hinges with necessary screws etc. complete 150 mm including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	2.00			Each	

8	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in-Charge.	9.00			Sqm	
9	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement : 3 sand) and jointed with cement slurry. (30x45cm) with 7 cm wide border/lifted at top including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in-Charge.	12.08			Sqm	
10	Distemping with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade. including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in-Charge.	1027.83			Sqm	
11	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.					
11.1	(c) 15 mm (fifteen millimetre) nominal bore	20.00			Rmt	
12	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm (twenty five to forty millimetre) nominal bore including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00			Each	
13	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1000.00			Liter	
14	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 110 mm (one hundred ten millimetre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	21.50			rmt	
15	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 75 mm (SEVENTY FIVE millimetre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	26.50			rmt	
16	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.					
16.1	I) 110mm (one hundred ten millimetre) dia	2.00			Each	
16.2	II) 150 mm (one hundred fifty millimetre) dia	2.00			Each	
17	Providing and fixing PVC plain double equal branch ISI marked including fixing with approved adhesive etc. including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.					
17.1	I) 110mm (one hundred ten millimetre) dia	1.00			Each	

18	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm (one hundred millimetre) sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required with vitreous china orissa pattern W.C. pan of size 580X440 mm (five hundred eighty into four hundred forty) with integral type foot rests including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	Each	
19	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	Each	
20	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe 40mm (forty millimetre) dia including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.00	Each	
21	Providing and fixing uplasticsed PVC connection pipe with brass unions 45 cm (forty five centumetre) length 15 mm (fifteen millimetre) nominal bore including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.00	Each	
22	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	Each	
23	Providing and Fixing Angular stop cock with wall flange of opel prime no. CON 150083KN Stop Cock of Jaquar or equivalent including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	Each	
24	Providing and Fixing Soap dish recessed type stainless steel AHS-1531 of Jaquar or equivalent including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.00	Each	
25	Providing and fixing Towel Rack with lower hanger 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms. superior quality including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00	Each	
26	Providing and fixing gun metal gate valve with G.I. wheel of approved quality (screwed end) : including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.			
27	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	Each	
27.1	15mm (fifteen millimetre) nominal bore	3.00	Each	
28	Providing and fixing PVC floor trap of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete. 110 mm X 90 mm (one hundred ten into nineteen millimetre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.			
Total:-				

Executive Engineer
B & R Division
H.P.P.W.D Gohar