

Himachal Pradesh
Public Works Department

No.PW/PLP/CB/TA/2022-23/- 14150760

Dated:- 6-10-2022

To


✓ The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.

Subject:- Publishing of Tender Notice.

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Pr. Secy.(PW) to the Govt. of H.P. letter No. PBW (B)A9(3)1/2020 dated Shimla-26th July 2021.


It is certified that the work mentioned in the Notice Inviting Tenders are urent in nature and in public interest.

DA/ NIT, SQs


Executive Engineer,
Palampur Division,
HPPWD, Palampur.

Copy forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
2. The Drawing Branch in this office.
3. All the Assistant Engineers working under this Division.


Executive Engineer,
Palampur Division,
HPPWD, Palampur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'SHORT NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 14.10.2022 up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 13.10.2022 up to 4.00 P.M and the application for issue of tender form shall be received on 12.10.2022 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Restoration of Rain damage on Parour Lahla Chachian road Km 1/00 to 10/00 (SW:- C/o R/Wall on RD 1/570 to 1/575.50)	Rs4,74,568/-	Rs. 9500/-	Three Months
2	Restoration of Rain damage on Parour Lahla Chachian road Km 1/00 to 10/00 (SW:- C/o R/Wall on RD 1/575.50 to 1/581)	Rs4,74,568/-	Rs. 9500/-	Three Months
3	Restoration of Rain damage on Parour Lahla Chachian road Km 1/00 to 10/00 (SW:- C/o R/Wall on RD 1/581 to 1/586)	Rs. 4,30,735/-	Rs 8700/-	Three Months
4	Restoration of Rain damage on Parour Lahla Chachian road Km 1/00 to 10/00 (SW:- C/o R/Wall on RD 1/586 to 1/591)	Rs. 4,30,735/-	Rs 8700/-	Three Months

Terms & Conditions

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/570 TO 1/575.50)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/570 TO 1/575.50)							Estimated cost Rs.	474568.00
							Earnest Money Rs.	9500.00
							Time Limits	Three Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains etc. in all kind of soil (not exceeding 1.5 m (one point five Metre) in width or 10 Per Square Metre (ten square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto any height, including getting out the excavated soil and disposal of surplus excavated soil asdirected, within a lead from the edge of excavation all kind of soil complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	17.33			Per cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc.as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	52.25			Per square metre			
3	Providing and laying in position cement concrete of specified grade 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	52.81			Per cubic metre			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : Five coarse sand : ten graded stone aggregate 40 mm (forty Millimetre) nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	38.50			Per cubic metre			
5	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.25			Per cubic metre.			
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	16.00			Each			

Executive Engineer,
Palampur Division
HP.PWD Palampur.




Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/575.50 TO 1/581).

DRAFT SCHEDULE OF QUANTITY


Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/575.50 TO 1/581).							Estimated cost Rs.	474568.00
							Earnest Money Rs.	9500.00
							Time Limits	Three Mon
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains etc. in all kind of soil (not exceeding 1.5 m (one point five Metre) in width or 10 Per Square Metre (ten square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto any height, including getting out the excavated soil and disposal of surplus excavated soil asdirected, within a lead from the edge of excavation all kind of soil complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	17.33			Per cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filelets, kerbs and steps etc.as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	52.25			Per square metre			
3	Providing and laying in position cement concrete of specified grade 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	52.81			Per cubic metre			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : Five coarse sand : ten graded stone aggregate 40 mm (forty Millimetre) nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	38.50			Per cubic metre			
5	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.25			Per cubic metre.			
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	16.00			Each			

Executive Engineer,
Palampur Division
HP.PWD Palampur.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/581 TO 1/586).

Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.			
			Time Limits			
			In Figures	In Word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains etc. in all kind of soil (not exceeding 1.5 m (one point five Metre) in width or 10 Per Square Metre (ten square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto any height, including getting out the excavated soil and disposal of surplus excavated soil asdirected, within a lead from the edge of excavation all kind of soil complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	15.75			Per cubic metre	430735.00
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc.as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	47.50			Per square metre	8700.00
3	Providing and laying in position cement concrete of specified grade 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	48.00			Per cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : Five coarse sand : ten graded stone aggregate 40 mm (forty Millimetre) nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	35.00			Per cubic metre	
5	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.50			Per cubic metre.	
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	12.00			Each	


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur.

Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/586 TO 1/591).

DRAFT SCHEDULE OF QUANTITY

Name of work:- Name of work:- Rain damage of Parour, Lahla, Chachian Road km 1/00 to 10/00 (SH:- C/O R/wall on Rd 1/586 TO 1/591).							DRAFT SCHEDULE OF QUANTITIES		
							Estimated cost Rs.		430735.00
							Earnest Money Rs.		8700.00
							Time Limits		Three Months
Sl. No.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains etc. in all kind of soil (not exceeding 1.5 m (one point five Metre) in width or 10 Per Square Metre (ten square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto any height, including getting out the excavated soil and disposal of surplus excavated soil asdirected, within a lead from the edge of excavation all kind of soil complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	15.75			Per cubic metre				
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	47.50			Per square metre				
3	Providing and laying in position cement concrete of specified grade 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	48.00			Per cubic metre				
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : Five coarse sand : ten graded stone aggregate 40 mm (forty Millimetre) nominal size) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	35.00			Per cubic metre				
5	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.50			Per cubic metre.				
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	12.00			Each				

Executive Engineer,
Palampur Division
HP.PWD Palampur.

84