

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23- 13471-73 Dated:- 4/10/2022

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 14.10.2022 up to 11:00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 13.10.2022 upto 01:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of damages on caused due to laying of OFC by Signal Regiment Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/00 to 17/810. (SH:- Construction of Retaining wall at RD 12/315 to 12/326.50)	4,86,065/-	9,700/-	350/-	One month
2	Annual repair and maintenance of non residential building of HPPWD Sub-Division Padhar. (SH:- Providing and laying panelling, wooden flooring in A.E. room, JE room at 1 st floor Assistant Engineer office Padhar)	4,85,053/-	9,700/-	350/-	One month
3	Annual repair and maintenance of non residential building of HPPWD Sub-Division Padhar. (SH:- Providing and laying almirah, panelling in JE room at ground floor, diary dispatch room of Assistant Engineer office Padhar)	1,88,832/-	3,800/-	350/-	One month
4.	Annual repair and maintenance of non residential building of HPPWD Sub-Division Padhar. (SH:- Providing and laying panelling, wooden flooring in JE room at 1 st floor, C.B. for JE, diary dispatch room of Assistant Engineer office Padhar)	4,93,668/-	9,900/-	350/-	One month
5	Annual repair and maintenance of non residential building of HPPWD Sub-Division Padhar. (SH:- Providing and laying almirah, panelling, wooden flooring in SDC room, JE room at first floor of Assistant Engineer office Padhar)	4,72,531/-	9,500/-	350/-	One month
6	Restoration of rain damages on Padhar Nauhali road Km 0/0 to 14/500. (SH:- Construction of retaining wall in PCC 1:4:8 at RD 4/335 to 4/350)	3,65,004/-	7,300/-	350/-	One month

- Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

- The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.

2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


**Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)**

Schedule of Quantity

Estimated Cost:- Rs. 486065.00
 Earnest Money:- Rs. 9700.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km. 0/00 to 17/810

Sub Head:- Construction of retaining wall at RD 12/315 to 12/326.50 .

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.20 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	75.69 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	17.94 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	38.00 Nos.			Each	
					Total	


 Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar

Schedule of Quantity

Estimated Cost:- 485053.00
 Earnest Money:- 9700.00
 Time:- One month

Name of work:- Annual repair and maintenance of non residential building of H.P.W.D. Sub-Division Padhar.
Sub Head:- Providing and laying panelling, wooden flooring in AE room, JE room at 1st floor of Assistant Engineer office Padhar.

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing 17mm (seventeen millimetre) thick laminated MDF Board for panelling of approved brand and manufacture including frame work, profile and skirting as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.465 Sqm.			Per square metre	
2	Providing and fixing W1-Paraquit or action tesa clip in prelaminated wooden flooring (M.D.F.) with poly sheet and thermocoal sheet with door profile and inside moulding lock with all fitting etcetera complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.500 Sqm.			Per square metre	
3	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board both side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	46.800 Sqm.			Per square metre	
4	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board one side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	19.470 Sqm.			Per square metre	
	Total:-					

Executive Engineer,
 Mandi Division No.1,
 H.P.P.W.D. at Padhar.

Schedule of Quantity

Estimated Cost:- 188832.00
 Earnest Money:- 3800.00
 Time:- One month

Name of work:- Annual repair and maintenance of non residential building in Padhar Sub-Division HP.PWD. Padhar under Mandi Division No.1.HP.PWD. at Padhar.
Sub Head:- Providing and laying almirah, panelling in JE room at ground floor, diary dispatch room of Assistant Engineer office Padhar.

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing 17mm (seventeen millimetre) thick laminated MDF Board for panelling of approved brand and manufacture including frame work, profile and skirting as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.74 Sqm.			Per square metre	
2	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board one side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	13.20 Sqm.			Per square metre	
3	Providing and fixing 1mm (one millimetre) thick Mica one side laminated for panelling of approved brand and manufacture including framework, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	13.20 Sqm.			Per square metre	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 493668.00
Earnest Money:- 9900.00
Time:- One month

Name of work:- Annual repair and maintenance of non residential building of H.P.P.W.D. Sub-Division Padhar.

Sub Head:- Providing and laying panelling, wooden flooring in JE room at 1st floor, C.B. for JE, diary dispatch room of Assistant Engineer office Padhar.

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing 17mm (seventeen millimetre) thick laminated MDF Board for panelling of approved brand and manufacture including frame work, profile and skirting as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	24.07 Sqm.			Per square metre	
2	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board one side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.88 Sqm.			Per square metre	
3	Providing and fixing 1mm (one millimetre) thick Mica one side laminated for panelling of approved brand and manufacture including framework, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.88 Sqm.			Per square metre	
4	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board both side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	36.96 Sqm.			Per square metre	
5	Providing and fixing W1-Paraquit or action tesa clip in prelaminated wooden flooring (M.D.F.) with poly sheet and thermocoal sheet with door profile and inside moulding lock with all fitting etcetera complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	19.25 Sqm.			Per square metre	
	Total:-					


Executive Engineer,
Mandi Division No.1,
H.P.P.W.D. at Padhar.

Schedule of Quantity

Estimated Cost:- 472531.00
 Earnest Money:- 9500.00
 Time:- One month

Name of work:- Annual repair and maintenance of non residential building of H.P.P.W.D. Sub-Division Padhar.
Sub Head:- Providing and laying almirah, panelling, wooden flooring in SDC room, JE room at 1st floor of Assistant Engineer office Padhar.

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board both side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	51.240 Sqm.			Per square metre	
2	Providing and fixing 1mm (one millimetre) thick Mica one side laminated for panelling of approved brand and manufacture including framework, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.920 Sqm.			Per square metre	
3	Providing and fixing 17mm (seventeen millimetre) thick laminated MDF Board for panelling of approved brand and manufacture including frame work, profile and skirting as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.690 Sqm.			Per square metre	
4	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board one side laminated for cupboard of approved brand and manufacture including frame work, profile as per specification complete with approved colour and design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.840 Sqm.			Per square metre	
5	Providing and fixing bright finished brass handles 100mm (one hundred millimetre) with screws etcetera complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	82.000 Nos.			Each	
6	Providing and fixing 100mm (one hundred millimetre) oxidised M.S. double acting spring hinges with necessary screws etcetera complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	82.000 Nos.			Each	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 H.P.P.W.D. at Padhar.

Schedule of Quantity

Estimated Cost:- Rs. 365004.00
Earnest Money:- Rs. 7300.00
Time:- One month

Name of work:- Restoration of rain damages on Padhar Nauhali road Km. 0/0 to 14/500.
Sub Head:- Construction of retaining wall in PCC 1:4:8 at RD 4/335 to 4/350.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	30.90 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	53.97 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.05 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	18.00 Nos.			Each	
					Total	

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar