



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Telephone No:-01782-240075
e-mail:-ee-kum-hp@nic.in

No. PW-KMS-AB-NIT/2022-23- 12891-98

Dated: - 14/10/22

To


✓ The Executive Engineer (IT Cell),
HP, PWD, Shimla-2

Subject: -

Publication of Tender Notice


Enclosed please find herewith the tender of works as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 16.07.2021 as the works mentioned in the tender notice are urgent in nature and public interest.

Encl: - Notice Inviting tender &
Schedule of Quantity and certificate.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

Copy to the Superintending Engineer, 11th Circle,
HP.PWD., Rampur Bsr. for information please.

Copy to Drawing Branch in this office.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER "

Sealed item/percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD. Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before **21.10.2022** up to **11:00 AM** and will be opened on same day at **11:30 PM** in the presence of intending contractors or their authorized representatives who may wish to be present.

The application for issue of tender form shall be received on **20.10.2022** up to **1.00 PM**. The tender form can be had from his office against cash payment (Non-refundable) on **20.10.2022** up to **5.00 P.M.**

The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

1. **Name of Work :-** C/O 50 bedded Civil Hospital at Kumarsain Tehsil Kumarsain Distt. Shimla HP.(SH:- Providing stand for placing water tanks). Estimated Cost:-4,97,548/- Earnest Money:-10000/- Time:- One Month.
2. **Name of Work:-** C/O 50 bedded Civil Hospital at Kumarsain Tehsil Kumarsain Distt. Shimla HP.(SH:- Providing & Fixing MS brackets sun shade in Ramp Block). Estimated Cost:-4,43,258/- Earnest Money:- 8900/- Time:- One Month.
3. **Name of Work:-** C/O 50 bedded Civil Hospital at Kumarsain Tehsil Kumarsain Distt. Shimla HP.(SH:- Providing & Fixing MS brackets sun shade in Main Block). Estimated Cost:-4,81,219/- Earnest Money:- 9700/- Time:- One Month.

Terms and conditions:-

1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPF No along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 90 days.

Note:- The rates quoted by the contractors should be 5% above to 30 % below only otherwise the tenders will be rejected.

Executive Engineer,
Kumarsain Division
HP.PWD, Kumarsain

Dated:- 14/10/2022

No.PW-KMS-AB-NIT/2022-23-

12840-49

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.

Copy to the Deputy Commissioner Shimla, District Shimla (H.P)

Copy to the Sub-Divisional Officer @ Kumarsain, Distt. Shimla (H.P.)

Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.

Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)

Copy to all Assistant Engineers under this Division for information & n.a.


Copy to various contractors for information.

Copy to Notice Board of this office.

Executive Engineer,
Kumarsain Division,
HP.PWD, Kumarsain

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO. PW-KMS-AB-NIT/ 2022-23-
12840-90 DATED 14/10/2022 ARE URGENT NATURE AND
PUBLIC INTEREST.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

SCHEDULE OF QUANTITY

Estimated cost:-Rs.497548/-

Earnest money:-Rs.10000/-

Time allowed:-One month.

Name of work:-Construction of 50 beded Civil Hospital at Kumarsain Tehsil Kumarsain Distt. Shimla HP(SH:-Providing stand for placing water tanks).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all kind of soils including all leads and lifts as per direction of Engineer-in-Charge.	1.22 m3			Per cubic metre.	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level in cement concrete 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	0.950 m3			Per cubic metre.	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level in cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	2.23 m3			Per cubic metre.	
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	2.75 m3			Per cubic metre.	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	3919.44 Kg.			Per Kilogramme.	
Total:-						


Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

SCHEDULE OF QUANTITY


Estimated cost:-Rs.443258-

Earnest money:-Rs.8900/-

Time allowed:-One month.

Name of work:-Construction of 50 bedded Civil Hospital at Kumarsain , (SH:-Providing and fixing MS brackets sun shade in Main Block).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In girding frame in gutter bar ladder, railing, bracket, gates and similar works including entire carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge.	3080.32 Kg			Per Kilogram	
	Total:-					


Executive Engineer,
Kumarsain Division,
HP.P.W.D., Kumarsain.

SCHEDULE OF QUANTITY


Estimated cost:-Rs.481219-

Earnest money:-Rs.9700/-

Time allowed:-One month.

Name of work:-Construction of 50 beded Civil Hospital at Kumarsain , (SH:-Providing and fixing MS brackets sun shade in Main Block).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In greeting frame in gutter bar ladder, railing, bracket, gates and similar works including entire carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge.	3344.12 Kg			Per Kilogram	
	Total:-					


Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.