

NO:-PW/SD/CB/TA/NIT /2022- 23-

To

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

14389

Dated- 1-10-2022

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2,

Subject:-


Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and sechdule of quantity.


Executive Engineer
B&R Division Shillai
HP PWD Shillai

CERTIFICATE

Certified that the tenders of works, as called vide this office letter No.PW-SD-
CB-TA 2022-23- 14390-99 dated 1-10-22 are of urgent nature.


Executive Engineer
B&R Division Shillai
HP PWD Shillai


Public Works Department
Notice inviting Tender

Engineer Shillai, Division HP, PWD on behalf of governor of himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP PWD. So as to reach in this office as per time schedule given below.
Date of receipt of application of tenders forms:- 12-10-2022 at 10:00 AM, Up To 12:00 PM

1. Date of receipt of application of tenders forms:- 12-10-2022 at 10:00 AM, Up To 12:00 PM
2. Date of issue/ sale of tender Forms:- 12-10-2022 at 12:00 PM, Up To 3:00 PM
3. Date of receipt of tender:- 12-10-2022 at 3:30 PM, Up To 4:00 PM
4. Date of opening of tender:- 12-10-2022 at 4:30 PM,

Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender Form	Eligible of class of Contractor
Restoration of rain damages to Shillai Achhoti Pandiyat road km. 0/0 to 7/500 (SH-Construction of R/wall at RD 5/810 to 5/847)	491534/-	9850/-	One Month	350/-	C & D Class
A/R & M/O Non residential court Building at Shillai Distt Sirmour HP. (SH-Providing and fixing PVC panling and linoleum flooring sheet at Court building)	333333/-	6700/-	One Month	350/-	C & D Class

1. Terms and conditions :- The tender documents shall be issued only to these contractors firms who fulfill the following criteria and submit the following documents with the application.
2. The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
3. The contractors should quote the rates of all the items in the tenders both in figures and words.
4. Income Tax and GST No. latest clearance certificate.
5. The contractors/firms shall accompany his enlistment /renewal and EPF submit before the award of tender.
6. The contractor should apply for two works only at a time for tenders.
7. The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reason.


Executive Engineer
B&R Division Shillai
HP PWD Shillai

dated- 1-10-2022

PW-SD-CB-TA-2022-23-

Copy forwarded for information and wide publicity to:- 14390-97

1. The Superintending Engineer in 12th HP PWD in Nahan.
2. All the Assistant Engineer working under this Division.
3. A/B and D/B in this office.
4. Notice Board.

Executive Engineer
B&R Division Shillai
HP PWD Shillai

SCHEDULE OF QUANTITY

Job Name of Work : A/R & M/o Non residential Court Building at Shillai Tehsil Shillai Distt Sirmour H.P. (SH:- Providing and fixing PVC Panling and Linolium flooring sheet at Court building)

Job.- Estimated Cost:- 333333/- Only.
Earnest Money:- 6700/- Only
Time Limit: - One month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Providing and fixing wall panelling with hollow 8mm (Eight millimetre) thick P.V.C. panels of 10'/12'(width and any height . The PVC panels should be posted with designer wall including fixing of "U" Channel/ Engle/ tees necessary nuts & Screw etc. on their edge of wall/ roof and offset. Within all leads lifts. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	103.40	Per Square metre			
2	Linolium covering to floor. Plain or Coloured laid with an approved adhesive on sub floor including cutting and fixing complete to sub floor including demp proofing treatment 3.2mm thick including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	25.48	Per Square metre			
3	Providing and fixing brass bib cock of approved quality, 15mm nominal bore including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	3.00	Each			
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	79.67	Per Square metre			
5	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 4.0 mm (Four milimetre)thick glass panes including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge.	5.81	Per Square metre			
6	Providing pre-laminated with decorative lamination on both side exterior Grase-I MDF board 18 mm(Eighteen milimetre) thick conforming to IS: 14587. including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	15.30	Per Square metre			
				Total:-		

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name & Address of Contractor with Phone No.:-

Executive Engineer

Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY						Estimated Cost:- 491534/- Only. Earnest Money:- 9850/- Only Time Limit: - One Month	
Name of work:- Restoration of rain damages to Shillai Achhoti Pandiyat road Km 0/0 to 7/500 (SH:- Construction of R/wall at RD 5/810 to 5/847).						Job:-	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	39.22 Cubic metre	Per cubic metre				
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	112.85 Cubic metre	Per cubic metre				
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	54.00 Nos.	Each				
					Total:-		

Note:-The contractor shall procure all the materials conformint to specification MORT&H at his own risk and cost.

Name & Address of Contractor with Phone No.:-

Executive Engineer
Shillai Division
HP PWD Shillai

