

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office **10.10.2022 upto 10:30 AM and shall be opened on the same day at 11:00 AM** in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Schedule	
1.	Last date for tender receipt of application for tender form	07.10.2022 upto 4:00 PM
2.	Last date of sale of tender forms.	08.10.2022 upto 4:00 PM
3.	Date of receipt of tender forms	10.10.2022 upto 10:30AM
4.	Date of opening of tenders	10.10.2022 at 11:00 AM

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1.	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road km 48/0 to 87/0 (SH:- C/O PCC R/wall between km 59/543 to 59/549).	4,47,159/-	9000/-	One month	350/-
2.	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road km 48/0 to 87/0 (SH:- C/O PCC R/wall between km 59/531 to 59/537).	4,54,000/-	9000/-	One month	350/-
3.	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road km 48/0 to 87/0 (SH:- C/O PCC R/wall between km 59/537 to 59/543).	4,54,394/-	9000/-	One month	350/-
4.	Restoration of rain damages on Rehari Gussan to Kathli Bharan road km 0/0 to 13/0 SH:- C/O PCC R/wall in km 9/990 to 9/996)	4,97,917	10000/-	Two month	350/-

Certificate :- It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who dose not have more than two works in hand in HPPWD Circle/ Division.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW)BJA(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.
12. The tender document shall be issued to only those contractors who submit registration of GST No.

-Se-
Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh
Tel. No. 01799-221023 Mail. ee-raj-hp@nic.in

Dated:- 03-10-2022

No.PW/RGH/Estt-Tender/2022-23-

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental wesite please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.

-Paul-
Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.

SCHEDULE OF QUANTITY

Estimated Cost: -	447159.00
Earnest Money: -	9000.00
Time: -	One months.

Name of work: Restoration of Rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- C/O PCC R/wall between Km 59/543 to 59/549)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	15.34	Per Cubic Metre.			
2	Providing and laying Plain Cement Concrete 1:2:4(one cement: Two sand: Four graded hard stone aggregate 40mm(forty millimeter nominal size) and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	20.45	Per cubic meter.			
3	Providing and laying Cement concrete 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	62.83	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	24.00	Each			

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	22.00	Per Cubic Meter.			


Executive Engineer,
Rajgarh Division
P. P. D. Rajgarh.

SCHEDULE OF QUANTITY

Estimated Cost: -	454000.00
Earnest Money: -	9000.00
Time: -	One months.

Name of work : Restoration of Rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- C/O PCC R/wall between Km 59/531 to 59/537)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	15.34	Per Cubic Metre.			
2	Providing and laying Plain Cement Concrete 1:2:4(one cement: Two sand: Four graded hard stone aggregate 40mm(forty millimeter nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	20.45	Per cubic meter.			
3	Providing and laying Cement concrete 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	62.83	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	25.00	Each			

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	21.91	Per Cubic Meter.			


 Executive Engineer,
 Rajgarh District,
 P.P. D. Rajgarh.

SCHEDULE OF QUANTITY

Estimated Cost: -	454394.00
Earnest Money: -	9000.00
Time: -	One months.

Name of work : Restoration of Rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- C/O PCC R/wall between Km 59/537 to 59/543)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	15.34	Per Cubic Metre.			
2	Providing and laying Plain Cement Concrete 1:2:4(one cement: Two sand: Four graded hard stone aggregate 40mm(forty millimeter nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	20.45	Per cubic meter.			
3	Providing and laying Cement concrete 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	62.83	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	26.00	Each			

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	22.08	Per Cubic Meter.			
---	--	-------	------------------	--	--	--


 Executive Engineer,
 Raigarh Division
 P.P. Pr D, Raigarh.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rehari Gussan to Kathli Bharan road Km 0/0 to 13/0(SH:- C/O PCC R/wall in Km. 9/990 to 9/996)

Estimated cost: - Rs.4,97,917/-
Earnest money: - Rs. 10,000/-
Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	40.71	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	92.830	Per Cubic Metre			

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	21.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	16.20	Per Cubic Metre.			


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh