

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated 19.10.2022 up to 10.30 AM and the same will be opened on the same day at 11.30 AM in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to to, 4.00 PM on dated 18.10.2022 and tender forms can be obtained from this office against cash payment (nonrefundable) on 17.10 2022 (4.00PM) and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Construction of Link Road from Ler to Than Road Km 0/0 to 1/750 (SH:- C/O Cement Concrete pavement at Rd 0/580 to 0/605, 0/780 to 0/805 & 0/870 to 0/904)	499216	10000	Three Month	350	6&8
2	Construction of Link Road Jhijjer to Magro Via Saleti Road Km 0/0 to 3/700 (SH:- C/O R/wall at Rd 0/525 to 0/540& 03/120 to 3/160) Under ScSP	498021	10000	Three Month	350	6&8
3	Construction of Link Road from Masch Khad to Kurial Khara Harijan Basti Jatoli Khatraian Jatoli Chakran Km 00 to 5/500 (Sh:- P/L 80mm Thick interlocking paver Block at Rd 0/800 to 0/896 (Under SCSP)	499170	10000	Three Month	350	6&8
4	Construction of Pucca Bhara to Lower Chalali Km 0/0 to 2/655 (SH C/O R/wall at Rd 0/660 to 0/671 & 0/937 to 0/965 (under Industrial corridor)).	466783	10000	Three Month	350	6&8
5	Construction of Health Institution Level _III Building at Dada Siba Tehsil Dada Siba Distt Kangra HP (SH Providing and fixing cup board work etc)	480297	10000	Three Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER/ 2022-23 4626-40

DATED 07/10/22

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

CERTIFICATE

Certified that tenders called vide this office Notice No
PWD/KB/CB/Tender /2022-23 -4626-40 dated 7.10.2022 for 05 Nos. Job are hereby
invited without press notice due to exigencies / emergency of work in the public interest


Executive Engineer,
Kotla Behan Division HPPWD.,
Kotla Behan

BILL OF QUANTITY

JOB No. 1

Estimate Cost :- Rs. 4,99,216/-

Earnest Money :-Rs. 10000/-

Time Limit :- Three Months.

Name of work:- Construction of Link road from Ler to Than road Km 0/0 to 1/750 (SH:- C/o Cement Concrete Pavement at RD. 0/5800 to 0/605, 0/780 to 0/805 & 0/870 to 0/902) (Under OTMNP).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	32.80 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.80 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) design mix with minimum cement contents of 404 Kg (Four hundred four Kilogram) in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	65.60 Cubic metre			Per Cubic metre	
TOTAL					


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

JOB No. 2

Estimate Cost :- Rs.4,98,021.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

Work of work:- Construction of Link road Jhijjer to Magru via Sihoti road Km. 0/0 to 3/700 (SH:- C/o Retaining wall at RD. 0/525 to 0/540 & 3/120 to 3/160) (Under SCSP).

BILL OF QUANTITY

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	77.55 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 300, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	142.10 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, SST, toll tax, sale tax or any other taxes imposed by the Government.	8.55 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	52.00 Number			Each	
TOTAL					


 Executive Engineer,
 Kotla Behar Division,
 PWD Kotla Behar.

JOB No. 3

Estimate Cost :- Rs.4,99,170.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

BILL OF QUANTITY

me of work:- Construction of link road from Maseh Khad to Kurial Khara Harijan Basti Jatoli Khatrain Jatoli Chakran Km. 0/0 to 5/500 (SH:- P/L 80mm Thick Interlocking Paver Block at RD. 0/800 to 0/896) (Under SCSP).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation for all type of road structure such as Retaining walls, Breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603 as per direction and entire satisfaction of Engineer-in-Charge, including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface is layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth any quantum of water including cleaning of slush which may arise out during dewatering as per direction and entire satisfaction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	58.37 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	7.68 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	30.72 Cubic metre			Per Cubic metre	
Providing and laying of inter locking concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 80mm (eighty millimeter) Grade M-40 IS Code-15658:2006 and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government	307.20 Square metre			Per square metre	
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

JOB No. 4

Estimate Cost :- Rs.4,66,783.00

Earnest Money :-Rs. 10000.00

Time Limit :- Three Month.

BILL OF QUANTITY

one of work:- Construction of Pucca Bharoo to Lower Chalali Km. 0/0 to 2/655 (SH:- C/o Retaining wall at RD. 0/660 to 0/671 & 0/937 to 0/965) (Under Industrial Corridor).

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiselling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	61.90 Cubic metre			Per Cubic metre	
Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	129.06 Cubic metre			Per cubic metre	
Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	29.40 Cubic metre			Per Cubic metre	
Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,708,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	33.00 Number			Each	
TOTAL					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

Job No 5

Estimate Cost :- Rs. 4,80,297/-
 Earnest Money :-Rs. 10000/-
 Time Limit :-Three Months.

BILL OF QUANTITY

Name of work:- Construcion of Health Institution Level-III Building at Dadasiba, Tehsil Dadasiba, Distt. Kangra HP (SH:- Providing and fixing Cupboard work Etcetra)

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Providing and Fixing Cabinet work made of 19 mm (Nineteen milimetre) thick water proof termite proof commercial board with shutters of 19 mm (Nineteen milimetre) thick commercial board including fixing with nickle plated piano hinges with screws etc. complete as per HPPWD specifications or as per the directions of the Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	47.26			Per Square Metre	
Providing and fixing oxidized 100x10 mm (One Hundred into ten milimetre) MS (Mild steel) Tower Bolts (Barrel type) with the necessary screws etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage or materials within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	158.00			Number	
Providing and laying mechanically mixed and vibrated reinforced concrete work Grade M-20 (M-twenty) design mix to obtain the minimum compressive strength of 20 N/mm2 (twenty newton) per square millimeter with minimum cement content of 320 Kg (Three hundred twenty) Kilogramme per cubic meter and curing complete including the cost of form work and reinforcement for reinforced concrete work in String courses, copings, bed plates, anchor blocks, plain windows sills and the like complete as per HPPWD specifications or as directed Dy the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.99			Per Cubic Metre	


 Executive Engineer,
 Kotla Behar Division ,
 HPPWD Kotla Behar.