

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-NHD-GA-TENDER/2022-23

6366-68

Dated:

13-10-2022

To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla-2

Subject:-

Publication of Notice Inviting Tenders.

Dear Sir,

Enclosed please find herewith the tender Notice for work as given in the Notice inviting Tender for Uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of HP letter No. PBW(BA9(3)1/2020 dated Shimla-2 16th July 2021. The works mentioned in the tender notice are of urgent nature and in public interest being restoration of rain damages during the monsoon season on various National Highways which has been blocked/ hindered due to heavy rains.

Amal Chh
Executive Engineer,
National Highway Division,
HP,PWD Hamirpur.

Copy to the Superintending Engineer National Highway Circle HPPWD
Shahpur for information please.

Copy to Computer Cell O/O Executive Engineer (IT Cell), Nigam Vihar
Shimla-2 for information and necessary action please.

Executive Engineer,
National Highway Division,
HP,PWD Hamirpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by **Executive Engineer, NH Division, HPPWD, Hamirpur (H.P)** from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on or before **22-10-2022 upto 11.00 A.M** and shall be opened on the same day at **11:30 A.M.** in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received upto **20-10-2022 upto 4:00 P.M.** on cash payment (Non-Refundable) and tender document will be issued on **21-10-2022 upto 5:00 P.M.** If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

SN	Name of work	Estimated cost	Earnest money	Time allowed	Cost of form	Form No
1	A/R & M/O on NH-70 (New NH-03) km. 58/400 to 114/0 (SH:-Construction of R/ wall at RD. 94/472 to 94/483 (L.H.S)	498235.00	10000.00	Two Months	350/-	6&8
2	A/R & M/O on NH-70 (New NH-03) km. 58/400 to 114/0 (SH:-Dressing of berms in km. 85/0 to 100/0	499830.00	10000.00	Two Months	350/-	6&8
3	A/R & M/O on NH-503 (Extn). Between Km. 0/0 to 19/0 (SH:-Dressing of Berms in km. 2/0 to 19/0	320100.00	6500.00	One Months	350/-	6&8
4	A/R & M/O on NH-503 (Extn). road Km. 0/0 to 19/0 (SH:-Providing and laying hard shouldering at Various stretches from Km. 0/0 to 7/500)	497948.00	10000.00	Two Months	350/-	6&8
5	A/R & M/O on NH-503 (Extn). at Km. 19/0 to 44/700 (SH:-Construction of U-shape drain fully covered with RCC covers in Km. 41/025 to 41/120 (LHS)	486677.00	10000.00	Two Months	350/-	6&8

Draft notice inviting/ specification special conditions can be seen in this office on any working day between **11:00 AM to 4:00 PM** ambiguous/ Telegraphic conditional tenders by fax shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. All the application must accompanied with the Earnest Money in the shape of call at deposit/ N.S.C. purchased from any post office in H.P/FDR from any nationalized bank duly pledged in favour of Executive Engineer. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: - The following document are required to be attached with the application:-

- 1 A copy of valid enlistment and renewal certificate.
- 2 A copy of GST
- 3 Any other information as desired by the Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found

eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false at any stage the tender is liable to be rejected and action taken against contractor/ firm.

4 Copy of Pan Card.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

NO.PW-NHD-HMR-GA-TENDER/2022-23
COPY FORWARDED TO THE FOLOWING:

6335-65



DATED: - 13-10-2022

- 1 The Engineer-in-Chief, HPPWD, Shimla-I
- 2 The Chief Engineer (NH), HPPWD, Shimla-I.
- 3 All the Superintending Engineer, NH /B&R in HP.
- 4 The D.C Hamirpur District Kangra at Dharamshala.
- 5 The D.C Hamirpur District Hamirpur.
- 6 All the Executive Engineer, NH/B&R in HP.
- 7 The Sub-Divisional Officer (Civil) Hamirpur. Hamirpur District Hamirpur .
- 8 All the Assistant Engineer, NH/B&R in HP.
- 9 The B.D.O. Hamirpur District Hamirpur.
- 10 The Executive Officer, Muncipal Committee Hamirpur
- 11 Secretary Zila Parishad Hamirpur
- 12 All the Contractors/ Suppliers working under HPPWD Hamirpur.
- 13 All the Head of Branches of this office.
- 14 Notice Board

Amir Ghal
Executive Engineer,
NH Division, HPPWD
Hamirpur.

Certificate

Certified that the tenders called vide this office letter No. NO.PW-NHD-HMR-GA-TENDER/2022-23-6335-65 DATED: - 13-10-2022 are of emergent/ urgent nature and in public interest being restoration of rain damages on various National Highways falls under the jurisdiction of this division during the monsoon season.


Executive Engineer,
NH Division, HPPWD
Hamirpur. 

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 498235.00
 Earnest Money:- Rs. 10000.00
 Time: - Two months

Name of work :- A/R & M/O on NH-70 (New NH-03) km. 58/400 to 114/0 (SH:-Construction of R/ wall at RD. 94/472 to 94/483 (L.H.S))

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimeter) compacted thickness including shoring and structting and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges.	62.59			Per Cubic meter	
2	Providing and laying, mechanically mixed & vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregates 20mm (Twenty millimeter) noninal size) including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge.	114.52			Per Cubic meter	
3	Providing weep holes in brick masonry/ plain /reinforced concrete abutment wing wall/ return wall etc.with 100mm dia (One Hundred Millimeters) PVC pipe extended through the full width of the structure with slope of 1(V) 20H towards drainage face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge.	32.00			Each	
4	Back filling with granular material wing walls, return walls and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals charges.	19.80			Per Cubic meter	
	G. Total					

Amul
 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

Job No- 2

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 499830.00
Earnest Money:- Rs. 10000.00
Time: - One Month

Name of work :- A/R & M/O on NH-70 (New NH-03) km. 58/400 to 114/0 (SH):-Dressing of berms in km. 85/0 to 100/0

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Making up loose of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification clause 1903 including entire carriage of material within all leads and lifts as per directions of Engineer-in-Charge and other incidental charges.	16661.00			Per square meter	
	G. Total					

Amr Chell

Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

Job No- 3

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 320100.00
 Earnest Money:- Rs. 10000.00
 Time: - One Month

Name of work :- A/R & M/O on NH-503 (Extn). Between Km. 0/0 to 19/0 (SH:-Dressing of Berms in km. 2/0 to 19/0

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Making up loose of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification clause 1903 including entire carriage of material within all leads and lifts as per directions of Engineer-in-Charge and other incidental charges.	10670.00			Per square meter	
	G. Total					



Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 497948.00
 Earnest Money:- Rs. 10000.00
 Time: - Two months

Name of work :-A/R & M/O on NH-503 (Extn). road Km. 0/0 to 19/0 (SH:-Providing and laying hard shouldering at Various stretches from Km. 0/0 to 7/500)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimeter) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges.	40.50			Per Cubic meter	
2	Providing and laying, mechanically mixed & vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregates 20mm (Twenty millimeter) nominal size) including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge.	40.50			Per Cubic meter	
3	P/L of interlocking concrete block pavements having thickness of 80mm as per drawings and technical specifications clause 1504. including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge.	270.00			Per square meter	
	G. Total					

Amr Lal
 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

Job No = 5

SCHEDULE OF QUANTITY

Estimated Cost:- Rs.
Earnest Money:- Rs.

486677.00
10000.00

Name of work :- A/R & M/O on NH-503 (Extn). at Km. 19/0 to 44/700 (SH:-Construction of U-shape drain fully covered with RCC covers in Km. 41/025 to 41/120 (LHS)
Time: - Two Months

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rock (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimeter) compacted thickness including shoring and structuring and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges.	109.73			Per Cubic meter	
2	Providing and laying, mechanically mixed & vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregates 20mm (Twenty millimeter) nominal size) including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge.	46.55			Per Cubic meter	
3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications clause 802, 804,805,806, 807, 1202 and 1204 RCC M-25(1:1.5:3) (One cement : One point five sand : three aggregate) all carriage of material in all leads and lifts & as per direction of Engineer in charge.	15.18			Per Cubic meter	
4	Supplying, fitting and placing TMT bar reinforcement (Fe 415) in substructure complete as per drawings and technical specifications Clauses 1002, 1005,1010 & 1202 including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-Charge.	2.20			Per Metric Tonne	
	G. Total					

Are over

Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)